SECTION 02050 – PROVISIONAL

DEMOLITION

Provisional Specification Summary:

3.1.04 – Add text as shown below.
3.2.03 – Update text as shown below.

(Update text as shown.)

3.1.04 Interruption of Services.

A. *Demolish and remove all necessary structures and equipment in accordance with the Contract Documents. Only one (1) clarifier will be out of service at any given time, leaving the other clarifiers fully operable, unless the Owner's operation and/or maintenance staff elect to shut down any other clarifier(s) not under current rework by the Contractor. All demolition and equipment replacement shall be completed in each clarifier before the Contractor proceeds to begin demolition in the next clarifier.*

B. *Obtain approval from the Owner prior to interrupting service to any clarifier. ALL service interruptions shall be scheduled at times and conditions acceptable to the Owner. Refer to Section 01030, Summary of Work.*

3.2.03 Salvage. Delete the entire sentence*" Salvage Fire Hydrants….. with Construction." Replace with the following:*

A. *Materials, equipment and appurtenances removed, that are not designated for relocation, shall become the property of Contractor and shall be hauled from site and disposed of at no additional cost to the Owner.*

B. *Material salvaged from this work shall not be reused, except, where reuse is specifically indicated in the Contract Documents, or when the equipment is to be turned over to the Owner for reuse.*

C. *Store equipment to be salvaged for relocation where directed by Engineer, and protect from the elements and damage during work. Other materials, equipment and appurtenances removed and designated for salvage by the Owner shall also be stored where directed by the Engineer.*

End of Provisional Section