SECTION 15067 – PROVISIONAL

MISCELLANEOUS PLASTIC PIPE, TUBING AND ACCESSORIES

Provisional Specification Summary:

1.3.01	*Update text as shown*
2.1.01	*Update text as shown*
2.1.02	*Delete text as shown*
3.1	*Replace text as shown*
3.2	*Replace text as shown*
3.2.02	*Delete text as shown*
3.3	*Replace text as shown*

(Update text as shown.)

1.3.01 Drawings and Date. Delete: "Chemical Resistant waste pipe and fittings, Expansion joint, Flange gaskets, FRP double wall pipe and fittings, Gas pipe and fittings, Pipe sleeves, CPVC pipe and fittings, and PVDF pipe and fittings."

1.3.01 Drawings and Data. Add "Heavy-Duty Polyethylene pipe and fittings".

2.1.01 Pipe Materials. Replace the paragraph with "Miscellaneous plastic pipe materials shall be for the services as indicated in the project drawings".

Delete the following Material Classifications and associated Pipe and Fittings and Flanges sections: "FRP-1, PVC-1, PVC-3, PVC-4, PVC-5, PVC-6, PVC-7, CPVC-1, PE-1, PE-2, PE-3, PE-4, PE-5, PE-6, PP-1, PP-2, PP-3, PVDF-1, PVDF-2, PVDF-3, PVDF-4, and RPT-1". **Delete complete sections.**

2.1.01 Pipe Materials. Add the following:

Material Classification	HDPE
Pipe	ASTM D3350, cell classification 423410C. Perforated. ASTM F667, "ADS single wall heavy duty polyethylene, ASTM 1248 Type III, Class C, Category 4, Grade P33 or Engineer Approved equivalent.

Provisional Specifications—which are issued separately from the Master Specifications on a per contract basis—shall supersede and govern over all other specifications or contract documents. All other wording in the Master Specifications that is not specifically stated to be modified in the Provisional Specifications shall remain in effect as is. The Provisional Specification Summary is included to clarify and/or highlight changes.

Fittings	ASTM F405 or ASTM F667, cell classification same as for pipe.
Drain Envelope	ADS Sock – Equivalent Opening Size 30 to 40, Knitted polyester, Burst strength 100 to 135 pounds per square inch) or Engineer Approved Equivalent.

2.1.02 Accessory Materials. Delete the following Materials Classifications and related information: “FRP-1, CPVC-1, and PE-1 through PE-6.” **Delete complete sections**.

3.1 Installation. Replace the paragraph with: “Materials furnished under this section shall be installed in accordance with the Project Drawings”.

3.2 Leakage and Pressure Tests. Replace the paragraph with: “After installation PVC piping shall be subjected to a leakage and pressure test”. Note: PVC piping may be pressure tested prior to connection with HDPE pipe.

3.2.02 Pressure and Leakage Test. Delete paragraph.

3.3 SCHEDULE. Replace the paragraph with: “Miscellaneous Plastic Pipe, Tubing and Accessories shall be as indicated in the Pipe and Accessories Quantities table as indicated in the project drawings”.

End of Provisional Section

Provisional Specifications—which are issued separately from the Master Specifications on a per contract basis—shall supersede and govern over all other specifications or contract documents. All other wording in the Master Specifications that is not specifically stated to be modified in the Provisional Specifications shall remain in effect as is. The Provisional Specification Summary is included to clarify and/or highlight changes.