SECTION 11050 – PROVISIONAL

EQUIPMENT GENERAL PROVISIONS

Provisional Specification Summary:

1.1 – Delete text as shown.
1.2.02 – Update text as shown.
1.11 – Update text as shown.
2.4 – Update text as shown.
3.1.01 – Delete text as shown.
3.1.06 - Delete text as shown.
3.1.09 – Delete text as shown.
3.3.02 – Delete text as shown.

(Update text as shown.)

1.1 SCOPE. Delete the entire sentence "Additional requirements for pumps are addressed in Master Specification Section 11100, Pump Applications General Requirements."

1.2.02 General Equipment Stipulations. Delete the entire sentence "Motors shall be as specified in Master Specification Section 16220, General Purpose Induction Motors – Procurement, unless indicated otherwise."

1.11 WARRANTIES. Modify the last sentence "Submit special warranties for the products so specified elsewhere in Division 11 of the Specifications."

2.4 PAINTING. Modify the first sentence "Equipment and identification shall be painted except for stainless steel or machined surface in accordance with Specification Section 09900, Painting, unless indicated otherwise."

Delete the following sentence "All exterior cast iron and or steel surfaces shall be given two shop coats of Amerlock 400 or approved equal."

Delete the entire third paragraph beginning with "All cast iron and steel surfaces which….."

3.1.01 Building Openings for Admission of Equipment. Delete the entire section.

3.1.06 Lines and Grades. Delete the entire paragraph "Axis lines within building shall be so spaced on each floor level that work may be laid out with metal tape measure having length of 100 feet (30.5 m) maximum. The use of cloth tape for layout will not be permitted."

3.1.09 Access Panels and Doors. Delete the entire section.

3.3.02 Tests. Delete paragraphs two, three and four, beginning with “All pumps 4 inches (10.2 cm) ….” and ending with “manufacturer’s curves for flow and horsepower.”

End of Provisional Section