SECTION 02145 – PROVISIONAL

CLARIFIER DEWATERING

Provisional Specification Summary:

Title	*Revise section title to "Clarifier Dewatering".*
1.1	*Replace text as shown.*
3.1	*Replace text as shown.*
3.2	*Delete text as shown.*
3.3	*Delete text as indicated.*
3.4	*Delete text as indicated.*
3.5	*Delete text as indicated.*
3.6	*Delete text as indicated*

(Update text as shown.)

1.1 SCOPE. Replace the paragraph with: "The Contractor shall furnish all labor, supervision, materials, tools, equipment and incidentals specified and required to complete the dewatering of the clarifier contents of the clarifiers as needed to proceed with the Work. Contractor shall pump the clarifier contents to a location on site as directed by the Engineer."

3.1 WET WELL CLEANING. Change the heading to "Clarifier Dewatering" and replace the first paragraph with: "The Owner will isolate the gates and dewater each clarifier down to the center area only and then turn it over to the Contractor. It will then be the contractor's responsibility to complete the dewatering and keep water out of the clarifiers during construction."

Delete the second, third, fourth and fifth paragraphs and replace them with: "Dewatering of the clarifiers shall be conducted by workmen certified in confined space entry and experienced in such work. All necessary equipment and materials, including pumps, piping, and hosing shall be provided by the Contractor.

3.2 REMOVAL OF WET WELL CONTENTS. Delete this entire paragraph.
3.3 SLUDGE TRANSPORTATION. Delete this entire paragraph.
3.4 SLUDGE/GRIT DISPOSAL. Delete this entire paragraph.
3.5 CLEANUP AND RESTORATION. Delete this entire paragraph.
3.6 INSPECTION. Delete this entire paragraph.

End of Provisional Section

Provisional Specifications—which are issued separately from the Master Specifications on a per contract basis—shall supersede and govern over all other specifications or contract documents. All other wording in the Master Specifications that is not specifically stated to be modified in the Provisional Specifications shall remain in effect as is. The Provisional Specification Summary is included to clarify and/or highlight changes.