SECTION 01040 – PROVISIONAL

CONTROL OF WORK

Provisional Specification Summary:

1.2.03 – Add section as indicated below.
1.2.04 – Add section as indicated below.

1.2.03 General Requirements.

The Contractor shall:

1. Develop a program, in cooperation with the Engineer to provide for the construction and putting into service the new work in the most orderly manner possible and in coordination with other construction projects;

2. Adhere to such program except as deviations therefrom are expressly permitted by the Engineer;

3. Plan all work of connecting with, cutting into, and reconstructing existing pipes or structures so as to interfere with the operation and maintenance of the existing facilities for the shortest possible time and when the demands on the facilities best permit such interference, even though it may be necessary to work outside of normal working hours to meet these requirements;

4. Make minor modifications in such work relating to existing structures as may be necessary, without additional compensation;

5. Before starting any work which will interfere with the operation of the existing facilities, do all possible preparatory work and shall see that all tools, materials, and equipment to be installed are made ready and at hand;

6. Conduct his operations so as to (a) interfere as little as possible with existing treatment works and other construction contracts, and (b) not damage existing equipment, structures, etc., or cause disruption of plant operations;

7. Make no claim for additional compensation by reason of delay or inconvenience in adapting his operations to the need for continuous primary treatment at the existing plant; and

8. Begin no work related to interference with, or connections to existing facilities necessary for continued plant operations until such schedule is accepted and approved by the Engineer.

1.2.04 Particular Requirements

The Contractor shall:

1. Be restricted to work on not more than one (1) clarifier at one time;

2. Substantially complete all required tank construction, performance testing and cleaning activities on each tank before the release of another clarifier by the Engineer;

3. Substantial Completions and Final Completion of the Work shall be achieved within the times appearing under Article 8, *Time,* of the *FORM OF AGREEMENT FOR CONTRACT NO. PC-756,* contained in Book 1 of 3 of the Contract Documents;

4. Before starting any on-site construction activity on any clarifier, drain and clean the clarifier. DWSD will isolate the gates, partially dewater each clarifier down to the center area only and then turn it over to the Contractor. It will be the Contractor's responsibility to complete the dewatering and cleaning and to keep water out of the clarifier during construction.

5. Refill each such respective clarifier per the direction of Engineer.

6. Submit a written notice to the Engineer upon substantial completion of the required Work for each such respective clarifier, including but not limited to:

   a. the completion of all required construction Work,

   b. the completion of all required performance testing and final adjusting of the new equipment, etc., and

   c. the completion of all required clarifier and corresponding temporary work site area restorations and cleanings;

   Such notice shall also request the Engineer's permission to proceed with similar Work on the next designated or assigned clarifier;

7. Upon the Engineer's acceptance in writing of such notice, immediately proceed with the required Work on next clarifier as indicated.

End of Provisional Section