SECTION 03700 – PROVISIONAL

CONCRETE RESTORATION

Provisional Specification Summary:

2.1.02	*Delete section as shown*
2.1.03	*Add section as shown*
2.1.04	*Delete section as shown*
3.1.01	*Update section as shown*
3.2.04	*Add text as shown*

(Update text as shown.)

2.1.02 Shotcrete. Delete the entire section

2.1.03 Gravity Feed Grout. Add the section: The contractor shall use Sika "Sikadur 35 Hi-Mod LV" for gravity feed applications as indicated in the Specifications. Prepare area and install grout as per manufacturer's recommendations.

2.1.04 Metallic Aggregate Epoxy Repair Mortar. Delete the entire section.

3.1.01 Spall and Crack Repair. Delete the entire second paragraph beginning with: Entry ports shall be provided along the crack….."

Add sentence to section. Route or saw cut cracks identified by the Engineer for repair.

3.2.04 Gravity Feed Grout. Add the section: Pour neat Sikadur 35, Hi-Mod LV into vee-notched crack as indicated in Project Drawings. Continue placement until completely filled.

END OF PROVISIONAL SECTION

Provisional Specifications—which are issued separately from the Master Specifications on a per contract basis—shall supersede and govern over all other specifications or contract documents. All other wording in the Master Specifications that is not specifically stated to be modified in the Provisional Specifications shall remain in effect as is. The Provisional Specification Summary is included to clarify and/or highlight changes.