SECTION 03250 – PROVISIONAL

CONCRETE ACCESSORIES

Provisional Specification Summary:
2.1.03 Replace text as indicated
3.3.03 Replace text as indicated
3.3.04 Delete text as indicated

(Update text as shown.)

2.1.03 Waterstops. Replace the paragraph with: "Shall be of the size and type indicated on the Plans consisting of active bentonite/butyl-rubber based waterstop."

3.3.03 Waterstops. Replace the third and forth paragraphs with: "Tightly butt coil ends together to form a continuous waterstop – do not overlap coil ends. Where required, cut coils with a sharp knife or utility blade to fit coil ends together. Make horizontal to vertical transitions by abutting product coil sections together, no special accessory pieces are required."

3.3.04 Slab Isolation Systems. Delete the entire second paragraph beginning with: "After installation of the isolation materials and pouring…"

End of Provisional Section

Provisional Specifications—which are issued separately from the Master Specifications on a per contract basis—shall supersede and govern over all other specifications or contract documents. All other wording in the Master Specifications that is not specifically stated to be modified in the Provisional Specifications shall remain in effect as is. The Provisional Specification Summary is included to clarify and/or highlight changes.