SECTION 03300 – PROVISIONAL

CAST-IN-PLACE CONCRETE

Provisional Specification Summary:

1.2.01	*Replace text as indicated*
1.4.04	*Replace text as indicated*
2.1.02	Add text as indicated
2.2.10	*Replace text as indicated*
2.2.17	*Add text as indicated.*

(Update text as shown.)

1.2.01 Governing Standards. Replace the following standard: ACI 318, "Building Code Requirements for Structural Concrete and Commentary." with ACI 350-01, "Code Requirements for Environmental Engineering Concrete Structures and Commentary (ACI 350R-01)."

1.4.04 Test Reports. Replace the first paragraph with: "Engage a testing agency acceptable to Engineer to perform material evaluation tests and to design concrete mixes."

2.1.02 Reinforcement Materials. Add the following sentence to the end of section: "Reinforcement anchors shall be installed as indicated on the Contract Drawings."

2.2.10 Water Stops. Replace the last paragraph with: "Hydrophilic water strop shall be Volclay "Waterstop – RX" bentonite/butyl rubber based or Engineer approved equivalent with adhesive as recommended by the manufacturer.

2.2.17 Epoxy Bonding Agent. Add the following section to paragraph: "Hilti HYT 150 Adhesive or Engineer approved equivalent."

End of Provisional Section