## SECTION 01110 – PROVISIONAL

## CONSTRUCTION FACILITIES AND IDENTIFICATION

***Provisional Specification Summary:***
*1.3.02 – Replace subsection as shown below.*
.

***(Update text as shown.)***

1.3.02 Furnishing. Each workspace shall have a 30”x60” desk, two desk chairs, telephone, file drawer, one fax machine at least one duplex outlet, and lighting that is functional and in good condition. The project engineer and superintendent offices shall each have a 36”x42” drafting table, one plan rack (minimum capacity eight plan sets), one first aid kit, one 10A: 80 – B:C fire extinguisher, and an automatic controlled HVAC system. The conference room shall include a conference table and chairs to seat all attendees at recurring meetings.

The contractor shall furnish and maintain bottled water and sanitary facilities for the field office. The contractor shall clean the office at least once per week. The contractor shall provide and pay for all utility service throughout the duration of the Project, including local telephone service and long distance telephone service.

A trailer having equal facilities and floor space may be used in place of the described field office if so desired.

The field office shall be furnished with a minimum of an aggregate surfaced driveway and parking area, for the exclusive use of the engineer, for at least (3) vehicles. Contractor shall maintain parking area including snow removal.

The cost for furnishing and installing the field office, for furnishing utilities and utility service, and for maintenance of the field office and facilities, unless otherwise specified in the proposal, will not be paid for separately but shall be included in the price bid for various items of work under the contract. The building shall be removed by the contractor upon completion of the contract and shall become his property.

End of Provisional Section

*Provisional Specifications—which are issued separately from the Master Specifications on a per contract basis—shall supersede and govern over all other specifications or contract documents. All other wording in the Master Specifications that is not specifically stated to be modified in the Provisional Specifications shall remain in effect as is. The Provisional Specification Summary is included to clarify and/or highlight changes.*

THIS PAGE INTENTIONALLY LEFT BLANK