

DWSD Community Meeting: Charles Wright Academy Bioretention

April 29, 2021

Agenda

- 1. Why We're Here Today
- 2. DWSD At Work
- 3. Project Overview
- 4. Impacts to You
- 5. Questions



Why We Are Here

Since 2013, in accordance with the NPDES permit, the Detroit Water and Sewerage Department (DWSD) has been pursuing Green Stormwater Infrastructure and will invest \$50 million into Green Stormwater Infrastructure (GSI) by 2029. This investment is part of the City's effort to reduce Combined Sewer Overflows (CSO) to the Rouge River.

The projects for this year include the Charles Wright Academy Bioretention.



DWSD Capital Improvement Program Update

DWSD has invested \$200M in capital improvement projects since 2019

Water main, hydrant and lead service line replacement

Sewer lining and replacement

Green Stormwater Infrastructure installations

 Condition assessments and other data are used to determine necessary upgrades

DWSD and our contractors have:

 Replaced 66 miles of water main and more than 1,155 lead service lines


- Replaced or lined 50 miles of sewer collection piping
- Installed 11 bioretention gardens
- DWSD crews also performing
 preventative maintenance tasks



Charles Wright Bioretention

- Redirect rooftop and parking lot areas to two bioretention cells
- Stormwater is infiltrated/filtered; excess flows to Rouge River
- 5.5 acres of area removed from combined sewer system
- 150,000 gallons of storage volume for water quality treatment and infiltration
- Reduces annual flows to the combined sewer system by up to 3 million gallons






Planting Examples of Grasses and Perennials

- 1 Blue Flag Iris
- 2 Butterfly Milkweed
- 3 Purple Coneflower
- 4 Prairie Sedge
- 5 Prairie Dropseed
- 6 Brown Fox Sedge





Planting Plan – South Basin





Planting Plan – North Basin





What to Expect

- These upgrades will be implemented in two phases
 - Phase 1: Excavation
 - Phase 2: Pipe Installation and Restoration
- During construction it is DWSD's intention to minimize inconveniences
- Contractors will work with the neighborhood school to ensure all safety precautions are met and normal school operations continue to function with minimal interruption





PHASE 1: Excavation

- Spring 2021
- DWSD and contractors provided advance notification of construction
- Construction can be disruptive and dirty we will take every effort to reduce impact
 - Equipment may be staged on an empty lot with owner's permission, on the right-of-way and/or in the alley
 - Tree trimming or removal may take place in order to access the pipes and other infrastructure
 - Workers will follow COVID-19 safety protocols





PHASE 2: Pipe Installation & Restoration

- Summer Fall 2021
- Construction will continue to be disruptive we will take every effort to reduce impact
- There may be traffic impediments, but the neighborhood will be accessible
- There may be sidewalk closures and impacts to street parking
- Property restoration, such as lawns, sidewalks, driveways and fences occur after construction, as weather permits and between April – October





Next Steps

- Construction begins mid-May
- Check Nextdoor for project updates
- Email questions or concerns to dwsd-publicaffairs@detroitmi.gov





Questions?



Detroit Water & Sewerage Department

Email: DWSD-publicaffairs@detroitmi.gov

For more information visit: www.detroitmi.gov/dwsd

FOLLOW US!







