DHDC 22-7937

APPROVAL DOCUMENT - POST AT WORK LOCATION

CITY OF DETROIT HISTORIC DISTRICT COMMISSION 2 WOODWARD, SUITE 808 DETROIT, MICHIGAN 48226

1/13/2023

CERTIFICATE OF APPROPRIATENESS

Diane Van Buren 3030 Seminole Detroit, MI

RE: Application Number #22-7937; 3030 Seminole; Indian Village Historic District Project Scope: ERECT ONE-STORY REAR ADDITION TO INCLUDE INTEGRATION OF EXISTING REAR PORCH

Dear Ms. Van Buren,

At the Regular Meeting that was held on 8/10/2022, the Detroit Historic District Commission ("DHDC") reviewed the above-referenced application. Pursuant to Section 5(1) of the Michigan Local Historic District Act, as amended, being MCL 399.205 (1) and Sections 21-2-73/21-2-78 of the 2019 Detroit City Code; the DHDC hereby issues a Certificate of Appropriateness ("COA") for the following work, effective on 1/13/2023, as it meets the Secretary of Interior's Standards for Rehabilitation and the district's Elements of Design:

Per the attached drawings

- Retain the existing brick priers and vertical heavy timber columns at the remains of the historic rear porch
- Integrate the existing timber capitals per drawing note # 11 which states that 2 of the three layers will be removed and the outermost ply will be left/retained to allow for new windows be recessed behind
- Infill openings of existing brick priers and vertical heavy timber columns with new brick, stucco, aluminum-clad wood windows, and a door per the submitted drawings. A railing will be installed at the perimeter of the roof
- Erect a flat and shed-roof, one-story addition at the building's rear elevation, adjacent to the porch per the submitted drawings. Exterior walls will be clad with brick and windows will be aluminum-clad wood units.

This COA has been issued with the following conditions:

• HDC staff shall be afforded the opportunity to review and approve the final construction drawings for the project; the final drawings must be dimensioned and provide details regarding the height, material, and style of the rooftop railing and the manner in which the new windows, doors, stucco, and brick infill will be integrated with the existing structure.


• The existing brackets shall be retained, at least in part, such that the existing fenestration on the porch be retained. Should HDC staff determine that any aspect of the final drawings does not meet the Secretary of the Interior's Standards, the project will be forwarded to the Commission for review at a monthly meeting.

Please retain this COA for your files and post it at the subject property until work is complete. It is important to note that approval by the DHDC does not waive the applicant's responsibility to comply with any other applicable ordinances or statutes. If you have any questions regarding the foregoing, please contact staff at 313-224-1762 or hdc@detroitmi.gov.

For the Commission:



Detroit Historic District Commission



ARCHITECT:

4545 architectu

3011 W. GRAND BLVD STE 400 DETROIT, MI 48208 P. 248.320.6098 TIM.FLINTOFF@4545ARCHITECTURE.COM

CONSULTANT:

ELEVATION KEY NOTES:

(TYPICAL THIS SHEET ONLY)

- 1 NEW WOOD WINDOW.
 MANUFACTURER: MARVIN
 EXTERIOR: BRONZE CLAD
 INTERIOR: LEATHER STAINED PINE
- NEW MASONRY WALL. 4" FACE BRICK WITH 1" AIR GAP ON $\frac{1}{2}$ " INSULATED VAPOR BARRIER ON 2x6 WOOD STUD WALL WITH MIN. R-19 FIBERGLASS BATT INSULATION ON $\frac{5}{8}$ " GYP., PAINTED (COLOR TBD)
- $\fbox{3}$ POURED IN PLACE CONCRETE STEPS. MAX. 12" TREAD, MAX. 7" RISER
- 4 METAL WALL CAP/COPING. 2-PIECE, 4" HIGH ON 2X NAILER. DARK BRONZE COLOR.
- LIMESTONE OR CAST STONE SILL, 4" THICK x WIDTH OF WINDOW OPENING + 3" DOG EAR
- 6 WOOD DOOR WITH FULL LITE GLASS. INSULATED.
 MANUFACTURER: MARVIN
 EXTERIOR: BRONZE CLAD SASH
 INTERIOR: LEATHER STAINED PINE
- 7 DECORATIVE STEEL HANDRAIL/GUARD. MIN. 44" ABOVE ABOVE ROOF, MAX. PICKET SPACING 4" O.C. COLOR: BLACK
- $raket{8}$ REPLICATE EXISTING TIMBER FRAMING, SEE SECTIONS
- STUCCO WITH SCRATCH COAT ON 2X BLOCKING WITH PLYWOOD SHEATHING WITH $\frac{1}{2}$ " INSULATED VAPOR BARRIER ON 2x6 WOOD STUD WALL WITH MIN. R-19 FIBERGLASS BATT INSULATION ON $\frac{5}{8}$ " GYP.
- $\stackrel{\Large \frown}{10}$ STANDING SEAM METAL ROOF WITH WATER AND ICE BARRIER ON 3_4 " PLYWOOD SHEATHING ON 2X6 WOOD JOISTS
- EXISTING DECORATIVE WOOD FRAMING TO BE SALVAGED AND REINSTALLED. REMOVE 2 OUT OF 3 WOOD LAYERS, LEAVE EXTERIOR MOST PLY INTACT TO ALLOW WINDOW TO RECESS BEHIND.
- $\overline{\langle 12 \rangle}$ EXISTING WOOD POSTS TO REMAIN
- (13) EXISTING BRICK PIERS TO REMAIN


Project :

3030 SEMINOLE ADDITION

3030 SEMINOLE ST. DETROIT, MI 48214

Issued for :

PERMITS REV. 1/10/2023



Drawn by :

Check by:

Sheet Title : EXTERIOR ELEVATIONS

Project No. : **2022033**

Sheet No. :

A3.1



ARCHITECT:

4545 architectu

3011 W. GRAND BLVD STE 400 DETROIT, MI 48208 P. 248.320.6098 TIM.FLINTOFF@4545ARCHITECTURE.COM

CONSULTANT:

ELEVATION KEY NOTES:

(TYPICAL THIS SHEET ONLY)

- 1 NEW WOOD WINDOW.
 MANUFACTURER: MARVIN
 EXTERIOR: BRONZE CLAD
 INTERIOR: LEATHER STAINED PINE
- NEW MASONRY WALL. 4" FACE BRICK WITH 1" AIR GAP ON $\frac{1}{2}$ " INSULATED VAPOR BARRIER ON 2x6 WOOD STUD WALL WITH MIN. R-19 FIBERGLASS BATT INSULATION ON $\frac{5}{8}$ " GYP., PAINTED (COLOR TBD)
- igg(3igg) POURED IN PLACE CONCRETE STEPS. MAX. 12" TREAD, MAX. 7" RISER
- 4 METAL WALL CAP/COPING. 2-PIECE, 4" HIGH ON 2X NAILER. DARK BRONZE COLOR.
- 5 LIMESTONE OR CAST STONE SILL, 4" THICK x WIDTH OF WINDOW OPENING + 3" DOG EAR
- 6 WOOD DOOR WITH FULL LITE GLASS. INSULATED.
 MANUFACTURER: MARVIN
 EXTERIOR: BRONZE CLAD SASH
 INTERIOR: LEATHER STAINED PINE
- DECORATIVE STEEL HANDRAIL/GUARD. MIN. 44" ABOVE ABOVE ROOF, MAX. PICKET SPACING 4" O.C. COLOR: BLACK
- 8 REPLICATE EXISTING TIMBER FRAMING, SEE SECTIONS
- STUCCO WITH SCRATCH COAT ON 2X BLOCKING WITH PLYWOOD SHEATHING WITH $\frac{1}{2}$ " INSULATED VAPOR BARRIER ON 2x6 WOOD STUD WALL WITH MIN. R-19 FIBERGLASS BATT INSULATION ON $\frac{5}{8}$ " GYP., PAINTED (COLOR TBD)
- $\fbox{10}$ STANDING SEAM METAL ROOF WITH WATER AND ICE BARRIER ON $\frac{3}{4}$ PLYWOOD SHEATHING ON 2X6 WOOD JOISTS
- EXISTING DECORATIVE WOOD FRAMING TO BE SALVAGED AND REINSTALLED. REMOVE 2 OUT OF 3 WOOD LAYERS, LEAVE EXTERIOR MOST PLY INTACT TO ALLOW WINDOW TO RECESS BEHIND.
- $\langle \overline{12} \rangle$ EXISTING WOOD POSTS TO REMAIN
- (13) EXISTING BRICK PIERS TO REMAIN


Project :

3030 SEMINOLE ADDITION

3030 SEMINOLE ST. DETROIT, MI 48214

Issued for :

PERMITS REV. 1/10/2023



Drawn by :


Check by:

Sheet Title : EXTERIOR ELEVATIONS

Project No. : 2022033

Sheet No. :

eet No. : **Δ3 2**





ARCHITECT:

4545 architecture

3011 W. GRAND BLVD STE 400 DETROIT, MI 48208 P. 248.320.6098 TIM.FLINTOFF@4545ARCHITECTURE.COM

CONSULTANT:


Project :

3030 SEMINOLE ADDITION

3030 SEMINOLE ST. DETROIT, MI 48214

Issued for :

PERMITS REV. 1/10/2023



Drawn by :


Check by:

Sheet Title : EXTERIOR ELEVATIONS

Project No. : **2022033**

Sheet No. :

A4.1



ARCHITECT:

4545 architecture

3011 W. GRAND BLVD STE 400 DETROIT, MI 48208 P. 248.320.6098 TIM.FLINTOFF@4545ARCHITECTURE.COM


CONSULTANT:

Project:
3030 SEMINOLE ADDITION

3030 SEMINOLE ST. DETROIT, MI 48214

Issued for :

PERMITS REV. 1/10/2023



Drawn by:

Check by:

Sheet Title : EXTERIOR ELEVATIONS

Project No. : 2022033

Sheet No. :

A4.2