

Terry Swafford Inc
716 Marlborough Street
Detroit, MI 48215
773-655-2951
terryswafford@gmail.com
www.swaffordbuildingworkshop.com

3333 Cambridge Estimate, 7/29/20:

Demo (lead safe) all windows, panels, gutters, electrical (except for external flood light) and haul away debris: \$800.00

Replace rotten structural posts (4 are known to be in need of replacement), then build structural framework (2 x 4 cedar, horizontals) that connect the posts and divides the sections into (3) vertical panels. L + M: \$2,200.00

Build (29) wooden-framed screen inserts, install with stops. Upper screens are aprox 20" ht, lower screens are 52". Build (14) wooden, trimmed out panels for the bottom sections, L + M: \$6,800.00


Design, fabricate, and install white metal, extended drip edge system around upper perimeter, just under the roof edge, L + M: \$700.00
Repair/ replace top frieze/ fascia behind and under gutters, L + M: \$400.00

Remove loose lead paint from porch ceiling (lead safe), lead block prime, surface fill, apply 2nd prime coat, L + M: \$700.00
Paint 2 coats Guardian Exterior, all components, L + M: \$1,800.00
Permit Fee: \$390.00


Total Estimate for This Work: \$13,790.00

Owners

By: 
Michael & Jonelle Tolhurst

 7/29/20

Contractor

By: 
Robert Terence Swafford
Terry Swafford Inc. #2101211515

