2 A400 NORTH EXTERIOR ELEVATION
SCALE: 3/16" = 1'-0"

1 A400 WEST EXTERIOR ELEVATION
SCALE: 3/16" = 1'-0"

RESTORATION WORK KEYNOTES:

1. EXISTING BRICK MORTAR JOINTS TO BE TUCKPOINT. MATCH EXISTING MORTAR COLOR
2. REMOVE AND REPLACE MORTAR WASH.
3. REPLACE BRICKS (# OF BRICKS)
4. CLEAN OUT SKY FACING JOINTS AT SILLS, SANDSTONE CORNICE BANDS AND INSTALL SEALANT.

ELEVATION LEGEND

WINDOW TYPE – SEE DETAILS ON SHEETS A410_ FOR DETAILS AND DIMENSIONAL LAYOUT

Hannah Neumann/Smith

1500 Woodward
Suite 300
Detroit, Michigan 48226
phone 313.782.4822
fax 248.352.1821
ns@neumannsmith.com

Project Name

LEAR CORPORATION

Lear Corporation
119 State Street
Detroit, Michigan 48226

Revisions

11-23-2015: Addendum 01
10-28-2015: PERMITS/BIDS
10-26-2015: Review Set
9-28-2015: Progress Set
9-09-2015: Progress Set

Date
☐ Preliminary
■ Construction
☐ Record

Drawn
JMC

Checked
JS

Do not scale
Use figured dimensions only

Approved
Approved

Bidpak Number
Bidpak Number

Job Number
2014206

Title
EXTERIOR ELEVATIONS

Sheet
A400

Drawing Name: /open/2014206_Lear 119 State Street Renovation/3D/Construction Documents/2014206_SHT/A400.dwg
Date: Nov 23, 2015 - 2:53pm Layout: 2D/1-A22x36 SHT/A400 Plotted by: JMC