

NORTH ELEVATION
"FRONT"

691 W CANFIELD



REMOVE EXISTING MOSS COVERED ASPHALT ROOF SHINGLES ON PORCH. REPLACE WITH NEW ASPHALT SHINGLES TO MATCH UPPER ROOF

REMOVE EXISTING SLIDING VINYL BASEMENT WINDOW LOWER SILL 10" AND PROVIDE NEW SINGLE HUNG VINYL EGRESS WINDOW


PROVIDE 6X6 PTW WINDOW WELL TO SUIT. REPLACE EXISTING WOOD TRIM TO MATCH.

6' METAL PICKET FENCE TO CLOSE OFF EAST SIDE YARD. GATED FOR ACCESS

GENERAL NOTE
REPAIR/REPAINT EXISTING WOOD TRIM AS REQUIRED
PAINT EXISTING COLOR

WEST ELEVATION

691 W CANFIELD



REMOVE/REPLACE 2
EXISTING BASEMENT
WINDOWS AND PLY
WOOD. NEW SLIDING

VINYL WINDOWS
TO BE INSTALLED.
WINDOW 'A' TO BE
EGRESS.

REMOVE/REINSTALL
EXISTING BRICK PAVERS
ON NEW GRANULAR
BASE

REMOVE PLYWOOD AT
DOOR AND WINDOW.
INFILL WITH EXISTING
SALVAGED BRICK
FROM THE SITE

EXISTING CONCRETE
STAIRS AND RUBBLE
STRUCTURE TO BE
STABILIZED AND REMAIN



SOUTH ELEVATION
1 OF 3

691 W CANFIELD




REMOVE PLYWOOD
AND BRICK IN OPENING
TO MATCH WITH
SALVAGED SITE BRICK

REINSTATE STONE SILL,
REMOVE WOOD LINTEL
AND REPLACE WITH
4X6 STEEL LINTEL

REMOVE EXISTING STEEL
FRAME / DOOR / PLYWOOD
PROVIDE NEW 1/3 LIGHT
STEEL DOOR ON WOOD

FRAME. MAKE GOOD
EXISTING MASONRY






REMOVE PLYWOOD AND
BRICK IN RIGHT SIDE
WINDOW TO MATCH.
EXTEND LEFT WINDOW

SILL DOWN 18" AND
PROVIDE VINYL SINGLE
HUNG WINDOW. MAKE
GOOD MASONRY OPENING

EAST ELEVATION 1 OF 2

691 W CANFIELD



REMOVE SECURITY GRILL AND PLYWOOD AT BASEMENT WINDOW. PROVIDE OPERATING VINYL WINDOW TO EXISTING OPENING

REMOVE EXISTING GLASS BLOCK WINDOW, LOWER SILL 18" AND PROVIDE NEW VINYL SINGLE HUNG WINDOW.

SUPPLY AND INSTALL NEW VINYL SINGLE HUNG WINDOW TO MATCH BESIDE. MAKE GOOD
←

691 W CANFIELD
MASONRY CHIMNEY

EAST ELEVATION
SECOND CHIMNEY
BACK



INVESTIGATE STRUCTURAL
INTEGRITY OF LEANING
CHIMNEY. DETERMINE IF
CHIMNEY HAS CRACKED
AND REMOVE BRICK
DOWN TO STONE COLLAR,
OR INTRODUCE CHIMNEY
BRACE.

EXISTING BRICK FROM
HOUSE TO BE REUSED
IF REQUIRED