Smart Roof

4071 Leslie Street Detroit, MI 48238



CONTACT US 31520 Carion Dr Warren, MI 48092

(248) 579-4272choose@smartroofus.com

ESTIMATE

Services

Residential - Contract Proposal/ Agreement

This contract is the whole document for the work described below. Description of work to be performed is to be detailed as follows:

Windows Replaced - Scope of work to be included

Remove and replace all windows Replace windows with Andersen E-Series All Windows is installed to manufacturers specifications WOOD IS REPLACED AT AN ADDITIONAL CHARGE (If we are found rated wood, sold in full links only and replaced at contractor's discretion) for normal installation The contractor shall perform an excellent clean-up and haul away all jobs of all related exterior debris. (job site will be cleaned up daily) for normal installation Labor and material included in the price Window Inspection: Still Window Type: Casement Still (original windows on the house) The windows need to be replaced due to unable to be fixed. Outer Wall Finish: Brick Interior Wall Finish: Plaster Window Location: First and second Flor Install From: Outside Project Site Hazards: No Home Alarm: No Blinds will fit back: yes Casing:NO Casing Type:NO Stops: OG 3/4 round molding Windows needing stops: all match stains to the windows finish Mullion removals: 0 Total Windows:23

TOTAL

\$63,535.34

Materials

amount

Window descriptions

E-Series Casement, 2 7/8" Frame Depth, No Flange, Cocoa Bean 2604 Exterior Frame, Cocoa Bean 2604 Exterior Sash/Panel, Pine w/Cinnamon - Stained Interior Frame, Pine w/Cinnamon - Stained Interior Sash/Panel, Unit 1: Left, Unit 2: Stationary, Unit 3: Right, Sash Set (2 Piece), Align w/Stationary Stops, Standard Hinge, Dual Pane Low-E4 SmartSun Standard Argon Fill Flat Finelight Grilles-Between-the-Glass 2 Wide, 4 High, Specified Equal Light Pattern, Cocoa Bean, w/Cocoa Bean, 5/8" Grille Bar, Ovolo Glass Stop Stainless Glass / Grille Spacer, Handle w/Cover, Bronze, Standard, High Performance Keeper, Bronze, Full, Aluminum

Wrapping: Interior Drywall Return Bead Pine / Cinnamon - Stained 7/16" X 1 5/16" Perimeter Complete Unit Extension Jambs, Factory Applied

BRZ LH HARDWARE KIT CSMT BAG W6204PKLKN2 PN:9078349

Insect Screen 1: E-Series Casement, CAX 24.375 x 51 Full Aluminum Bronze

BRZ RH HARDWARE KIT CSMT BAG W6204PKRKN2 PN:9078350

Insect Screen 1: E-Series Casement, CAX 24.375 x 51 Full Aluminum Bronze

Extension Jamb 1: CAX 73.125 x 51 Interior Drywall Return Bead 7/16" X 1 5/16" Pine Cinnamon - Stained

Complete Unit Extension Jambs Factory Applied

For all windows description please see attached documents

Materials subtotal: \$0.00

Subtotal \$63,535.34

Total \$63,535.34

We Appreciate Your Business!