DocuSign Envelope ID: 4C077C38-FA98-419B-B651-E66DE9437930



HISTORIC DISTRICT COMMISSION APPLICATION FOR WORK APPROVAL

| City of Detroit - Planning & Development Department 2 Woodward Avenue, Suite 808 | APPLICATION ID |
|---|---|
| Detroit, Michigan 48226 | HDC2024-00007 |
| PROPERTY INFORMATION | |
| ADDRESS(ES): 2490 LONGFELLOW ST | |
| HISTORIC DISTRICT: Boston-Edison | |
| SCOPE OF WORK: (Check ALL that apply) | |
| Windows/ Walls/ Painting Roof/Gutters/ Port | ch/Deck/Balcony |
| Demolition Signage New Addition Site | e Improvements dscape, trees, fences, os, etc.) |
| BRIEF PROJECT DESCRIPTION: Roof Mounted Solar Installation with 7.90 KW System. | |

APPLICANT IDENTIFICATION

| TYPE OF APPLICANT: Contractor | | | |
|--|-----------------------------|----------------|-------------------|
| NAME: Joungho Choi | COMPANY NAME: Generati | on Solar | |
| ADDRESS: 1192 E Draper Pkwy, Suite 466 | CITY: Draper | STATE: UT | ZIP: 84020 |
| PHONE: +1 (888) 985-2859 | EMAIL: mi.permitting@genera | ationsolar.net | |

I AGREE TO AND AFFIRM THE FOLLOWING:

I understand that the failure to upload all required documentation may result in extended review times for my project and/or a denied application.

| \mathbf{v} | |
|--------------|--|
| | |

X

х

I understand that the review of this application by the Historic District Commission does not waive my responsibility to comply with any other applicable ordinances including obtaining appropriate permits (building, sign, etc.) or other department approvals prior to beginning the work.

I hereby certify that the information on this application is true and correct. I certify that the proposed work is authorized by the owner of record and I have been authorized to make this application as the property owner(s) authorized agent.

DocuSigned by: Jourgho Choi

SIGNATURE

01/10/2024

DATE

NOTE: Based on the scope of work, additional documentation may be required. See www/detroitmi.gov/hdc for scope-specific requirements.

PROJECT DETAILS – TELL US ABOUT YOUR PROJECT

Instructions: Add project details using the text box in each section. If your details exceed the space provided, attach the details via the attachment icon for that section.

ePLANS PERMIT NUMBER:

(only applicable if you've already applied for permits through ePLANS)

N/A

GENERAL

| 1. | DESCRIPTION OF EXISTING CONDITION | | |
|------|--|--------------|--|
| | Please tell us about the current appearance and conditions of the areas you want to change. You may use a few sentences or | | |
| | attach a separate prepared document on the right. (For example, "existing roof on my garage is covered in gray aspha in poor condition.") | alt shingles | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| 2. | PHOTOGRAPHS | | |
| ۷. | Help us understand your project. Please attach photographs of all areas where work is proposed. | | |
| | | | |
| | | | |
| 3. | DESCRIPTION OF PROJECT | | |
| | In this box, tell us about what you want to do at the areas described above in box #1. (For example, Install new aspha roofing at garage.) | lt shingle | |
| | | | |
| Roc | of Mounted Solar Project with 7.90 KW System. | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| 4. | DETAILED SCOPE OF WORK | | |
| | In this box, please describe all steps necessary to complete the work described in box #3. (For example, "remove exis shingles, replace wood deck as necessary, replace wood eaves, install roof vents, replace rotted fascia boards, paint, | | |
| | worksite.") | cican | |
| SYS | STEM SIZE: 7.90 kW-DC 5.80 kW-AC | | |
| | DULE: (20) CS3U- 395W | | |
| | /ERTER: (20) ENPHASE IQ8+-72-2-US | | |
| IINV | LRTER. (20) ENFLASE IQUT-12-2-03 | | |
| | | | |
| | | | |
| | | \square | |
| | | 0// | |
| | | | |
| | | | |
| 5. | BROCHURES/CUT SHEETS | | |

Please provide information on the products or materials you are proposing to install. For example, a brochure on the brand and color of the shingles proposed.

ADDITIONAL DETAILS

9. OTHER

Please provide any additional details. HDC Staff may ask you to submit additional information at a later time depending on your project.

Ø



November 22, 2023

Generation Solar 1192 East Draper Parkway, Ste. 466 Draper, UT 84020

> Re: Engineering Services Smith Residence 2490 Longfellow Street, Detroit, MI 7.900 kW System

To Whom It May Concern:

We have received information regarding solar panel installation on the roof of the above referenced structure. Our evaluation of the structure is to verify the existing capacity of the roof system and its ability to support the additional loads imposed by the proposed solar system.

A. Site Assessment Information

- 1. Site visit documentation identifying attic information including size and spacing of framing for the existing roof structure.
- 2. Design drawings of the proposed system including a site plan, roof plan and connection details for the solar panels. This information will be utilized for approval and construction of the proposed system.

B. Description of Structure:

Roof Framing:2 x 6 dimensional lumber at 16" on center.Roof Material:Composite Asphalt ShinglesRoof Slope:27 degreesAttic Access:AccessibleFoundation:Permanent

C. Loading Criteria Used

- Dead Load
 - Existing Roofing and framing = 7 psf
 - New Solar Panels and Racking = 3 psf
 - TOTAL = 10 PSF
- Live Load = 20 psf (reducible) 0 psf at locations of solar panels
- Ground Snow Load = 25 psf
- Wind Load based on ASCE 7-10
 - Ultimate Wind Speed = 115 mph (based on Risk Category II)
 - Exposure Category C

Analysis performed of the existing roof structure utilizing the above loading criteria is in accordance with the 2015 International Residential Code, including provisions allowing existing structures to not require strengthening if the new loads do not exceed existing design loads by 105% for gravity elements and 110% for seismic elements. This analysis indicates that the existing framing will support the additional panel loading without damage, if installed correctly.

Page 2 of 2

D. Solar Panel Anchorage

- 1. The solar panels shall be mounted in accordance with the most recent Unirac installation manual. If during solar panel installation, the roof framing members appear unstable or deflect non-uniformly, our office should be notified before proceeding with the installation.
- 2. The maximum allowable withdrawal force for a 5/16" lag screw is 235 lbs per inch of penetration as identified in the National Design Standards (NDS) of timber construction specifications. Based on a minimum penetration depth of 2½", the allowable capacity per connection is greater than the design withdrawal force (demand). Considering the variable factors for the existing roof framing and installation tolerances, the connection using one 5/16" diameter lag screw with a minimum of 2½" embedment will be adequate and will include a sufficient factor of safety.
- 3. Considering the wind speed, roof slopes, size and spacing of framing members, and condition of the roof, the panel supports shall be placed no greater than 48" on center.

Based on the above evaluation, this office certifies that with the racking and mounting specified, the existing roof system will adequately support the additional loading imposed by the solar system. This evaluation is in conformance with the 2015 IRC, current industry standards, and is based on information supplied to us at the time of this report.

Should you have any questions regarding the above or if you require further information do not hesitate to contact me.

VOUR Scott E. Wyssling, PE Michigan License No 62 068147






SMITH RESIDENCE


PHOTOVOLTAIC SYSTEM 2490 LONGFELLOW STREET DETROIT, MI 48206

SYSTEM SIZE: 7.90 kW-DC | 5.80 kW-AC **MODULE:** (20) CS3U- 395W **INVERTER:** (20) ENPHASE IQ8+-72-2-US


| Gillow Qkingcuts | GENERAL | 11. PLUMBING AND MECHANICAL VENTS THROUGH THE ROOF 9. FOR UNGROUNDED SYSTEMS, THE INV SHALL NOT BE COVERED BY SOLAR MODULES NO WITH GROUND FAULT PROTECTION DURING AND FAULT PROTECTION |
|--|--|---|
| man and a second s | 1. UTILITY SHALL BE NOTIFIED BEFORE ACTIVATION OF PHOTOVOLTAIC SYSTEM. | BUILDING, PLUMBING OR MECHANICAL VENTS TO BE COVERED, CONSTRUCTED OR ROUTED AROUND SOLAR MODULES. 10. PV MODULE FRAMES SHALL BE BOND OR BARE COPPER GEC/GEC |
| | BE LABELED, LISTED, OR CERTIFIED BY A NATIONALLY RECOGNIZED TESTING LABORATORY ACCREDITED BY | |
| | THE UNITED STATES OCCUPATIONAL SAFETY HEALTH ADMINISTRATION 3. CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS | 12. THE PHOTOVOLTAIC INVERTER WILL I |
| C Constantion St | INSTALLATION DOCUMENTS PRIOR TO INITIATING | 1. WIRING MATERIALS SHALL COMPLY WITH MAXIMUM CONTINUOUS CURRENT OUTPUT AT 25°C AND WILL BE CONTINUOUS, EXCEPT FOR |
| | CONSTRUCTION. 5. ALL EQUIPMENT AND ASSOCIATED CONNECTIONS, ETC, AND ALL ASSOCIATED WIRING AND INTERCONNECTIONS SHALL BE INSTALLED ONLY BY | RATED AT 90°C. 2. EXPOSED PHOTOVOLTAIC SYSTEM CONDUCTORS ON |
| Edeoarde | QUALIFIED PERSONNEL. 6. THE CONTRACTOR OR OWNER MUST PROVIDE ROOF ACCESS (LADDER TO ROOF) FOR ALL THE REQUIRED | 3. PHOTOVOLTAIC SYSTEM CONDUCTORS SHALL BE 16. WHEN APPLYING THE 120% RULE, T 10ENTIFIED AND GROUPED. THE MEANS OF 10ENTIFICATION SHALL BE PERMITTED BY SEPARATE 10. WHEN APPLYING THE 120% RULE, T 10ENTIFICATION SHALL BE PERMITTED BY SEPARATE 10. WHEN APPLYING THE 120% RULE, T 10ENTIFICATION SHALL BE PERMITTED BY SEPARATE |
| VICINITY MAP | INSPECTIONS. LADDERS MUST BE OSHA APPROVED, MINIMUM TYPE I WITH A 250LB. RATING, IN GOOD CONDITION AND DESIGNED FOR ITS INTENDED USE. | COLOR-CODING, MARKING TAPE, TAGGING OR OTHER APPROVED MEANS. 4. ALL EXTERIOR CONDUIT, FITTINGS, AND BOXES SHALL |
| CHARLES CON | CONTRACTOR SHALL VERIFY THAT THE ROOF STRUCTURE WILL WITHSTAND THE ADDITIONAL LOADS. LAG SCREWS SHALL PENETRATE A MINIMUM 2" INTO | BE RAIN-TIGHT AND APPROVED FOR USE IN WET LOCATIONS. |
| | SOLID SAWN STRUCTURAL MEMBERS AND SHALL NOT EXCEED MANUFACTURER RECOMMENDATIONS FOR FASTENERS INTO ENGINEERED STRUCTURAL | |
| | MEMBERS. 9. AN ACCESS POINT SHALL BE PROVIDED THAT DOES NOT PLACE THE GROUND LADDER OVER OPENINGS | OTHER EQUIPMENT SHALL NOT DISCONNECT THE |
| | SUCH AS WINDOWS OR DOORS ARE LOCATED AT STRONG POINTS OF BUILDING CONSTRUCTION AND IN LOCATIONS WHERE THE ACCESS POINT DOES NOT | BUILDING CONNECTION BETWEEN THE GROUNDING ELECTRODE CONDUCTOR AND THE PV SOURCE AND/OR OUTPUT CIRCUIT GROUNDED CONDUCTOR. 8. FOR GROUNDED SYSTEMS, THE PHOTOVOLTAIC |
| | TREE LIMBS, WIRES, OR SIGNS. 10. WHERE DC CONDUCTORS ARE RUN INSIDE BUILDING, THEY SHALL BE CONTAINED IN A METAL RACEWAY; | SOURCE AND OUTPUT CIRCUITS SHALL BE PROVIDED |
| AERIAL MAP | THEY SHALL NOT BE INSTALLED WITHIN 10" OF THE ROOF DECKING OR SHEATHING EXCEPT WHERE COVERED BY THE PV MODULES AND EQUIPMENT. | WITH A GROUND-FAULT PROTECTION DEVICE OR SYSTEM THAT DETECTS A GROUND FAULT, INDICATES THAT FAULT HAS OCCURED AND AUTOMATICALLY DISCONNECTS ALL CONDUCTORS OR CAUSES THE INVERTER TO AUTOMATICALLY CEASE SUPPLYING POWER TO OUTPUT CIRCUITS. |
| | 3 | |

| | GOVERNING CODE ALL MATERIALS, EQUIPMENT, INSTAI WORK SHALL COMPLY WITH THE FO APPLICABLE CODES: • 2014 NATIONAL ELECTRIC CODE (N • 2015 MICHIGAN BUILDING CODE • 2015 MICHIGAN PUMBING CODE • 2015 INTERNATIONAL FUEL GAS CC • 2015 INTERNATIONAL FUEL GAS CC • 2015 INTERNATIONAL MECHANICAL • 2015 INTERNATIONAL FIRE CODE (I • 2015 INTERNATIONAL FIRE CODE (I • 1CC/ANSI A117.1 - 2009 | LLATION AND LLOWING IEC) DDE _ CODE ODE FC) |
|--|--|---|
| INVERTER IS EQUIPPED ION AND A GFI FUSE ITION. NDED TO RACKING RAIL PER THE MODULE JCTION SHEET. . BE BONDED TO BARE .SCO GBL-4DBT LAY-IN L BE LISTED AS UL 1741 D BE UL2703 RATED. | SHEET INDEX: PV-1 - COVER PAGE PV-2 - PROPERTY PLAN PV-3 - SITE PLAN PV-4 - ELECTRICAL CALCULATIONS PV-5 - 1-LINE DIAGRAM PV-5.1 - 3-LINE DIAGRAM PV-6 - ELECTRICAL LABELS PV-7 - ELECTRICAL PHOTOS | |
| CTRODE CONDUCTOR OR SPLICES OR JOINTS IPMENT. E METHOD OF UTILITY ERS SHALL NOT READ THE SOLAR BREAKER DSITE END OF THE BUS ROUND THE EXISTING WELL AS THE NEW | | |
| MAINTAINED. | LICENSE NUMBER: 6218 SMITH, MIRANDA | A |
| | 2490 LONGFELLOW STRI DETROIT, MI 48206 7348589871 | |
| | COVER PAGE JOB #: 4184 REV #1: DATE: 11/21/2023 REV #2: DRAWN BY: IAN REV #3: | PV-1 |






| N | LEGEND: | | |
|--------------|---|------|--|
| | PROPERTY LINE: | | |
| \checkmark | DRIVEWAY: | | |
| | FENCE:0000 | -0 | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | SCALE: 1" = 20' | | |
| | LICENSE NUMBER: 62185 | 537 | |
| | SMITH, MIRANDA | | |
| • | 2490 LONGFELLOW STREET DETROIT, MI 48206 | | |
| 2 · | 7348589871 | | |
| | 5 | | |
| WINDING | GENERATION SOLAR 1192 E. DRAPER PARKWAY STE 4 DRAPER, UT 84020 (2021) ADS DSCO | 66 | |
| 111. | (888) 985-2859 PROPERTY PLAN | | |
| 1 | JOB #: 4184 REV #1: | | |
| | DATE: 11/21/2023 REV #2: DRAWN BY: IAN REV #3: | PV-2 | |
| | | | |



427.38

1533.4002



WIND UPLIFT AT ATTACHMENT POINTS IS PROVIDED WITH THE ENGINEERING LETTER.

SUPPORT LOCATIONS HAVE BEEN OPTIMIZED TO WITHSTAND UPLIFT




| | 3000 PA DOWINWARD | |
|----------------------------------|--|--|
| MODULE WEIGHT | 22.5 KG (49.6 LBS) | |
| MODULE DIMENSIONS (H X L X D) | 2000 × 992 × 35 MM (78.7 × 39.1 × 1.38 INCHES) | |
| MODULE AREA | 21.3692 FT ² | |
| MODULE MECHANICAL SPECIFICATIONS | | |
| DESIGN WIND SPEED | 115 MPH | |
| DESIGN SNOW LOAD | 35 PSF | |
| ROOF PITCH | 27° | |

TOTAL ARRAY AREA (SQ. FT)

TOTAL ROOF AREA (SQ. FT)

| MODULE INFORMATION | | |
|-------------------------------|--|--|
| MODULE TYPE | CS3U-395W | |
| MAX DESIGN LOAD (WIND & SNOW) | 5400 PA UPWARD / 3600 PA DOWNWARD | |
| MODULE WEIGHT | 22.5 KG (49.6 LBS) | |
| MODULE DIMENSIONS (H X L X D) | 2000 × 992 × 35 MM (78.7 × 39.1 × 1.38 INCHES) | |
| MODULE AREA | 21.3692 FT ² | |

| MODULE INFORMA | TION |
|-------------------------------|--|
| MODULE TYPE | CS3U-395W |
| MAX DESIGN LOAD (WIND & SNOW) | 5400 PA UPWARD / 3600 PA DOWNWARD |
| MODULE WEIGHT | 22.5 KG (49.6 LBS) |
| MODULE DIMENSIONS (H X L X D) | 2000 × 992 × 35 MM (78.7 × 39.1 × 1.38 INCHES) |
| MODULE AREA | 21.3692 FT ² |




| 1 | DocuSign Envelope ID: | 4C07 | 77C38-FA98-419B-B651-E66 | DE9437930 |
|---|---|------|--------------------------|-----------|
| | ROOF TYPE: ASPHALT SHINGLE | | ENPHASE CIRCUITS | |
| | ROOF SECTION 1: 4 MODULES AZIMUTH: 334° PITCH: 27° | 1 | CIRCUIT # 1: 10 MODULES | |
| | ROOF SECTION 2: 16 MODULES AZIMUTH: 154° PITCH: 27° | 2 | CIRCUIT # 2: 10 MODULES | |

| N | SYSTEM LEGEN | D | | |
|----------------------|---|---|--|--|
| $\mathbf{\Lambda}$ | PHOTOVOLTAIC SYSTEM: DC SYSTEM SIZE: 7.90 kW | | | |
| Ň | AC SYSTEM SIZE: 5.80 kW | | | |
| | | | | |
| | MP MAIN SERVICE PANEL | | | |
| | | | | |
| | EC ENPHASE AC COMBINER PANE | EL | | |
| | (20) CS3U- 395W WITH ENPH MICROINVERTERS MOUNTED MODULE | | | |
| | | IT | | |
| | CONDUIT RUN CONDUIT TO BE RUN IN ATTIC OTHERWISE CONDUIT BLOCKS ABOVE ROOF SURFACE, CLOSE T AND UNDER EAVES; TO BE PAIN EXTERIOR/EXISTING BACKGROUNE LOCATION; TO BE LABELED AT MAX CONDUIT RUNS ARE APPROXIMAT BE DETERMINED IN THE BY THE INS | MIN. 1"/MAX 6" O RIDGE LINES, TED TO MATCH O COLOR OF ITS (10' INTERVALS. TE AND ARE TO | | |
| | FIRE CODE SETBACK (18" MI | _ | | |
| | ROOF ATTACHMENT P | OINT | | |
| | RAIL RAFTER | | | |
| | | | | |
| | SCALE: 1" = 10' | 537 | | |
| 0 | SMITH, MIRANDA 2490 LONGFELLOW STREET DETROIT, MI 48206 7348589871 | | | |
| International Action | I 192 E. DRAPER PARKWAY STE DRAPER, UT 84020 (888) 985-2859 | 466 | | |
| | SITE PLAN | | | |
| ' | JOB #: 4184 REV #1: DATE: 11/21/2023 REV #2: DRAWN BY: IAN REV #3: | PV-3 | | |
| | | | | |


| Ampacity Calculation: | | | | | | |
|--|-------------------|-------------|-----------|--------------|------|-------|
| Wiring Location: | | rray to In | verter ([| Direct Curre | ent) | |
| | | | • | | | |
| All calculations show minimum sizing | for ampacity | | | | | |
| Actual wire sizing may be larger for w | oltage drop or ot | her factors | S | | | |
| All calculations are according the the | 2020 National E | Electric Co | de | | | |
| Initial Input Values | | | | | | |
| | | Amps | | | | Amps |
| Isc (Short Circuit Current) | | 10.25 | | | | |
| Number of circuits | | 10.25 | Х | 1 | = | 10.25 |
| Maximum Circuit Current (NEC 690.8 (A)(1+2) | | 10.25 | х | 125% | = | 12.81 |
| | | 10.25 | ^ | 12,5 % | - | 12.01 |
| Overcurrent device rating (NEC 690.8 (B)(1) | | 12.81 | х | 125% | = | 16.02 |
| Minimum overcurrent device | | 20.00 | | | | OK |
| | SIZE AWG # | | | | | |
| Chosen Conductor Type THHN, RHW-2 or USE-2 | 10 | | | | | |
| | | | | | | |
| Conductor Derating | | | | | | |
| NEC 690.31 (C) ref (NEC 310.16) | | | | | | |
| Conductor 90°C Ampacity | | 30 | | | | |
| Conduit Fill Derating | 3 | 30.00 | Х | 1.00 | = | 30.00 |
| Temperature Derating °F | 105-113 | 30.00 | Х | .87 | = | 26.10 |
| Ampacity vs. Overcurrent Device | | | | | | |
| Conductor Ampacity Check | | 26.10 | ≥ | 12.81 | | ОК |
| Conductor to Overcurrent Check | | 26.10 | 2 | 20.00 | | OK |

| Ampacity Calculation: | | | | | |
|---|------------------|--------------|-------|-----------|----------|
| Wiring Location: | INVERTER to | Main Service | (Alte | rnating C | urre |
| | | | • | | |
| All calculations show minimum sizing for | or ampacity | | | | |
| Actual wire sizing may be larger for volt | age drop or othe | r factors | | | |
| All calculations are according the the 2 | 020 National Ele | ctric Code | | | |
| Initial Input Values | | | | | |
| Inverter Continous AC ouput (Watts) | 290 | | | | |
| Minimum Operating Voltage | 240 | Watts | | Volts | |
| | | 290 | / | 240 | |
| | | | | | |
| Inverter Continious AC Amps | | 1.21 | | | |
| Number of circuits | | 1.21 | Х | 20 | <u> </u> |
| Overcurrent device rating | | | | | |
| NEC 690.8 (B)(3) | | 24.17 | Х | 125% | |
| Minimum overcurrent device | | 40.00 | | | |
| | SIZE AWG # | | | | |
| Chosen Conductor Type | | | | | |
| THHN, RHW-2 or USE-2 | 6 | | | | |
| | | | | | |
| Conductor Derating | | | | | |
| NEC 690.31 (C) ref (NEC 310.16) | | 75 | | | |
| Conductor 90°C Ampacity | 0 | 75 | V | 4.00 | |
| Conduit Fill Derating | 3 | 75.00 | X | 1.00 | |
| Temperature Derating °F | 105-113 | 75.00 | Х | .87 | |
| Ampacity vs. Overcurrent Device | | | | | |
| Conductor Ampacity Check | | 65.25 | ≥ | 30.21 | |
| Conductor Overcurrent Check | | 65.25 | 2 | 40.00 | |



UTILITY AC DISCONNECT MUST BE ACCESSIBLE, LOCKABLE, LABELED, BLADE-STYLE SWITCH, AND LOCATED WITHIN 5' FROM THE UTILITY METER

| | CONDUCTOR AND CONDUIT SCHEDULE | | | | | | |
|-----|--------------------------------|-----------|-----------------|--------------|-------------------|--|--|
| TAG | WIRE TYPE | WIRE SIZE | # OF CONDUCTORS | CONDUIT TYPE | MIN. CONDUIT SIZE | | |
| 1 | PV WIRE | #10 | 2 - L1 L2 | FREE AIR | N/A | | |
| 1 | BARE COPPER | #6 | 1 - BARE | FREE AIR | N/A | | |
| 2 | THWN-2 | #10 | 2 - L1 L2 | EMT | 3/4" | | |
| 2 | THWN-2 EGC | #10 | 1 - GND | EMT | 3/4" | | |
| 3 | THWN-2 | #6 | 3 - L1 L2 N | EMT | 3/4" | | |
| 3 | THWN-2 EGC | #8 | 1 - GND | EMT | 3/4" | | |



ENPHASE IQ8+-72-2-US

MICRO-INVERTER

| PV MODULE ELECTRICAL S | PECIFICATIONS | | | | |
|--|---------------|------------------------------------|------------------------------------|--|-------------------------|
| | | INVERTER ELECTRICAL SPECIFICATIONS | | SYSTEM OVER-CURRENT PROTECTION DEVICE (OCPD) | |
| MODULE TYPE | CS3U- 395W | INVERTER TYPE | INVERTER TYPE ENPHASE IQ8+-72-2-US | | |
| POWER MAX (P _{MAX}) | 395W | MAX INPUT DC VOLTAGE | 60V | INVERTER TYPE | ENPHASE IQ8+-72-2-US |
| OPEN CIRCUIT VOLTAGE (V _{OC}) | 48.4V | MAX DC SHORT CIRCUIT CURRENT | 15A | # OF INVERTERS | 20 |
| SHORT CIRCUIT CURRENT (I _{SC}) | 10.25A | MAXIMUM OUTPUT POWER | 290W | | 1.21 |
| MAX POWER-POINT VOLTAGE (VMP) | 40.6V | MAXIMUM CONT. OUTPUT CURRENT | 1.21A | MAX CONTINUOUS OUTPUT CURRENT | 1.21 |
| (WI / | | | | (# OF INVERTERS) X (MAX CONT. OUTPUT CURRENT) X 1 OCPD RATING | |
| MAX POWER-POINT CURRENT (I _{MP}) | 9.73A | CEC EFFICIENCY | 97% | | |
| SERIES FUSE RATING | 19.9A | MAX UNITS PER 20A CIRCUIT | 13 | (20 x 1.21A x 1.25)= 30.25A <= 4 | 10A, OK |

PHOTOVOLTAIC SYSTEM: DC SYSTEM SIZE: 7.900 kW AC SYSTEM SIZE: 5.80 kW INVERTER: (20) ENPHASE IQ8+-72-2-US MODULE: (20) CS3U- 395W

NOTES

(E) 150A RATED

MAIN SERVICE

PANEL

- MODULES ARE BONDED TO RAIL USING UL 2703 RATED BONDING SYSTEM -INTEGRATED BONDING MID-CLAMPS + DIRECT-BURIAL LAY-IN-LUGS; SEE ATTACHED FOR SPECIFICATIONS IF APPLICABLE
- PV DC SYSTEM IS UNGROUNDED
- PV ARRAY WILL HAVE A GROUNDING ELECTRODE SYSTEM IN COMPLIANCE WITH NEC 250.58 AND 690.47(A)
- WITH NEC 200:50 AND 590.47(A) PV SOURCE, OUTPUT, AND INVERTER INPUT CIRCUIT WIRING METHODS SHALL COMPLY WITH NEC 690.1(G) BACKFED PV BREAKER WILL BE INSTALLED AT OPPOSITE END OF THE BUS BAR FROM THE MAIN BREAKER. A PERMANENT WARNING LABEL TO BE
- INSTALLED PER SYSTEM SIGNAGE, PAGE
- BARE COPPER IS TRANSITIONED TO THWN-2 VIA IRREVERSIBLE CRIMP WHEN PRESENT, THE GEC TO BE CONTINUOUS
- INVERTER(S) TO BE COMPLIANT WITH UL 1741 SUPPLEMENT A
- CONDUIT AND CONDUCTOR SPECIFICATIONS ARE BASED ON MINIMUM CODE REQUIREMENTS AND ARE NOT MEANT TO LIMIT UP-SIZING AS REQUIRED BY FIELD CONDITIONS
- CONDUIT AND CONDUCTOR SPECIFICATIONS ARE BASED ON MINIMUM CODE REQUIREMENTS AND ARE NOT MEANT TO LIMIT UPSIZING AS REQUIRED BY FIELD CONDITIONS.

INSTALLER NOTES:



Signed 11/24/2023

LICENSE NUMBER: 6218537

SMITH, MIRANDA

2490 LONGFELLOW STREET DETROIT, MI 48206 7348589871



1192 E. DRAPER PARKWAY STE 466 DRAPER, UT 84020 (888) 985-2859

1-LINE DIAGRAM & CALCULATIONS


PV-5

JOB #: 4184 DATE: 11/21/2023 DRAWN BY: IAN

REV #1: REV #2: REV #3:

UTILITY AC DISCONNECT MUST BE ACCESSIBLE, LOCKABLE, LABELED, BLADE-STYLE SWITCH, AND LOCATED WITHIN 5' FROM THE UTILITY METER

| | CONDUCTOR AND CONDUIT SCHEDULE | | | | | | |
|-----|--------------------------------|-----------|-----------------|--------------|-------------------|--|--|
| TAG | WIRE TYPE | WIRE SIZE | # OF CONDUCTORS | CONDUIT TYPE | MIN. CONDUIT SIZE | | |
| 1 | PV WIRE | #10 | 2 - L1 L2 | FREE AIR | N/A | | |
| 1 | BARE COPPER | #6 | 1 - BARE | FREE AIR | N/A | | |
| 2 | THWN-2 | #10 | 2 - L1 L2 | EMT | 3/4" | | |
| 2 | THWN-2 EGC | #10 | 1 - GND | EMT | 3/4" | | |
| 3 | THWN-2 | #6 | 3 - L1 L2 N | EMT | 3/4" | | |
| 3 | THWN-2 EGC | #8 | 1 - GND | EMT | 3/4" | | |



ENPHASE IQ8+-72-2-US

MICRO-INVERTER

| | | 1 | | | | |
|--|---------------|------------------------------|------------------------------------|---|-------------------------|--|
| PV MODULE ELECTRICAL S | PECIFICATIONS | INVERTER ELECTRICAL S | INVERTER ELECTRICAL SPECIFICATIONS | | | |
| MODULE TYPE | CS3U- 395W | | | SYSTEM OVER-CURRENT PROTECTION | I DEVICE (OCPD) | |
| | 0000-000 | INVERTER TYPE | ENPHASE IQ8+-72-2-US | CALCULATIONS | _ | |
| POWER MAX (P _{MAX}) | 395W | MAX INPUT DC VOLTAGE | 60V | INVERTER TYPE | ENPHASE IQ8+-72-2-US | |
| OPEN CIRCUIT VOLTAGE (V _{OC}) | 48.4V | MAX DC SHORT CIRCUIT CURRENT | 15A | # OF INVERTERS | 20 | |
| SHORT CIRCUIT CURRENT (I _{SC}) | 10.25A | MAXIMUM OUTPUT POWER | 290W | MAX CONTINUOUS OUTPUT CURRENT | 1.21 | |
| MAX POWER-POINT VOLTAGE (VMP) | 40.6V | MAXIMUM CONT. OUTPUT CURRENT | 1.21A | MAX CONTINUOUS OUTPUT CURRENT | 1.21 | |
| | 0.701 | | 070/ | (# OF INVERTERS) X (MAX CONT. OUTPUT CURRENT) X 12 OCPD RATING | | |
| MAX POWER-POINT CURRENT (I _{MP}) | 9.73A | CEC EFFICIENCY | 97% | | | |
| SERIES FUSE RATING | 19.9A | MAX UNITS PER 20A CIRCUIT | 13 | (20 x 1.21A x 1.25)= 30.25A <= 4 | IOA, OK | |

PHOTOVOLTAIC SYSTEM: DC SYSTEM SIZE: 7.900 kW AC SYSTEM SIZE: 5.80 kW INVERTER: (20) ENPHASE IQ8+-72-2-US MODULE: (20) CS3U- 395W

NOTES

- MODULES ARE BONDED TO RAIL USING UL 2703 RATED BONDING SYSTEM -INTEGRATED BONDING MID-CLAMPS + DIRECT-BURIAL LAY-IN-LUGS; SEE ATTACHED FOR SPECIFICATIONS IF APPLICABLE
- PV DC SYSTEM IS UNGROUNDED
- PV ARRAY WILL HAVE A GROUNDING ELECTRODE SYSTEM IN COMPLIANCE WITH NEC 250.58 AND 690.47(A)
- PV SOURCE, OUTPUT, AND INVERTER INPUT CIRCUIT WIRING METHODS SHALL COMPLY WITH NEC 690.1(G)
- BACKFED PV BREAKER WILL BE INSTALLED AT OPPOSITE END OF THE BUS BAR FROM THE MAIN BREAKER. A PERMANENT WARNING LABEL TO BE INSTALLED PER SYSTEM SIGNAGE, PAGE
- BARE COPPER IS TRANSITIONED TO THWN-2 VIA IRREVERSIBLE CRIMP WHEN PRESENT, THE GEC TO BE CONTINUOUS
- INVERTER(S) TO BE COMPLIANT WITH UL 1741 SUPPLEMENT A
- CONDUIT AND CONDUCTOR SPECIFICATIONS ARE BASED ON MINIMUM CODE REQUIREMENTS AND ARE NOT MEANT TO LIMIT UP-SIZING AS REQUIRED BY FIELD CONDITIONS
- CONDUIT AND CONDUCTOR SPECIFICATIONS ARE BASED ON MINIMUM CODE REQUIREMENTS AND ARE NOT MEANT TO LIMIT UPSIZING AS REQUIRED BY FIELD CONDITIONS.

INSTALLER NOTES:



Signed 11/24/2023

LICENSE NUMBER: 6218537

SMITH, MIRANDA

2490 LONGFELLOW STREET DETROIT, MI 48206 7348589871



1192 E. DRAPER PARKWAY STE 466 DRAPER, UT 84020 (888) 985-2859

3-LINE DIAGRAM & CALCULATIONS


JOB #: 4184 DATE: 11/21/2023 DRAWN BY: IAN

REV #1: REV #2: REV #3:





(E)150A RATED MAIN SERVICE PANEL

FACILITY GROUND (E) GROUND ROD + (E) WATER PIPE BOND









SMITH, MIRANDA

2490 LONGFELLOW STREET DETROIT, MI 48206 7348589871




1192 E. DRAPER PARKWAY STE 466 DRAPER, UT 84020 (888) 985-2859

ELECTRICAL PHOTOS

PV-7

JOB #: 4184 DATE: 11/21/2023 DRAWN BY: IAN REV #1: REV #2: REV #3:



2490 LONGFELLOW STREET, DETROIT, MI 48206

Section CanadianSolar

KuMax HIGH EFFICIENCY MONO PERC MODULE CS3U-380|385|390|395|400MS (1000 V / 1500 V)


MORE POWER



Better shading tolerance

Low power loss in cell connection

Low temperature coefficient (Pmax): -0.36 % / °C



Low NMOT: 42 + 3 °C

MORE RELIABLE

Lower hot spot temperature

Minimizes micro-crack impacts

Heavy snow load up to 5400 Pa, wind load up to 3600 Pa*





linear power output warranty*



enhanced product warranty on materials and workmanship*

*According to the applicable Canadian Solar Limited Warranty Statement.

MANAGEMENT SYSTEM CERTIFICATES

ISO 9001:2015 / Quality management system ISO 14001:2015 / Standards for environmental management system OHSAS 18001:2007 / International standards for occupational health & safety

PRODUCT CERTIFICATES*

IEC 61215 / IEC 61730: VDE / CE / CQC / MCS / KS / INMETRO UL 1703 / IEC 61215 performance: CEC listed (US) / FSEC (US Florida) UL 1703: CSA / IEC 61701 ED2: VDE / IEC 62716: VDE / IEC 60068-2-68: SGS Take-e-way




* As there are different certification requirements in different markets, please contact your local Canadian Solar sales representative for the specific certificates applicable to the products in the region in which the products are to be used.

CANADIAN SOLAR INC. is committed to providing high quality solar products, solar system solutions and services to customers around the world. No. 1 module supplier for quality and performance / price ratio in IHS Module Customer Insight Survey. As a leading PV project developer and manufacturer of solar modules with over 40 GW deployed around the world since 2001.

* For detailed information, please refer to the Installation Manual.

ENGINEERING DRAWING (mm)



ELECTRICAL DATA | STC*

| CS3U | 380MS | 385MS | 390MS | 395MS | 400MS |
|--|-------------|-------------|-----------|-----------|------------|
| Nominal Max. Power (Pmax) | 380 W | 385 W | 390 W | 395 W | 400 W |
| Opt. Operating Voltage (Vmp) | 40.0 V | 40.2 V | 40.4 V | 40.6 V | 40.8 V |
| Opt. Operating Current (Imp) | 9.50 A | 9.58 V | 9.66 A | 9.73 A | 9.81 A |
| Open Circuit Voltage (Voc) | 47.8 V | 48.0 V | 48.2 V | 48.4 V | 48.6 V |
| Short Circuit Current (Isc) | 10.01 A | 10.09 A | 10.17 A | 10.25 A | 10.33 A |
| Module Efficiency | 19.2% | 19.4% | 19.7% | 19.9% | 20.2% |
| Operating Temperature | -40°C ~ | +85°C | | | |
| Max. System Voltage | 1500V (I | (EC/UL) | or 1000 | / (IEC/UI | _) |
| Module Fire Performance | TYPE 1 (| UL 1703 | 5) | | |
| Module Fire Performance | or Class | C (IEC 6 | 1730) | | |
| Max. Series Fuse Rating | 30 A | | | | |
| Application Classification | Class A | | | | |
| Power Tolerance | 0 ~ + 10 | W | | | |
| * Under Standard Test Conditions (STC) | ofirradianc | o of 1000 V | V/m² spor | trum AM 1 | 5 and coll |


 \star Under Standard Test Conditions (STC) of irradiance of 1000 W/m², spectrum AM 1.5 and cell temperature of 25°C.

ELECTRICAL DATA | NMOT*

| CS3U | 380MS | 385MS | 390MS | 395MS | 400MS |
|------------------------------|--------|--------|--------|--------|--------|
| Nominal Max. Power (Pmax) | 283 W | 287 W | 290 W | 294 W | 298 W |
| Opt. Operating Voltage (Vmp) | 37.2 V | 37.4 V | 37.6 V | 37.8 V | 38.0 V |
| Opt. Operating Current (Imp) | 7.60 A | 7.66 A | 7.72 A | 7.78 A | 7.84 A |
| Open Circuit Voltage (Voc) | 44.8 V | 45.0 V | 45.2 V | 45.4 V | 45.6 V |
| Short Circuit Current (Isc) | 8.08 A | 8.14 A | 8.20 A | 8.27 A | 8.33 A |

 \star Under Nominal Module Operating Temperature (NMOT), irradiance of 800 W/m², spectrum AM 1.5, ambient temperature 20°C, wind speed 1 m/s.

CS3U-400MS / I-V CURVES



MECHANICAL DATA

| Specification | Data |
|---------------------------------------|---|
| Cell Type | Mono-crystalline |
| Cell Arrangement | 144 [2 X (12 X 6)] |
| Dimensione | 2000 X 992 X 35 mm |
| Dimensions | (78.7 X39.1 X1.38 in) |
| Weight | 22.5 kg (49.6 lbs) |
| Front Cover | 3.2 mm tempered glass |
| F | Anodized aluminium alloy, |
| Frame | crossbar enhanced |
| J-Box | IP68, 3 bypass diodes |
| Cable | 4 mm² (IEC), 12 AWG (UL) |
| Cable Length (Including Connector) | Portrait: 400 mm (15.7 in) (+) / 280 mm (11.0 in) (-); landscape: 1250 mm (49.2 in); leap-frog connection: 1670 mm (65.7 in)* |
| Connector | T4 series or H4 UTX or MC4-EVO2 |
| Per Pallet | 30 pieces |
| Per Container (40' HO) | 660 pieces |

Per Container (40' HQ) 660 pieces

* For detailed information, please contact your local Canadian Solar sales and technical representatives.

TEMPERATURE CHARACTERISTICS

| Specification | Data |
|--------------------------------------|--------------|
| Temperature Coefficient (Pmax) | -0.36 % / °C |
| Temperature Coefficient (Voc) | -0.29 % / °C |
| Temperature Coefficient (Isc) | 0.05 % / °C |
| Nominal Module Operating Temperature | 42 ± 3°C |

PARTNER SECTION

* The specifications and key features contained in this datasheet may deviate slightly from our actual products due to the on-going innovation and product enhancement. Canadian Solar Inc. reserves the right to make necessary adjustments to the information described herein at any time without further notice. Please be kindly advised that PV modules should be handled and installed by qualified people who have professional skills and please carefully read the safety and installation instructions before using our PV modules.

CANADIAN SOLAR INC.

545 Speedvale Avenue West, Guelph, Ontario N1K 1E6, Canada, www.canadiansolar.com, support@canadiansolar.com

Data Sheet Enphase Networking

Enphase IQ Combiner 4/4C

X-IQ-AM1-240-4 X-IQ-AM1-240-4C



The Enphase IQ Combiner 4/4C with Enphase IQ Gateway and integrated LTE-M1 cell modem (included only with IQ Combiner 4C) consolidates interconnection equipment into a single enclosure and streamlines IQ microinverters and storage installations by providing a consistent, pre-wired solution for residential applications. It offers up to four 2-pole input circuits and Eaton BR series busbar assembly.

Smart

- Includes IQ Gateway for communication and control
- Includes Enphase Mobile Connect cellular modem (CELLMODEM-M1-06-SP-05), included only with IQ Combiner 4C
- Includes solar shield to match Enphase IQ Battery aesthetics and deflect heat
- Flexible networking supports Wi-Fi, Ethernet, or cellular
- · Optional AC receptacle available for PLC bridge
- Provides production metering and consumption monitoring

Simple

- Centered mounting brackets support single stud mounting
- · Supports bottom, back and side conduit entry
- Up to four 2-pole branch circuits for 240 VAC plug-in breakers (not included)
- 80A total PV or storage branch circuits

Reliable

- Durable NRTL-certified NEMA type 3R enclosure
- · Five-year limited warranty
- Two years labor reimbursement program coverage included for both the IQ Combiner SKU's
- UL listed



To learn more about Enphase offerings, visit enphase.com

DocuSign Envelope ID: 4C077C38-FA98-419B-B651-E66DE9437930

| MODEL NUMBER | |
|---|---|
| IQ Combiner 4 (X-IQ-AM1-240-4) | IQ Combiner 4 with Enphase IQ Gateway printed circuit board for integrated revenue grade PV production metering (ANS C12.20 +/- 0.5%) and consumption monitoring (+/- 2.5%). Includes a silver solar shield to match the IQ Battery system and IQ System Controller 2 and to deflect heat. |
| IQ Combiner 4C (X-IQ-AM1-240-4C) | IQ Combiner 4C with Enphase IQ Gateway printed circuit board for integrated revenue grade PV production metering (ANSI C12.20 +/- 0.5%) and consumption monitoring (+/- 2.5%). Includes Enphase Mobile Connect cellular modem (CELLMODEM-M1-06-SP-05), a plug-and-play industrial-grade cell modem for systems up to 60 microinverters. (Available in the US, Canada, Mexico, Puerto Rico, and the US Virgin Islands, where there is adequate cellular service in the installation area.) Includes a silver solar shield to match the IQ Battery and IQ System Controller and to deflect heat |
| ACCESSORIES AND REPLACEMENT PARTS | (not included, order separately) |
| Ensemble Communications Kit COMMS-CELLMODEM-M1-06 CELLMODEM-M1-06-SP-05 CELLMODEM-M1-06-AT-05 | Includes COMMS-KIT-01 and CELLMODEM-M1-06-SP-05 with 5-year Sprint data plan for Ensemble sites 4G based LTE-M1 cellular modem with 5-year Sprint data plan 4G based LTE-M1 cellular modem with 5-year AT&T data plan |
| Circuit Breakers BRK-10A-2-240V BRK-15A-2-240V BRK-20A-2P-240V BRK-15A-2P-240V-B BRK-20A-2P-240V-B | Supports Eaton BR210, BR215, BR220, BR230, BR240, BR250, and BR260 circuit breakers. Circuit breaker, 2 pole, 10A, Eaton BR210 Circuit breaker, 2 pole, 15A, Eaton BR215 Circuit breaker, 2 pole, 20A, Eaton BR220 Circuit breaker, 2 pole, 15A, Eaton BR215B with hold down kit support Circuit breaker, 2 pole, 20A, Eaton BR220B with hold down kit support |
| EPLC-01 | Power line carrier (communication bridge pair), quantity - one pair |
| XA-SOLARSHIELD-ES | Replacement solar shield for IQ Combiner 4/4C |
| XA-PLUG-120-3 | Accessory receptacle for Power Line Carrier in IQ Combiner 4/4C (required for EPLC-01) |
| XA-ENV-PCBA-3 | Replacement IQ Gateway printed circuit board (PCB) for Combiner 4/4C |
| X-IQ-NA-HD-125A | Hold down kit for Eaton circuit breaker with screws. |
| ELECTRICAL SPECIFICATIONS | |
| Rating | Continuous duty |
| System voltage | 120/240 VAC, 60 Hz |
| Eaton BR series busbar rating | 125 A |
| Max. continuous current rating | 65 A |
| Max. continuous current rating (input from PV/storage) | 64 A |
| Max. fuse/circuit rating (output) | 90 A |
| Branch circuits (solar and/or storage) | Up to four 2-pole Eaton BR series Distributed Generation (DG) breakers only (not included) |
| Max. total branch circuit breaker rating (input) | 80A of distributed generation / 95A with IQ Gateway breaker included |
| Envoy breaker | 10A or 15A rating GE/Siemens/Eaton included |
| Production metering CT | 200 A solid core pre-installed and wired to IQ Gateway |
| Consumption monitoring CT (CT-200-SPLIT) | A pair of 200 A split core current transformers |
| MECHANICAL DATA | |
| Dimensions (WxHxD) | 37.5 x 49.5 x 16.8 cm (14.75" x 19.5" x 6.63"). Height is 21.06" (53.5 cm) with mounting brackets. |
| Weight | 7.5 kg (16.5 lbs) |
| Ambient temperature range | -40° C to +46° C (-40° to 115° F) |
| Cooling | Natural convection, plus heat shield |
| Enclosure environmental rating | Outdoor, NRTL-certified, NEMA type 3R, polycarbonate construction |
| Wire sizes | 20 A to 50 A breaker inputs: 14 to 4 AWG copper conductors 60 A breaker branch input: 4 to 1/0 AWG copper conductors Main lug combined output: 10 to 2/0 AWG copper conductors Neutral and ground: 14 to 1/0 copper conductors Always follow local code requirements for conductor sizing. |
| Altitude | To 2000 meters (6,560 feet) |
| INTERNET CONNECTION OPTIONS | |
| | 802.11b/g/n |
| Integrated Wi-Fi | |
| Cellular | CELLMODEM-M1-06-SP-05, CELLMODEM-M1-06-AT-05 (4G based LTE-M1 cellular modem). Note that an Enphase Mobile Connect cellular modem is required for all Ensemble installations |
| - | CELLMODEM-M1-06-SP-05, CELLMODEM-M1-06-AT-05 (4G based LTE-M1 cellular modem). Note that an Enphase Mobile Connect cellular modem is required for all Ensemble installations. Optional, 802.3, Cat5E (or Cat 6) UTP Ethernet cable (not included) |
| Cellular | Mobile Connect cellular modem is required for all Ensemble installations. |
| Cellular Ethernet | Mobile Connect cellular modem is required for all Ensemble installations. |



To learn more about Enphase offerings, visit enphase.com

© 2022 Enphase Energy. All rights reserved. Enphase, the Enphase logo, IQ Combiner 4/4C, and other names are trademarks of Enphase Energy, Inc. Data subject to change. 02-14-2022

\ominus ENPHASE.





IQ8 and IQ8+ Microinverters

Our newest IQ8 Microinverters are the industry's first microgrid-forming, softwaredefined microinverters with split-phase power conversion capability to convert DC power to AC power efficiently. The brain of the semiconductor-based microinverter is our proprietary application-specific integrated circuit (ASIC) which enables the microinverter to operate in grid-tied or off-grid modes. This chip is built in advanced 55nm technology with high speed digital logic and has super-fast response times to changing loads and grid events, alleviating constraints on battery sizing for home energy systems.



Part of the Enphase Energy System, IQ8 Series Microinverters integrate with the Enphase IQ Battery, Enphase IQ Gateway, and the Enphase App monitoring and analysis software.



Connect PV modules quickly and easily to IQ8 Series Microinverters using the included Q-DCC-2 adapter cable with plug-n-play MC4 connectors.



IQ8 Series Microinverters redefine reliability standards with more than one million cumulative hours of power-on testing, enabling an industryleading limited warranty of up to 25 years.



IQ8 Series Microinverters are UL Listed as PV Rapid Shut Down Equipment and conform with various regulations, when installed according to manufacturer's instructions.

© 2022 Enphase Energy. All rights reserved. Enphase, the Enphase logo, IQ8 Microinverters, and other names are trademarks of Enphase Energy, Inc. Data subject to change.

Easy to install

- Lightweight and compact with plug-n-play connectors
- Power Line Communication (PLC) between components
- Faster installation with simple two-wire cabling

High productivity and reliability

- Produce power even when the grid is down*
- More than one million cumulative hours of testing
- Class II double-insulated
 enclosure
- Optimized for the latest highpowered PV modules

Microgrid-forming

- Complies with the latest advanced grid support**
- Remote automatic updates for the latest grid requirements
- Configurable to support a wide
 range of grid profiles
- Meets CA Rule 21 (UL 1741-SA)
 requirements
- * Only when installed with IQ System Controller 2, meets UL 1741.
- ** IQ8 and IQ8Plus supports split phase, 240V installations only.

IQ8 and IQ8+ Microinverters

| w v v | 235 - 350 60-cell/120 half-cell | 235 – 440 60-cell/120 half-cell, 66-cell/132 half-cell and 72-cell/144 |
|-------------|---|---|
| | 60-cell/120 half-cell | 60-cell/120 half-cell, 66-cell/132 half-cell and 72-cell/144 |
| | | half-cell |
| v | 27 - 37 | 29 - 45 |
| | 25 - 48 | 25 – 58 |
| v | 30 / 48 | 30 / 58 |
| v | 50 | 60 |
| A | 15 | 5 |
| | " | I Contraction of the second |
| mA | C |) |
| | 1x1 Ungrounded array; No additional DC side protection requi | ired; AC side protection requires max 20A per branch circuit |
| | IQ8-60-2-US | IQ8PLUS-72-2-US |
| VA | 245 | 300 |
| VA | 240 | 290 |
| V | 240 / 21 | 11 - 264 |
| А | 1.0 | 1.21 |
| Hz | 60 | 0 |
| Hz | 50 - | - 68 |
| Arms | 2 | 2 |
| | 16 | 13 |
| | <5 | % |
| | П | I |
| mA | 30 | 0 |
| | 1.0 | C |
| | 0.85 leading - | 0.85 lagging |
| % | 97.5 | 97.6 |
| % | 97 | 97 |
| mW | 60 | 0 |
| | | |
| | -40°C to +60°C (| -40°F to +140°F) |
| | 4% to 100% (| condensing) |
| | МС | 24 |
| | 212 mm (8.3") x 175 mm | (6.9") x 30.2 mm (1.2") |
| | 1.08 kg (2 | 2.38 lbs) |
| | Natural convec | ction – no fans |
| | Ye | es |
| | PC | 03 |
| | Class II double-insulated, corrosi | on resistant polymeric enclosure |
| | NEMA Туре (| 6 / outdoor |
| | | |
| (| CA Rule 21 (UL 1741-SA), UL 62109-1, UL1741/IEEE1547, FCC Part 1 | 5 Class B, ICES-0003 Class B, CAN/CSA-C22.2 NO. 107.1-01 |
| 6 | 690.12 and C22.1-2018 Rule 64-218 Rapid Shutdown of PV System | |
| | mA 1 VA 1 VA <td>Image: Amage: Amage:</td> | Image: Amage: |

 No enforced DC/AC ratio. See the compatibility calculator at https://link.enphase.com/module-compatibility
 Maximum continuous input DC current is 10.6A (3) Nominal voltage range can be extended beyond nominal if required by the utility. (4) Limits may vary. Refer to local requirements to define the number of microinverters per branch in your area. LSCO

TYPE

IPC

Insulation Piercing Connectors Dual Rated



Features

- Body is molded from tough, resilient glass-filled nylon
 Compact design
 Tin plated copper contact teeth
 Insulation piercing
 Per forated end tabs
 Provided with different kubricant

- Pre-filled with silicone lubricant
- Versatile
- Increased safety
- Horizontal line grid
 Temperature rating 90° C



Fig. 1





• Provides high degree of breakage resistance and long dependable use

Contains no external energized parts. Can be installed "hot" on energized con-ductors providing tap conductor is not under load.

Easily penetrates most types of insulation
No need to strip the conductor which saves installation time
Break out easily by hand
Prevents oxidation and moisture from entering the contact area
Can be used as a splice or tap connector
Contain and entering the contact area

Provides a visual guide for proper installation of conductors



Benefits

Saves space

| Catalog | Figure | Wire | Range | | Current | Rating | D | imension | S | Torque | Bolt Head |
|-------------|--------|-------------------|-------------------|-----------------------------|---------|--------|---------|----------|---------|----------|-----------|
| Number | Number | Main | Тар | Volts | CU | AL | L | W | H | Ft. Lbs. | Size |
| IPC-1/0-2 | 3 | 1/0-8 | 2-8 | 300 (480 Grounded Y System) | 130 | 100 | 1-7/32 | 1-15/32 | 2-5/16 | 16 | 1/2 |
| IPC-4/0-6 | 2 | 4/0-4 | 6-14 | 600 | 75 | 60 | 1-27/64 | 1 | 1-7/8 | 13 | 1/2 |
| IPC-4/0-2/0 | 3 | 4/0-2 | 2/0-6 | 600 | 195 | 150 | 1-21/32 | 1-7/8 | 2-7/8 | 25 | 1/2 |
| IPC-250-4/0 | 2 | 250kcmil-1 | 4/0-6 | 600 | 260 | 205 | 1-7/8 | 2-11/32 | 3-11/32 | 30 | 5/8 |
| IPC-350-4/0 | 3 | 350kcmil-4/0 | 4/0-10 | 300 (480 Grounded Y System) | 260 | 205 | 1-43/64 | 2-7/16 | 3-1/8 | 25 | 5/8 |
| IPC-350-350 | 4 | 350kcmil-4/0 | 350kcmil-4/0 | 300 (480 Grounded Y System) | 350 | 280 | 2-43/64 | 2-23/32 | 3-1/4 | 25 | 5/8 |
| IPC-500-12 | 1 | 500kcmil-250kcmil | 10-12 | 300 (480 Grounded Y System) | 40 | 35 | 1-43/64 | 2-7/16 | 3-1/4 | 25 | 5/8 |
| IPC-500-250 | 1 | 500kcmil-250kcmil | 250kcmil-4 | 600 | 290 | 230 | 2-27/64 | 2-29/32 | 3-3/4 | 55 | 5/8-11/16 |
| IPC-500-500 | 1 | 500kcmil-300kcmil | 500kcmil-250kcmil | 600 | 430 | 350 | 3-3/16 | 3-5/8 | 5 | 75 | 7/8-7/8 |
| IPC-750-500 | 1 | 750kcmil-500kcmil | 500kcmil-350kcmil | 600 | 430 | 350 | 3-3/16 | 3-5/8 | 5 | 75 | 7/8-7/8 |

All wire sizes, unless noted otherwise, are American Wire Gauge (AWG) Tested to UL 486A/B, UL File E6207



DocuSign Envelope ID: 4C077C38-FA98-419B-B651-E66DE9437930





BETTER SOLAR STARTS HERE

UNIRAC Code-Compliant Installation Manual

© 2022 by Unirac, Inc. All rights reserved.

UNIRAC welcomes input concerning the accuracy and user-friendliness of this publication. Please write to publications@unirac.com.

PUB2023FEB10



INSTALLATION GUIDE

TABLE OF CONTENTS


PRO SERIES SYSTEM

| PRO SERIES SYSTEM COMPONENTS 1 |
|---------------------------------------|
| SYSTEM COMPONENTS 2-3 |
| THERMAL BREAK |
| SYSTEM LAYOUT |
| ROOF ATTACHMENT & L-FEET |
| SPLICE |
| ATTACH RAIL TO L-FEET |
| MICROINVERTER MOUNTING |
| MICROINVERTER SYSTEM GROUNDING |
| SPLICE & THERMAL BREAK 11 |
| STANDARD SYSTEM GROUNDING12 |
| ENDCLAMP, FIRST MODULE |
| BONDING MIDCLAMP 14 |
| REMAINING MODULES |
| BONDING CONNECTION GROUND PATHS 16-17 |
| TRIM AND END CAP INSTALLATION |

STANDARD SERIES SYSTEM

| STANDARD SERIES SYSTEM COMPONENTS1 | 9 |
|--|---|
| STANDARD SERIES END & MID CLAMPS | 0 |
| ATTACH RAIL TO L-FEET | 1 |
| ENDCLAMP & FIRST MODULE | 2 |
| BONDING MIDCLAMP & TRIM | 3 |
| REMAINING MODULES & TRIM | 4 |
| TRIM RETROFIT INSTALLATION | 5 |
| BONDING CONNECTION GROUND PATHS 26-2 | |
| CODE COMPLIANCE NOTES | 8 |
| MECHANICAL LOAD TEST | 9 |
| SYSTEM LEVEL FIRE CLASSIFICATION | 0 |
| COMPATIBLE MODULES | 4 |
| APPENDIX A: FLASHKIT PRO INSTALLATION | 5 |
| APPENDIX B: FLASHLOC COMP INSTALLATION | 6 |
| APPENDIX C: FLASHLOC DUO INSTALLATION | 7 |
| APPENDIX D: UAF END & MID CLAMP INSTALLATION 38-34 | 9 |
| | |





| Wrenches and Torque | | | | |
|---------------------|-----------------------|--------------------------------|--|--|
| | Wrench or Socket Size | Recommended Torque (ft-lbs) | | |
| Mid Clamp 🛽 | 1/2" | 11 | | |
| MLPE Mount 9 | 1/2" | 10 | | |
| End Clamp 🛛 | 1/2" | 5 | | |
| L-Foot to Rail 🗿 | 1/2" | 30 | | |
| Rail Splice 🖲 | 1/2" | 10 | | |

Anti-Seize OO

Stainless steel hardware can seize up, a process called galling. To significantly reduce its likelihood: 1. Apply minimal lubricant to bolts only where indicated in installation process, preferably Anti-Seize commonly found at auto parts stores (Anti-seize has been factory applied to mid clamp bolts) 2. Shade hardware prior to installation, and 3. Avoid spinning stainless nuts onto bolts at high speed. **ORAIL**: Supports PV modules. Use at least two per row of modules. Aluminum extrusion, available in mill, clear anodized, or dark anodized.

OORAIL SPLICE: Non structural splice joins, aligns, and electrically bonds rail sections into single length of rail. Forms a rigid splice joint, 4 inches long, preassembled with bonding hardware. Available in dark anodized or mill finish.

QL-FOOT: Use to secure rails through roofing material to building structure. Refer to loading tables or U-Builder for spacing.

● L-FOOT T- BOLT: (3/8" x ¾" or 1") – Use one per L-foot to secure rail to L-foot. Stainless steel. Supplied with L-foot in combination with flange nut, provides electrical bond between L-foot and rail. OSERRATED FLANGE NUT : Use one per L-foot to secure and bond rail to L-foot. Stainless steel. Sup-

plied with L-foot. **MODULE ENDCLAMP**: Pre-assembled universal clamp that secures module to rail at module flange by tightening 1/2" hex head bolt.

©MODULE MIDCLAMP: Pre-assembled clamp provides module to module and module to rail bond. Aluminum clamp with stainless steel bonding pins and T-bolt. Available in clear or dark finish. **@MICROINVERTER MOUNTING BOLT**: Preassembled bolt, nut, and captive star washer attaches and bonds microinverter to rail.

NOTE - POSITION INDICATOR: T-bolts have a slot in the hardware end corresponding to the direction of the T-Head.

NOTE - Pro Series Mid and End Clamps are single use only



SYSTEM COMPONENTS 2 PAGE

RAILS

| ТҮРЕ | PART NUMBER | DESCRIPTION |
|-----------------|-------------|-------------------------|
| | 315168M | SM LIGHT RAIL 168" MILL |
| | 315168D | SM LIGHT RAIL 168" DRK |
| LIGHT RAIL | 315208M | SM LIGHT RAIL 208" MILL |
| | 315208D | SM LIGHT RAIL 208" DRK |
| | 315246M | SM LIGHT RAIL 246" MILL |
| | 315246D | SM LIGHT RAIL 246" DRK |
| | 320132M | SM RAIL 132" MILL |
| | 310132C | SM RAIL 132" CLR |
| | 320168M | SM RAIL 168" MILL |
| | 310168C | SM RAIL 168" CLR |
| STANDARD RAIL | 310168D | SM RAIL 168" DRK |
| STANDARD RAIL | 320208M | SM RAIL 208" MILL |
| | 310208C | SM RAIL 208" CLR |
| | 320246M | SM RAIL 246" MILL |
| | 310246C | SM RAIL 246" CLR |
| | 310246D | SM RAIL 246" DRK |
| | 410144M | SMHD, RAIL 144" MILL |
| HEAVY DUTY RAIL | 410168M | SMHD, RAIL 168" MILL |
| | 410204M | SMHD RAIL 204" MILL |
| | 410246M | SMHD, RAIL 246" MILL |

| SYMBOL | DESCRIPTION | LETTER | SUPPORTED MODULE | |
|----------|----------------------|--------|------------------|--|
| AL | ALUMINUM | | THICKNESS | |
| CLR | CLEAR ANODIZED | В | 30MM - 32MM | |
| DRK | DARK BRONZE ANODIZED | С | 33MM -36MM | |
| SS | STAINLESS STEEL | D | 38MM -40MM | |
| | BLACK OXIDE COATED | К | 39MM -41MM | |
| DRK SS | STAINLESS STEEL | F | 45MM -47MM | |
| <u> </u> | 1 | E | 50MM - 51MM | |

MID CLAMPS AND END CLAMPS

| S.NO. | PART NUMBER | DESCRIPTION |
|-------|-------------|-----------------------------|
| 1 | 302021C | SM ENDCLAMP B CLR AL |
| 2 | 302021D | SM ENDCLAMP B DRK AL |
| 3 | 302022C | SM ENDCLAMP C CLR AL |
| 4 | 302022D | SM ENDCLAMP C DRK AL |
| 5 | 302023C | SM ENDCLAMP D CLR AL |
| 6 | 302023D | SM ENDCLAMP D DRK AL |
| 7 | 302024C | SM ENDCLAMP E CLR AL |
| 8 | 302024D | SM ENDCLAMP E DRK AL |
| 9 | 302025C | SM ENDCLAMP F CLR AL |
| 10 | 302025D | SM ENDCLAMP F DRK AL |
| 11 | 302026C | SM ENDCLAMP K CLR AL |
| 12 | 302026D | SM ENDCLAMP K DRK AL |
| 13 | 302027C | SM BND MIDCLAMP BC SS |
| 14 | 302027D | SM BND MIDCLAMP BC DRK SS |
| 15 | 302028C | SM BND MIDCLAMP EF SS |
| 16 | 302028D | SM BND MIDCLAMP EF DRK SS |
| 17 | 302029C | SM BND MIDCLAMP DK SS |
| 18 | 302029D | SM BND MIDCLAMP DK DRK SS |
| 19 | 302030D | SM MIDCLAMP PRO DRK |
| 20 | 302030M | SM MIDCLAMP PRO MILL |
| 21 | 302035M | SM ENDCLAMP PRO W/CAP |
| 22 | 302045D | UNIVERSAL AF MID CLAMP DRK |
| 23 | 302045M | UNIVERSAL AF MID CLAMP MILL |
| 24 | 302050D | UNIVERSAL AF END CLAMP DRK |
| 25 | 302050M | UNIVERSAL AF END CLAMP MILL |



SYSTEM COMPONENTS A STALLATION GUIDE A PAGE

COMPONENTS

| S.NO. | PART NUMBER | DESCRIPTION |
|-------|-------------|----------------------------------|
| 1 | 303019M | BND SPLICE BAR PRO SERIES MILL |
| 2 | 303019D | BND SPLICE BAR PRO SERIES DRK |
| 3 | 304001C | L-FOOT SERR W/ T-BOLT, CLR |
| 4 | 304001D | L-FOOT SERR W/ T-BOLT, DRK |
| 5 | 0090105 | SPLICE TEK SCRW #12-14X3/4" SS |
| 6 | 0090205 | BND T-BOLT&NUT 3/8" X 3/4" SS |
| 7 | 0090215 | BND T-BOLT&NUT 3/8" X 1" SS |
| 8 | 004055M | FLASHKIT PRO, MILL 10 PK |
| 9 | 004055D | FLASHKIT PRO, DRK 10 PK |
| 10 | 004015D | SOLARMOUNT FLASHKIT PRO SB, DARK |
| 11 | 004015M | SOLARMOUNT FLASHKIT PRO SB, MILL |
| 12 | 004085M | FLASHLOC COMP KIT MILL |
| 13 | 004085D | FLASHLOC COMP KIT DRK |
| 14 | 004275M | FLASHLOC DUO MILL |
| 15 | 004275D | FLASHLOC DUO DARK |
| 16 | 003250W | #12-14 X 2.50 SCREW HDW SS SD |
| 17 | 004CT5H | SOLARHOOK UNIV SIDE MT CT5 |
| 18 | 004CT1H | SOLARHOOK SPANISH 7" BASE |
| 19 | 004CT2H | SOLARHOOK SPANISH 9" BASE |
| 20 | 004FLAT | SOLARHOOK FLASHING FLAT |
| 21 | 004FLCT | SOLARHOOK FLASHING SPANISH FLCT |
| 22 | 004AT1H | SOLARHOOK FLAT TILE |
| 23 | 004ST1S | SOLARHOOK STONE COATED MT ST1 |
| 24 | 004AST1 | SOLARHOOK ADJ STONE COATED ST1 |
| 25 | 004300M | STANDOFF 3" 2 PIECE AL, MILL |
| 26 | 004300D | STANDOFF 3" 2 PIECE AL, DRK |
| 27 | 004400M | STANDOFF 4" 2 PIECE AL, MILL |

| S.NO. | PART NUMBER | DESCRIPTION |
|-------|-------------|---------------------------------|
| 28 | 004400D | STANDOFF 4" 2 PIECE AL, DRK |
| 29 | 004600M | STANDOFF 6" 2 PIECE AL, MILL |
| 30 | 004600D | STANDOFF 6" 2 PIECE AL, DRK |
| 31 | 004700M | STANDOFF 7" 2 PIECE AL, MILL |
| 32 | 004700D | STANDOFF 7" 2 PIECE AL, DRK |
| 33 | 330007M | AL STNDOFF 3/8" BOLT&EPDMWSHR |
| 34 | 004013C | FLASH SOFT AL 18X18 OATEY 12836 |




THERMAL BREAK4INSTALLATION GUIDEPAGE

EXPANSION JOINT USED AS THERMAL BREAK

Expansion joints prevent buckling of rails or system failure due to thermal expansion. Determine location of expansion joints prior to installation of L-feet and rails. To create a thermal expansion joint, set gap between rails that is sufficient for proper installation of end clamps and tooling to achieve required torque. A thermal break is required when a continuous length of spliced rails exceeds the length, in feet, shown in the table to the right. For additional concerns on thermal breaks in your specific project, please consult a licensed structural engineer.

Rails in expansion joint configurations are considered cantilevered and must follow the cantilever rule, on both sides of the expansion joint, which states that the maximum amount of rail that can be cantilevered is 1/3 the respective adjacent span. An expansion joint must not be spanned by a PV module. Installing a module over an expansion joint would defeat the goal of a thermal break and could result in damage to the array.

Bonding connection for splice used as a thermal break. Option shown uses two Ilsco lugs (Model No. GBL-4DBT P/N GBL-4DBT - see product data sheet for more details) and solid copper wire. Optional grounding may be achieved through Enphase microinverter. See page 11.



| | Maximum Continuous Length (ft.) of Spliced Rails | | | | |
|---------|---|----------|---------------------|-----|--|
| | Solarmount Standard | | Solarmount Light | | |
| | Attachm | ent Span | Attachment Spa | | |
| ΔT (°F) | 48" 72" | | 48" | 72" | |
| 0-40 | 86 | 105 | 70 | 81 | |
| 40-50 | 70 | 93 | 62 | 81 | |
| 50-60 | 70 | 81 | 54 | 69 | |
| 60-70 | 62 | 69 | 54 | 69 | |
| 70-80 | 54 | 69 | 46 | 57 | |
| 80-90 | 54 | 69 | 46 | 57 | |
| 90-100 | 54 | 57 | 46 | 57 | |
| 100-120 | 46 | 57 | 38 | 45 | |
| 120-140 | 38 | 45 | 38 | 45 | |

The values displayed are the maximum allowed rail length, in feet, without a thermal break.

These values apply only to the Flashkit Pro L-foot. For Flashloc Comp Mount, or if your span is less than 48", refer to the Solarmount Design & Engineering Guide for max lengths of continuous rail before a thermal break is required. The installer is responsible for determining the maximum temperature difference (ΔT) used to establish the maximum rail length, without expansion joint, at the install location.

As spans increase, so does the maximum reaction force that the rail exerts on the L-foot. It is the responsibility of the installer to ensure that Maximum Reaction Force does not exceed the shear capacity of the roof connection. See SM Design and Engineering Guide for corresponding reaction forces.

 ΔT refers to the maximum difference in the temperature of the rail between installation and the extreme high or low temperature. The Extreme Annual Design Conditions table at the following url can be used as a reference when determining ΔT .

http://ashrae-meteo.info/



SYSTEM LAYOUT INSTALLATION GUIDE PAGE

PLANNING YOUR SOLARMOUNT INSTALLATIONS

The installation can be laid out with rails parallel to the rafters or perpendicular to the rafters. Note that SOLARMOUNT rails make excellent straight edges for doing layouts.

Center the installation area over the structural members as much as possible. Leave enough room to safely move around the array during installation. Some building codes and fire codes require minimum clearances around such installations, and the installer should check local building code requirements for compliance.

The length of the installation area is equal to:


Standard Series:

- the total width of the modules,
- plus 1/4" inch for each space between modules (for mid- clamp),
- plus approximately 3" (11/2 inches for each Endclamp)

Pro Series:

- the total width of the modules,
- plus 1" inch for each space between modules (for mid- clamp),
- plus 0 to 1" (0 to 1/2 inches for each Endclamp)

RAILS MAY BE PLACED PARALLEL OR PERPENDICULAR TO RAFTERS



LAYING OUT L-FEET FOR TOP CLAMPS

L-feet, in conjunction with proper flashing equipment and techniques, can be used for attachment through existing roofing material, such as asphalt shingles, sheathing or sheet metal to the building structure.


Locate and mark the position of the L-feet lag screw holes within the installation area as shown below. Follow manufacturer module installation guide for rail spacing based on appropriate mounting locations

NOTE: For expansion joint requirements, refer to page 4. Rail Lengths and locations of l-feet for expansion joints will need to be determined at this stage in planning system layout.

If multiple rows are to be installed adjacent to one another, it is not likely that each row will be centered above the rafters. Adjust as needed, following the guidelines below as closely as possible.

Refer to Unirac Solarmount D&E Guide & U-Builder for allowable spans and cantilevers.


LAYOUT WITH RAILS PERPENDICULAR TO RAFTERS (RECOMMENDED)




DocuSign Envelope ID: 4C077C38-FA98-419B-B651-E66DE9437930



ROOF ATTACHMENT & L-FEET INSTALLATION GUIDE PAGE




ROOF PREPARATION: Layout and install flashing at rafter locations determined per Design and Engineering Guide.




DRILL PILOT HOLES: Center the roof attachment over the rafter and drill a pilot hole(s) for the lag bolt(s).

NOTE: Determine lag bolt size and embedment depth.

Quick Tip: Pre-drill the pilot hole through the flat flashing lag bolt location for easier installation.




FLASHING INSTALLATION: Insert the flashing so the top part is under the next row of shingles and the hole lines up with the pilot hole.



INSTALL LAG BOLTS & L-FOOT: Insert the lag bolt through the L-Foot in the order shown in the illustration. Verify proper orientation before tightening lag bolts.

For high snow load conditions, install the L-foot as shown above, and install the rail on the downslope face of the L-Foot






2 PIECE ALUMINUM STANDOFF WITH FLASHING & L-FOOT:

- If necessary cut an opening in the roofing material over a rafter to accommodate the flashing riser.
- Install the standoff, ensuring that both lag bolts are screwed into the rafter.
- Insert the flashing under the shingle above and over the shaft of the standoff. (No-Calk[™] collar does not require sealing of the flashing and standoff shaft)
- Add L-Foot to top with bolt that secures the EPDM washer to the top of the standoff.

See Standoffs Installation Manual for Additional Details.



Side MOUNT SOLARHOOK:

- Remove or slide up the roof tile, position the roof hook above the roof rafter
- Place SolarHook in the middle of the underlying interlocking tile's valley. Drill 3/16 inch pilot holes through the underlayment into the center of the rafters. Securely fasten each tile hook to the rafters using included lag screws.
- Slide down or re-insert the tile.

See Unirac Solarhook Installation Manual for Additional Information.



SPLICE 7 INSTALLATION GUIDE


SPLICE INSTALLATION (IF REQUIRED PER SYSTEM DESIGN)

If your installation uses SOLARMOUNT splice bars, attach the rails together before mounting to the L-feet/footings. Use splice bars only with flush installation and those that use low-profile tilt legs. A rail must be supported by more than one footing on both sides of the splice. There can be a gap between rails, up to 3/16" at the splice connections. To install, slide T-feature on splice into the T-slot on each rail, centering the splice between the two rails. Tighten each bolt until the bolt-head is flush against the splice and torqued to 10 ft-lbs. Installation is complete when the bonding hardware penetrates the opposite side of the rail and the assembly torque is achieved. T-bolts should not be placed less than a distance of 1" from the end of the rail regardless of a splice.

TORQUE VALUE


Hex head socket size $\frac{1}{2}$ " – Do not exceed 10 ft-lbs. Do not use Anti-Seize. See table on page 4 for max length of spliced rails. An expansion joint is required above the lengths published in the table.


Rails in splice joint configurations are considered cantilevered and must follow the cantilever rule, on both sides of the splice, which states that the maximum amount of rail that can be cantilevered is 1/3 the respective adjacent span. See table on page 4.






ATTACH RAIL TO L-FEET 8 INSTALLATION GUIDE PAGE





PLACE T-BOLT INTO RAIL & SECURE BOLT: Insert 3/8" T-bolt into rail at L-foot locations. Apply Anti-Seize to bolt. Rotate T-bolt into position.

SECURE T-BOLT: Apply Anti-Seize to bolt. Rotate T-bolt into position.




ALIGN POSITION INDICATOR: Hand tighten nut until rail alignment is complete. Verify that position indicator on bolt is vertical (perpendicular to rail)

TORQUE VALUE: 3/8" nut to 30 ft-lbs

ALIGN RAILS: Align one pair of rail ends to the edge of the installation area. The opposite pair of rail ends will overhang installation area. Do not Trim them off until the installation is complete. If the rails are perpendicular to the rafters, either end of the rails can be aligned, but the first module must be installed at the aligned end.

If the rails are parallel to the rafters, the aligned end of the rails must face the lower edge of the roof. Securely tighten all hardware after alignment is complete.


Mount modules to the rails as soon as possible. Large temperature changes may bow the rails within a few hours if module placement is delayed.




DocuSign Envelope ID: 4C077C38-FA98-419B-B651-E66DE9437930




MICROINVERTER MOUNTING 9 INSTALLATION GUIDE PAGE



INSTALL MICROINVERTER MOUNT T-BOLT: Apply Anti-Seize and install pre-assembled ¼" dia. bonding T-bolts into top ¼" rail slot at microinverter locations. Rotate bolts into position.




INSTALL MICROINVERTER: Install microinverter on to rail. Engage with bolt.




INSTALL MICROINVERTER:

TORQUE VALUE 1/4" nut to 10 ft-lbs with Anti-Seize.



ALIGN POSITION INDICATOR: Verify that position indicator on bolt is perpendicular to rail.

MICROINVERTER SYSTEM GROUNDING Installation guide Page



SM EQUIPMENT GROUNDING THROUGH ENPHASE MICROINVERTERS


The Enphase M215 and M250 microinverters have integrated grounding capabilities built in. In this case, the DC circuit is isolated from the AC circuit, and the AC equipment grounding conductor (EGC) is built into the Enphase Engage integrated grounding (IG) cabling.

In order to ground the SOLARMOUNT racking system through the Enphase microinverter and Engage cable assembly, there must be a minimum of three PV modules connected to the same trunk cable within a continuous row. Continuous row is defined as a grouping of modules installed and bonded per the requirements of this installation guide sharing the same two rails. The microinverters are bonded to the SOLARMOUNT rail via the mounting hardware. Complete equipment grounding is achieved through the Enphase Engage cabling with integrated grounding (IG). No additional EGC grounding cables are required, as all fault current is carried to ground through the Engage cable.






ELECTRICAL GROUNDING W/ SPLICE & THERMAL BREAK ENPHASE MICROINVERTER FOR SPLICE & THERMAL BREAK ENPHASE FOR SPLICE & THERMA ENPHASE FOR SPLICE & THERMAL BREAK ENPHASE FOR SPLICE & THERMA ENPHASE FOR SPLICE



ELECTRICAL BONDING SPLICE

EXPANSION JOINT USED AS THERMAL BREAK W/ GROUNDING LUGS & COPPER JUMPER EXPANSION JOINT USED AS THERMAL BREAK W/O ELECTRICAL BONDING CONNECTION





GROUNDING LUG MOUNTING DETAILS:


Details are provided for both the WEEB and Ilsco products. The WEEBLug has a grounding symbol located on the lug assembly. The Ilsco lug has a green colored set screw for grounding indication purposes. Installation must be in accordance with NFPA NEC 70, however the electrical designer of record should refer to the latest revision of NEC for actual grounding conductor cable size.

Required if not using approved integrated grounding microinveters

| GROUNDING LUG - BOLT SIZE & DRILL SIZE | | | | | |
|--|-----------|---------------------------------|--|--|--|
| GROUND LUG | BOLT SIZE | DRILL SIZE | | | |
| WEEBLug | 1/4" | N/A - Place in Top SM Rail Slot | | | |
| ILSCO Lug | #10-32 | 7/32" | | | |

• Torque value depends on conductor size.


• See product data sheet for torque value.



WEEBLUG CONDUCTOR - UNIRAC P/N 008002S:

Apply Anti Seize and insert a bolt in the aluminum rail and through the clearance hole in the stainless steel flat washer. Place the stainless steel flat washer on the bolt, oriented so the dimples will contact the aluminum rail. Place the lug portion on the bolt and stainless steel flat washer. Install stainless steel flat washer, lock washer and nut. Tighten the nut until the dimples are completely embedded into the rail and lug.

TORQUE VALUE 10 ft lbs. See product data sheet for more details, Model No. WEEB-LUG-6.7




ILSCO LAY-IN LUG CONDUCTOR - UNIRAC P/N 008009P: Alternate Grounding Lug - Drill, deburr hole and bolt thru both rail walls per table. TORQUE VALUE 5 ft lbs.

See ILSCO product data sheet for more details, Model No. GBL-4DBT.

NOTE: ISOLATE COPPER FROM ALUMINUM CONTACT TO PREVENT CORROSION




INSTALL MODULE END CLAMPS: The End clamp is supplied as an assembly with a 1/2" hex head bolt Slide end clamp on to rail by that is accessible at the ends of rails. The clamp should be installed on the rails prior to installing end modules.



INSTALL END CLAMPS ON RAIL: engaging the two t-guide brackets with the top slot of the rails. Ensure bolt is extended as far as possible so that clamp is positioned at max. distance from end of rail.




POSITION END CLAMPS: Slide end clamp assembly on to rail until bolt head engages with end of rail End clamps are positioned on rails prior to the first end module and prior to the last end module.



ENDCLAMP, FIRST MODULE INSTALLATION GUIDE PAGE


NOTE: To assist insertion of clamp into rail slot, Pressure may be applied to top or side of bracket as shown. Do not force clamp into rail by pushing on bolt with excessive force.




INSTALL FIRST MODULE:

Install the first end module onto rails with the flange of the module frame positioned between end clamps an ends of rails.






ENGAGE CLAMP: While holding module in position and with flange in full contact with rail, rotate end clamp bolt until clamp engages with flange to provide clamp force. To ensure bolt is not over-torqued, use low torque setting on drill or If using an impact driver, stop rotation as soon as impact action of driver begins. **TORQUE VALUE** End clamp bolt to 5 ft-lbs, No anti-seize







BONDING MIDCLAMP INSTALLATION GUIDE PAGE




INSTALL MIDCLAMPS: Midclamp is supplied as an assembly with a T-bolt for module installation. Clamp assemblies may be positioned in rail near point of use prior to module placement.




INSERT MIDCLAMP ASSEMBLY: Insert 1/4" T-Bolt into top slot of rail



MIDCLAMP: Rotate midclamp assembly and slide until clamp is against module frame. Do not tighten nut until next module is in position. Ensure bolt is perpendicular to rail.



PLACE ADJACENT MODULE AGAINST CLAMPS: Modules must be tight against clamps with no gaps. Tighten nut to required torque.




POSITION INDICATOR - SERRATED T-BOLT: Verify the T-bolt position indicator is perpendicular to the rail.


TORQUE VALUE: 11 ft-lbs. No anti-seize.



REMAINING MODULES INSTALLATION GUIDE PAGE




INSTALL REMAINING MID-CLAMPS: Proceed with module installation. Engage each module with previously positioned Midclamp assemblies.



POSITION T-BOLT ALIGNMENT MARKS: Verify that the position indicator(s) & T-bolt shaft(s) are angled in the correct position. Tighten to final torque.


TORQUE VALUE: 11 ft-lbs. No anti-seize.



FINISH MODULE INSTALLATION: Proceed with module installation. Engage each module with the previously positioned clamp assembly:

DocuSign Envelope ID: 4C077C38-FA98-419B-B651-E66DE9437930

SMSOLAR BONDING CONNECTION GROUND PATHS INSTALLATION GUIDE PAGE






BONDING MIDCLAMP ASSEMBLY

BONDING MIDCLAMP ASSEMBLY


- 1 Aluminum mid clamp with stainless steel bonding pins that pierce module frame anodization to bond module to module through clamp
- 2 Stainless steel nut bonds aluminum clamp to stainless steel T-bolt
- Serrated T-bolt head penetrates rail anodization to bond T-bolt, nut, clamp, and modules to SM rail



BONDING RAIL SPLICE BAR


- Bonding Hardware creates bond between splice bar and each rail section
- 2 Aluminum splice bar spans across rail gap to create rail to rail bond. Rail on at least one side of splice will be grounded.


Note: Splice bar and bolted connection are non-structural. The splice bar function is rail alignment and bonding.



RAIL TO L-FOOT w/BONDING T-BOLT


- Serrated flange nut removes L-foot anodization to bond L-Foot to stainless steel T-bolt
- Serrated T-bolt head penetrates rail anodization to bond T-bolt, nut, and L-foot to grounded SM rail





BONDING MICROINVERTER MOUNT

- Hex nut with captive lock washer bonds metal microinverter flange to stainless steel T-bolt
- Serrated T-bolt head penetrates rail anodization to bond T-bolt, nut, and L-foot to grounded SM rail System ground including racking and modules may be achieved through the trunk cable of approved microinverter systems. See page 11 for details





RACK SYSTEM GROUND

WEEB washer dimples pierce anodized rail to create bond between rail and lug

Solid copper wire connected to lug is routed to provide final system ground connection. NOTE: Ilsco lug can also be used when secured to the side of the rail. See page 12 for details

SMSOLAR BONDING CONNECTION GROUND PATHS INSTALLATION GUIDE PAGE





TEMPORARY BONDING CONNECTION DURING ARRAY MAINTENANCE

When removing modules for replacement or system maintenance, any module left in place that is secured with a bonding Midclamp will be properly grounded. If a module adjacent to the end module of a row is removed or if any other maintenance condition leaves a module without a bonding mid clamp, a temporary bonding connection must be installed as shown

- Attach Ilsco SGB4 to wall of rail
- Attach Ilsco SGB4 to module frame
- Install solid copper wire jumper to Ilsco lugs

ELECTRICAL CONSIDERATIONS

SOLARMOUNT is intended to be used with PV modules that have a system voltage less than or equal to that allowable by NEC. For standard system grounding a minimum 10AWG, 105°C copper grounding conductor should be used to ground a system, according to the National Electric Code (NEC). It is the installer's responsibility to check local codes, which may vary. See below for interconnection information.

INTERCONNECTION INFORMATION

There is no size limit on how many SOLARMOUNT & PV modules can be mechanically interconnected for any given configuration, provided that the installation meets the requirements of applicable building and fire codes.

GROUNDING NOTES

The installation must be conducted in accordance with the National Electric Code (NEC) and the authority having jurisdiction. Please refer to these resources in your location for required grounding lug quantities specific to your project.


The grounding / bonding components may overhang parts of the array so care must be made when walking around the array to avoid damage.

Conductor fastener torque values depend on conductor size. See product data sheets for correct torque values.

PERIODIC INSPECTION: Conduct periodic inspections for loose components, loose fasteners or any corrosion, immediately replace any affected components.




TRIM AND END CAP INSTALLATION18INSTALLATION GUIDEPAGE




TRIM MIDCLAMPS: Ensure Trim lip is in contact with module face and verify alignment marks on T-bolts are in proper position, tighten midclamp on Trim, repeat at each gap between modules.

TORQUE VALUE: 11 ft-lbs. No anti-seize.



FINISH TRIM INSTALLATION. CUT EXCESS TRIM AND INSTALL TRIM CLIPS:


Attach trim to modules with at least one trim clip at each end of array and at locations where additional support is needed. Each section of trim must be attached to modules with at least one mid clamp.



INSTALL END CAPS: End caps install as supplied on SM standard rail and SM light rail. If desired for SM light rail, the end cap may be modified as shown by hand, or by using a cutting tool.



STANDARD SYSTEM COMPONENTS SERIES INSTALLATION GUIDE PAGE



| Wrenches and Torque | | | | |
|---------------------|-------------|--------------------------------|--|--|
| | Wrench Size | Recommended Torque (ft-lbs) | | |
| 1/4" Hardware 🛛 🕄 🕄 | 7/16" | *10 | | |
| 3/8" Hardware 🛛 | 9/16" | *30 | | |
| #12 Hardware | 5/16" | 10 | | |

Torques are not designed for use with wood connectors *w/Anti-Seize.

Anti-Seize*

Stainless steel hardware can seize up, a process called galling. To significantly reduce its likelihood: 1. Apply minimal lubricant to bolts, preferably Anti-Seize commonly found at auto parts stores 2. Shade hardware prior to installation, and 3. Avoid spinning stainless nuts onto bolts at high speed. **ORAIL**: Supports PV modules. Use at least two per row of modules. Aluminum extrusion, available in mill, clear anodized, or dark anodized.

OORAIL SPLICE: Non structural splice joins, aligns, and electrically bonds rail sections into single length of rail. Forms a rigid splice joint, 4 inches long, preassembled with bonding hardware. Available in dark anodized or mill finish.

QL-FOOT: Use to secure rails through roofing material to building structure. Refer to loading tables or U-Builder for spacing.

OMODULE ENDCLAMP: Provides bond from rail to endclamp. Pre-assembled aluminum clamp available in clear or dark finish. Supplied washer keeps clamp and bolt upright for ease of assembly.

©MODULE MIDCLAMP: Pre-assembled clamp provides module to module and module to rail bond. Stainless steel clamp and T-bolt. Available in clear or dark finish.

OMICROINVERTER MOUNTING BOLT: Pre-assembled bolt and nut attaches and bonds microinverter to rail. Washer at base keeps bolt upright for ease of assembly.


NOTE - POSITION INDICATOR: T-bolts have a slot in the hardware end corresponding to the direction of the T-Head.

NOTE - Standard Series Mid and End Clamps are single use.

DocuSign Envelope ID: 4C077C38-FA98-419B-B651-E66DE9437930





SM SOLAR MOUNT






ATTACH RAIL TO L-FEET 21 INSTALLATION GUIDE PAGE





PLACE T-BOLT INTO RAIL & SECURE BOLT: Insert 3/8" T-bolt into rail at L-foot locations. Apply Anti-Seize to bolt. Rotate T-bolt into position.

SECURE T-BOLT: Apply Anti-Seize to bolt. Rotate T-bolt into position.




ALIGN POSITION INDICATOR: Hand tighten nut until rail alignment is complete. Verify that position indicator on bolt is vertical (perpendicular to rail)

TORQUE VALUE: 3/8" nut to 30 ft-lbs

ALIGN RAILS: Align one pair of rail ends to the edge of the installation area. The opposite pair of rail ends will overhang installation area. Do not Trim them off until the installation is complete. If the rails are perpendicular to the rafters, either end of the rails can be aligned, but the first module must be installed at the aligned end.


If the rails are parallel to the rafters, the aligned end of the rails must face the lower edge of the roof. Securely tighten all hardware after alignment is complete.

Mount modules to the rails as soon as possible. Large temperature changes may bow the rails within a few hours if module placement is delayed.







ENDCLAMP & FIRST MODULE INSTALLATION GUIDE PAGE



INSTALL MODULE ENDCLAMPS: The Endclamp is supplied as an assembly with a T-bolt, serrated flange nut, and washer. The washer retains the clamp at the top of the assembly. This will enable the clamp to remain upright for module installation.




INSERT ENDCLAMP T-BOLT: Insert 1/4" T-bolt into rail.




ROTATE ENDCLAMP T-BOLT: Rotate T-bolt into position. Verify that the position indicator & T-bolt shaft are angled in the correct position.

End clamps are positioned on rails prior to the first end module and installed after the last end module.




INSTALL FIRST MODULE: Install the first end module onto rails. Engage module frame with Endclamps. Verify that the position indicator & T-bolt shaft are angled in the correct position.






POSITION INDICATOR - SERRATED T-BOLT: Verify the T-bolt position indicator is perpendicular to the rail.




POSITION INDICATOR - NON-SERRATED T-BOLT: Verify the T-bolt position indicator is angled as shown. **FOR USE WITH MILL FINISH RAIL ONLY**.




BONDING MIDCLAMP & TRIM INSTALLATION GUIDE PAGE




INSTALL MIDCLAMPS: Midclamp is supplied as an assembly with a T-bolt for module installation. Clamp assemblies may be positioned in rail near point of use prior to module placement.



INSERT MIDCLAMP T-BOLT: Apply Anti-Seize and insert 1/4" T-bolt into rail.




ROTATE MIDCLAMP T-BOLT: Rotate bolt into position and slide until bolt and clamp are against module frame. Do not tighten nut until next module is in position. Verify that the position indicator & T-bolt shaft are angled in the correct position.



POSITION INDICATOR - SERRATED T-BOLT: Verify the T-bolt position indicator is perpendicular to the rail.

TRIM INSTALLATION INSTRUCTIONS




TRIM MIDCLAMPS: Ensure Trim lip is in contact with module face and verify alignment marks on T-bolts are in proper position, tighten midclamp on Trim, repeat at each gap between modules.

TORQUE VALUE: 1/4" nuts to 10 ft-lbs with Anti Seize

DocuSign Envelope ID: 4C077C38-FA98-419B-B651-E66DE9437930




REMAINING MODULES & TRIM INSTALLATION GUIDE PAGE




INSTALL REMAINING MID-CLAMPS: Proceed with module installation. Engage each module with previously positioned Midclamp assemblies.

NOTE: Apply Anti-Seize to each Mid Clamp prior to installation.




POSITION T-BOLT ALIGNMENT MARKS: Verify that the position indicator(s) & T-bolt shaft(s) are angled in the correct position.

TORQUE VALUE: 1/4" nuts to 10 ft-lbs. with Anti Seize




INSTALL ENDCLAMPS: Apply Anti-Seize and install final Endclamps in same manner as first Endclamps. Slide clamps against module.

TORQUE VALUE: 1/4" nuts to 10 ft-lbs. with Anti Seize.




POSITION T-BOLT ALIGNMENT MARKS & CUT RAIL: Verify that the position indicator(s) & T-bolt shaft(s) are angled in the correct position. Trim off any excess rail, being careful not to cut into the roof. Allow ½" between the Endclamp and the end of the rail.



FINISH MODULE INSTALLATION: Proceed with module installation. Engage each module with the previously positioned clamp assembly:

- Install second module
- Install remaining Midclamps & modules & position alignment marks
- Install Endclamps & position alignment marks
- Cut rail to desired length

TRIM INSTALLATION INSTRUCTIONS



FINISH TRIM INSTALLATION, INSTALL ENDCLAMP & CUT EXCESS RAIL:


Install final endclamp & Cut away excess Trim at end of array or where required for proper cantilevers. See D&E Guide or U-Builder for allowable cantilevers.

TORQUE VALUE 1/4" nuts to 10 ft-lbs with Anti Seize


DocuSign Envelope ID: 4C077C38-FA98-419B-B651-E66DE9437930



TRIM RETROFIT INSTALLATION GUIDE25INSTALLATION GUIDEPAGE




PREPARATION: At front edge of array, ensure at least 3.25 inches of space between modules and roof surface and that modules are aligned to within 3/8". Plan for Trim length so that Endclamps can be properly installed.




1ST MIDCLAMP: Position Trim in front of array. Insert Midclamp into the Trim slot, aligned with the gap between the 1st two modules at either end of array.

NOTE: Apply Anti-Seize to Each Mid-Clamp prior to installation




MOUNT TRIM: Position Trim beneath modules by sliding T-bolt into gap between modules and tighten. Midclamp should stay in position and support Trim. Tighten snugly enough so that Trim is held firmly in place.


TORQUE VALUE: Do not exceed specified torque value (10 ft-lbs)



CLEAR T-BOLT SLOT: Rotate unattached end of Trim out and away from array so T-bolt slot (at next T-bolt insertion point) is clear of modules. This may require force to deflect the Trim slightly. Deflect only enough to insert T-bolt.




INSERT MIDCLAMPS: Insert T-bolt into slot and slide clamp (rotating Trim) into position between modules and leave loose. Continue to work down array, inserting Midclamps and positioning in gaps between modules.




FASTEN MIDCLAMPS: Return to each inserted Midclamp. Ensuring Trim lip is in contact with module face and verifying alignment marks on T-bolts are in proper position, tighten clamp.

TORQUE VALUE 1/4" nuts to 10 ft-lbs w/ Anti Seize




ENDCLAMPS: Install Endclamps per previous Endclamp install instructions

TORQUE VALUE 1/4" nuts to 10 ft-lbs w/ Anti Seize




CUT EXCESS TRIM: Mark excess Trim and cut at end of array or where required for proper cantilevers.

SMSOLAR BONDING CONNECTION GROUND PATHS INSTALLATION GUIDE PAGE



BONDING MIDCLAMP ASSEMBLY

- Stainless steel Midclamp points, 2 per module, pierce module frame anodization to bond module to module through clamp.
- 2 Serrated flange nut bonds stainless steel clamp to stainless steel T-bolt
- Serrated T-bolt head penetrates rail anodization to bond T-bolt, nut, clamp, and modules to grounded SM rail.




ENDCLAMP ASSEMBLY

Serrated flange nut bonds aluminum Endclamp
to stainless steel T-bolt

 Serrated T-bolt head penetrates rail anodization
 to bond T-bolt, nut, and Endclamp to grounded SM rail

Note: End clamp does not bond to module frame.




BONDING RAIL SPLICE BAR

Bonding Hardware creates bond between splice bar and each rail section


Aluminum splice bar spans across rail gap to create rail to rail bond. Rail on at least one side of splice will be grounded.


Note: Splice bar and bolted connection are non-structural. The splice bar function is rail alignment and bonding.



RAIL TO L-FOOT w/BONDING T-BOLT

- Serrated flange nut removes L-foot anodization to bond L-Foot to stainless steel T-bolt
- Serrated T-bolt head penetrates rail anodization to bond T-bolt, nut, and L-foot to grounded SM rail






BONDING MICROINVERTER MOUNT

Hex nut with captive lock washer bonds metal microinverter flange to stainless steel T-bolt

Serrated T-bolt head penetrates rail anodization to bond T-bolt, nut, and L-foot to grounded SM rail System ground including racking and modules may be achieved through the trunk cable of approved microinverter systems. See page 11 for details




RACK SYSTEM GROUND

1 WEEB washer dimples pierce anodized rail to create bond between rail and lug

2 Solid copper wire connected to lug is routed to provide final system ground connection.

NOTE: Ilsco lug can also be used when secured to the side of the rail. See page 11 for details

SMSOLAR BONDING CONNECTION GROUND PATHS INSTALLATION GUIDE PAGE



TEMPORARY BONDING CONNECTION DURING ARRAY MAINTENANCE

When removing modules for replacement or system maintenance, any module left in place that is secured with a bonding Midclamp will be properly grounded. If a module adjacent to the end module of a row is removed or if any other maintenance condition leaves a module without a bonding mid clamp, a temporary bonding connection must be installed as shown

- Attach Ilsco SGB4 to wall of rail
- Attach Ilsco SGB4 to module frame
- Install solid copper wire jumper to Ilsco lugs

ELECTRICAL CONSIDERATIONS

SOLARMOUNT is intended to be used with PV modules that have a system voltage less than or equal to that allowable by the NEC. For standard system grounding a minimum 10AWG, 105°C copper grounding conductor should be used to ground a 1000 VDC system, according to the National Electric Code (NEC). It is the installer's responsibility to check local codes, which may vary. See below for interconnection information.

INTERCONNECTION INFORMATION

There is no size limit on how many SOLARMOUNT & PV modules can be mechanically interconnected for any given configuration, provided that the installation meets the requirements of applicable building and fire codes.

GROUNDING NOTES

The installation must be conducted in accordance with the National Electric Code (NEC) and the authority having jurisdiction. Please refer to these resources in your location for required grounding lug quantities specific to your project.

The grounding / bonding components may overhang parts of the array so care must be made when walking around the array to avoid damage.

Conductor fastener torque values depend on conductor size. See product data sheets for correct torque values.




CODE COMPLIANCE NOTES INSTALLATION GUIDE **28** PAGE

UL2703 CERTIFICATION MARKING LABEL

Unirac SOLARMOUNT is listed to UL 2703. Certification marking is embossed on all mid clamps as shown. Labels with additional information will be provided . After the racking system is fully assembled, a single label should be applied to the SOLARMOUNT rail at the edge of the array. Before applying the label, the corners of the label that do not pertain to the system being installed must be removed so that only the installed system type is showing. **Note: The sticker label should be placed such that it is visible, but not outward facing.**









MECHANICAL LOAD TEST SYSTEM CERTIFICATION PAGE

The SOLARMOUNT system has been certified and listed to the UL 2703 standard (Rack Mounting Systems and Clamping Devices for Flat-Plate Photovoltaic Modules and Panels). This standard included electrical grounding, electrical bonding, mechanical load and fire resistance testing.

In conducting these tests, specific modules are selected for their physical properties so that the certifications can be broadly applied. The following lists the specific modules that were tested and the applicability of those certifications to other modules that might come onto the market. PV modules may have a reduced mechanical load rating, independent of the SM load rating. Please consult the PV module manufacturer's installation guide for more information.

In addition to UL 2703 certification, Unirac performs internal testing beyond the requirements of certification tests in order to establish system functional limits, allowable loads, and factors of safety. These tests include functional system tests, and destructive load testing.

MECHANICAL LOAD TEST MODULES

The modules selected for UL 2703 mechanical load testing were selected to represent the broadest range possible for modules on the market. The tests performed cover the following basic module parameters:

Frame thicknesses greater than or equal to 1.0 mm

Basic single and double wall frame profiles (some complex frame profiles could require further analysis to determine applicability) Clear and dark anodized aluminum frames`

| Tested Modules | | | | | |
|------------------------|-----------------|----------------|--|--|--|
| Module Manufacturer | Model/Series | Area [sqft] | UL2703 Certification Load Ratings | | |
| Hyundai | HiS-S325TI | 21.06 | Down– 113 PSF, Up – 50 PSF Down-Slope – 15 PSF | | |
| SunPower | SPR-P19-395-COM | 22.20 | Down– 113 PSF, Up – 50 PSF Down-Slope – 15 PSF | | |
| First Solar | FS-6xxx-P | 27.12 | Down– 33.9 PSF, Up – 33.9 PSF Down-Slope – 16.5 PSF | | |



SYSTEM LEVEL FIRE CLASSIFICATION SYSTEM CERTIFICATION PAGE

SYSTEM LEVEL FIRE CLASSIFICATION

The system fire class rating requires installation in the manner specified in the SOLARMOUNT Installation Guide. SOLARMOUNT has been classified to the system level fire portion of UL2703. SOLARMOUNT has achieved system level performance for steep sloped roofs and low sloped roofs. See table below for definition of steep sloped and low sloped roofs. The system is to be mounted over fire resistant roof covering rated for the application. There is no required minimum or maximum height limitation above the roof deck to maintain the system fire rating for SOLARMOUNT. Module Types, System Level Fire Ratings, & Mitigation Requirements are listed below:

| ROOF TYPE | Rail Type | Module Fire Type | System Level Fire Rating | Rail Direction | Module Orientation | Mitigation Required |
|---|-------------------------------|---|-----------------------------|---|--------------------------|--|
| | Standard & HD Rail | 1, 2, 3 with metal frame, 10 with metal frame, 19, 22, 25, 29, & 30 | Class A | Parallel OR Perpendic- ular to Ridge | Landscape OR Portrait | None Required |
| Steep Slope - roof pitches ≥ 2 in/ft | Light Rail | 1 & 2 | | | | None Required |
| | Standard, Light, & HD Rail | 4 & 5 | | | | Trim installation per Solar Mount Installation Guide |
| | Standard & HD Rail | | | | Landscape OR Portrait | |
| Low Slope - roof | Light Rail | Type 1, 2, 29, & 30 | | Parallel OR Perpendic- ular to Ridge | | None Required |
| pitches < 2in/ft | Standard, Light, & HD Rail | .,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,, | | | | |

This racking system may be used to ground and/or mount a PV module complying with UL1703 or UL61730 only when the specific module has been evaluated for grounding and/or mounting in compliance with the included instructions.



Electrical Bonding and Grounding Test Modules

The list below is not exhaustive of compliant modules but shows those that have been evaluated and found to be electrically compatible with the SOLARMOUNT system.

| Manufacture | Module Model / Series | Manufacture | Module Model / Series | Manufacture | Module Model / Series |
|----------------|---|----------------------------------|---|----------------|---|
| Aionrise | AION60G1, AION72G1 | | CS5A-M CS6K-(M/MS/MS AllBlack/P/P HE) | | HT60-156M-C HT60-156M(V)-C HT72-156(M/P) HT72-156P-C, HT72-156P(V)-C HT72-156M(PDV)-BF, HT72-156M(PD)-BF HT72-166M, HT72-18X |
| Aleo | P-Series & S-Series DNA-120-(MF/BF)10-xxxW DNA-120-MF10 DNA-120-(MF/BF)23 | - CS6F Canadian Solar (cont.) | CS6P-(M/P) CS6P-(M/P) CS6R-MS CS6U-(M/P/P HE) CS6W-(MS/MB-AG) | HT-SAAE | |
| Aptos Solar | DNA-144-(MF/BF)23 DNA-120-(MF/BF)26 | | CS6X-P, CSX-P ELPS CS6(A/P)-MM | Hyperion Solar | HY-DH108P8 |
| | DNA-144-(MF/BF)26 DNA-108-(MF/BF)10-xxxW | Centrosolar America | C-Series & E-Series | _ | KG, MG, RW, TG, RI, RG, TI, KI, HI Series HiA-SxxxHG, HiD-SxxxRG(BK), HiS-S400PI |
| Astronergy | CHSM6612 M, M/HV CHSM6612P Series CHSM6612P/HV Series | CertainTeed | CT2xxMxx-01, CT2xxPxx-01, CTxxxMxx-01 CTxxxPxx-01, CTxxxMxx-02, CTxxxMxx-03 CTxxxMxx-04, CTxxxHC11-04 | Hyundai | HIA-SXXXHG, HID-SXXXKG(BK), HIS-S400PI HIS-SXXXYH(BK) HIS-SXXXG(BK) HIN-SXXXG(BK) |
| 57 | CHSM72M-HC CHSM72M(DG)/F-BH AXN6M610T AXN6P610T AXN6M612T AXN6P612T | Eco Solargy | Orion 1000 & Apollo 1000 | | iT-SE Series |
| Auxin | | EMMVEE | ExxxP72-B ExxxM72-B ExxxH CM120-B | Japan Solar | |
| | | ET Solar | ET AC Module, ET Module ET-M772BH520-550WW/WB | | JPS-60 & JPS-72 Series |
| Axitec | AC-xxx(M/P)/60S, AC-xxx(M/P)/72S AC-xxxP/156-60S AC-xxxMH/120(S/V/SB/VB) AC-xxxMH/144(S/V/SB/VB) | First Solar | FS-6XXX(A) FS-6XXX(A)-P,FS-6XXX(A)-P-I | | JAM72D30MB, JAM78D10MB JAM72S30 /MR JAP6 60-xxx JAM6(K)-60/xxx, JAP6(k)-72-xxx/4BB JAP72S##-xxx/** JAP6(k)-60-xxx/4BB, JAP60S##-xxx/** JAM6(k)-72-xxx/**, JAM72S##-xxx/** JAM6(k)-60-xxx/**, JAM60S##-xxx/** |
| | | Flextronics | FXS-xxxBB | | |
| Boviet | BVM6610, BVM6612 | Freedom Forever | FF-MP-BBB-xxx, FF-MP1-BBB-xxx | | |
| BYD | P6K & MHK-36 Series | FreeVolt | PVGraf | JA Solar | |
| | CS1(H/K/U/Y)-MS | GCL | GCL-P6 & GCL-M6 Series | | |
| | CS3K-(MB/MB-AG/MS/P/P HE/PB-AG) CS3L-(MS/P) | Hansol | TD-AN3, TD-AN4 UB-AN1, UD-AN1 | | i. ##: 01, 02, 03, 09, 10 ii. **: SC, PR, BP, HiT, IB, MW, MR |
| Canadian Solar | CS3N-MS CS3U-(MB/MB-AG/MS/P/P HE/PB/PB-AG) | Hanwha SolarOne | HSL 60 | | ** = Backsheet, ## Cell technology |
| | CS3U-(MB/MB-AG/MS/P/P HE/PB/PB-AG) CS3W-(MS/MB-AG/P/P-PB-AG) CS3Y-MB-AG | Heliene | 36M, 36P 60M, 60P, 72M & 72P Series 144HC M6 144HC M10 SL Bifacial | | |

• Unless otherwise noted, all modules listed above include all wattages and specific models within that series. Variable wattages are represented as "xxx"

• Items in parenthesis are those that may or may not be present in a compatible module's model ID

• Slashes "/" between one or more items indicates that either of those items may be the one that is present in a module's model ID

• The frame profile must not have any feature that might interfere with the bonding devices that are integrated into the racking system

• Use with a maximum over current protection device OCPD of 30A

• Listed models can be used to achieve a Class A fire system rating for steep slope applications. See page 30



Electrical Bonding and Grounding Test Modules

The list below is not exhaustive of compliant modules but shows those that have been evaluated and found to be electrically compatible with the SOLARMOUNT system.

| Manufacture | Module Model / Series | Manufacture | Module Model / Series | Manufacture | Module Model / Series |
|----------------|---|---|--|-------------|--|
| Jinko | JKM & JKMS Series JKMxxxM-72HL-V JKMxxxM-72HL4-(T)V JKMxxxM-72HLM-TV JKMxxxM-7RL3-V JKMxxxM-72HL4-TV | | LR4-60(HPB/HPH) LR4-72(HPH) LR6-60 LR6-60(BK/HPB/HPH/HV/PB/PE/PH) LR6-72 LR6-72(BK/HV/PB/PE/PH) RealBlack LR4-60HPB RealBlack LR6-60HPB | Peimar | SGxxxM (FB/BF) SMxxxM |
| | | LONGi LR6-60 LR6-72 LR6-72 RealBla | | Phono Solar | PSxxxM1-20/U PSxxxM1H-20/U PSxxxM1-20UH PSxxxM4-20UH PSxxxM4(H)-24/TH PSxxxM1-20/UH PSxxxM1-20/UH PSxxxM1-20/UH PSxxxM-24/T PSxxxM-24/T PSxxxM-24/TH PSxxxM-24/TH |
| Kyocera | KD-F & KU Series | Maxeon | SPR-MAX3-xxx-COM | | |
| LA Solar | LSxxxHC(166) | Meyer Burger | Meyer Burger Black, Meyer Burger White Meyer Burger Glass | | |
| | LSxxxBL LSxxxHC | Mission Solar Energy | MSE Mono, MSE Perc MSExxx(SR8T/SR8K/SR9S/SX5T) MSExxx(SX5K/SX6W) | | |
| | LGxxx(E1C/E1K/N1C/N1K/N2T/N2W/S1C/ S2W/Q1C/Q1K)-A5 LGxxx(A1C/M1C/M1K/N1C/N1K/Q1C/Q1K/ QAC/QAK)-A6 LGxxxN2W-B3 LGxxxN1K-B5 LGxxxN1K-B6 LGxxx(N1C/N1K/N2T/N2W)-E6 LGxxx(N1C/N1K/N2T/N2W)-E6 LGxxx(N1C/N1K/N2W/S1C/S2W)-G4 LGxxxN2T-J5 LGxxx(N1C/N1K/N2T/N2W)-L5 LGxxx(N1C/N1C/Q1C/Q1K)-N5 LGxxx(N1C/N1K/N2W/Q1C/Q1K)-V5 LGxxxN3K-V6 | | | Prism Solar | P72 Series, P72X-xxx |
| | | Mitrex | Mxxx-L3H, Mxxx-I3H | | |
| | | Mitsubishi | MJE & MLE Series | | Peak G5(SC) , G6(+)(SC)(AC), G7, G8(+), Plus, Pro, Peak L-G2, L-G4, L-G5 |
| | | Neo Solar Power Co. | D6M Series | | Peak L-G5, L-G6, L-G7, L-G8(BFF) |
| LG Electronics | | NE Solar | NESE xxx-72MHB-M10 NESE xxx-60MH-M6 | | Q.PEAK DUO BLK-G6+/TS |
| | | Panasonic | VBHNxxxSA06/SA06B/SA11/SA11B VBHNxxxSA15/SA15B/SA16/SA16B, VBHNxxxKA, VBHNxxxKA03/04, VBHNxxxSA17/SA17G/SA17E/SA18/SA18E, VBHNxxxZA01/ZA02/ZA03/VBHNxxxZA04 EVPVxxx EVPVxxx(H/K/PK/HK) | | U.PEAK DUU (BLK)-G/ |

• Unless otherwise noted, all modules listed above include all wattages and specific models within that series. Variable wattages are represented as "xxx"

- Items in parenthesis are those that may or may not be present in a compatible module's model ID
- Slashes "/" between one or more items indicates that either of those items may be the one that is present in a module's model ID
- The frame profile must not have any feature that might interfere with the bonding devices that are integrated into the racking system
- Use with a maximum over current protection device OCPD of 30A
- Listed models can be used to achieve a Class A fire system rating for steep slope applications. See page 30



Electrical Bonding and Grounding Test Modules

The list below is not exhaustive of compliant modules but shows those that have been evaluated and found to be electrically compatible with the SOLARMOUNT system.

| Manufacture | Module Model / Series | Manufacture | Module Model / Series | Manufacture | Module Model / Series |
|-----------------|---|---------------|--|-----------------|--|
| | Q.PEAK DUO L-(G7/G7.1/G7.2/G7.3/G7.7) | | | Sunmac Solar | M754SH-BB Series |
| | Q.PEAK DUO (BLK) G8(+) Q.PEAK DUO L-(G8/G8.1/G8.2/G8.3) Q.PEAK DUO L-G8.3 (BFF/BFG/BGT) | S-Energy | SN72 & SN60 Series | SunPower | AC, X-Series, E-Series & P-Series SPR E20 435 COM (G4 Frame) Axxx-BLK-G-AC, SPR-Mxxx-H-AC |
| | Q.PEAK DUO (BLK) ML-G9(+) Q.PEAK DUO XL-(G9/G9.2/G9.3) | | SEG-(6PA/6PB/6MA/6MA-HV/6MB/E01/E11) | | SPR-Mxxx-H-AC |
| | Q.PEAK DUO XL-G9.3/BFG | | SRP-(6QA/6QB) | SunTech | STP, STPXXXS - B60/Wnhb |
| Q.Cells (cont.) | Q.PEAK DUO-G10+ Q.PEAK DUO BLK G10(+) Q.PEAK DUO BLK G10+ /AC | Seraphim | SRP-xxx-6MB-HV, SRP-320-375-BMB-HV, SRP-xxx-BMC-HV, SRP-390-450-BMA-HV, SRP-xxx-BMZ-HV, SRP-390-405-BMD-HV | Talesun | TP572, TP596, TP654, TP660 TP672, Hipor M, Smart, TD6172M |
| | Q.PEAK DUO (BLK) ML-G10(a)(+) | Sharp | NU-SA & NU-SC Series | Tesla | SC, SC B, SC B1, SC B2, TxxxS, TxxxH |
| | Q.PEAK DUO XL-(G10/G10.2/G10.3/G10.c/ G10.d) Q.PEAK DUO XL-G10.3/BFG Q.PEAK DUO XL-G10.d/BFG Q.PEAK DUO XL-(G11.2/G11.3) Q.PEAK DUO XL-G11.3/BFG | Silfab | SLA-M, SLA-P, SLG-M, SLG-P & BC Series SIL-xxx(BK/BL/HC/HC+/HL/HM/HN/ML/NL/ NT/NX/NU) | Trina | PA05, PD05, DD05, DD06, DE06, DE09.05 PD14, PE14, DD14, DE14, DE15, DE15V(II) DEG15HC.20(II), DEG15MC.20(II) DEG15VC.20(II), DE18M(II), DEG18MC.20(II) DE19, DEG19C.20 |
| | | Solar4America | S4Axxx-108MH10BB, S4Axxx-72MH5BB | | |
| | | SolarEver USA | SE-166*83-xxxM-120N | | |
| | RECxxxAA (BLK/Pure) | | SE-182*91-xxxM-108N | TSMC | TS-150C2 CIGSw |
| REC | RECxxxNP (N-PEAK) RECxxxNP2 (Black) RECxxxPE, RECxxxPE72 RECxxxTP, RECxxxTP72 RECxxxTP2(M/BLK2) | Solaria | PowerXT-xxxR-(AC/PD/BD) PowerXT-xxxC-PD PowerXT-xxxR-PM (AC) PowerX-400R | Universal Solar | UNI4xx-144BMH-DG UNI5xx-144BMH-DG UNIxxx-108M-BB UNIxxx-120M-BB |
| | | Solartech | STU HJT, STU PERC & Quantum PERC | 1 | UNIxxx-120MH |
| | RECxxxTP2S(M)72 RECxxxTP3M (Black) | SolarWorld | Sunmodule Protect, Sunmodule Plus/Pro | Upsolar | UP-MxxxP, UP-MxxxM(-B) |
| | RECXXXTP3M (Black) RECXXXTP4 (Black) | | SS-M-360 to 390 Series | | D7Kxxx(H7A/H8A), D7Mxxx(H7A/H8A) |
| Renesola | All 60-cell modules | Sonali | SS-M-390 to 400 Series | URECO | FAKxxx(C8G/E8G), FAMxxxE7G-BB FAMxxxE8G(-BB), FBKxxxM8G F6MxxxE7G-BB FBMxxxMFG-BB |
| Risen | RSM Series, RSM110-8-xxxBMDG |] | SS-M-440 to 460 Series SS-M-430 to 460 BiFacial Series | | |
| SEG Solar | SEG-xxx-BMD-HV/TB | Sun Edison | F-Series, R-Series | | Eldora, Somera, Ultima |
| | | Suniva | MV Series & Optimus Series (35mm) | Vikram | PREXOS VSMDHT.60.AAA.05 PREXOS VSMDHT.72.AAA.05 |

• Unless otherwise noted, all modules listed above include all wattages and specific models within that series. Variable wattages are represented as "xxx"

• Items in parenthesis are those that may or may not be present in a compatible module's model ID

• Slashes "/" between one or more items indicates that either of those items may be the one that is present in a module's model ID

• The frame profile must not have any feature that might interfere with the bonding devices that are integrated into the racking system

• Use with a maximum over current protection device OCPD of 30A

• Listed models can be used to achieve a Class A fire system rating for steep slope applications. See page 30



Electrical Bonding and Grounding Test Modules

The list below is not exhaustive of compliant modules but shows those that have been evaluated and found to be electrically compatible with the SOLARMOUNT system.

| Manufacture | Module Model / Series |
|--------------|------------------------------------|
| | VNS-72M1-5-xxxW-1.5, |
| | VNS-72M3-5-xxxW-1.5, |
| Vina | VNS-144M1-5-xxxW-1.5, |
| | VNS-144M3-5-xxxW-1.5, |
| | VNS-120M3-5-xxxW-1.0 |
| | VSUNxxx-60M-BB, VSUNxxx-72MH |
| | VSUN4xx-144BMH |
| | VSUN4xx-144BMH-DG |
| | VSUN5xx-144BMH-DG |
| VSUN | VSUNxxx-108M-BB VSUNxxx-120M-BB |
| | VSUNxxx-120M-BB |
| | VSUNXXX-120DMIN VSUNXXX-132BMH |
| | VSUNXXX-132BMH VSUNXXX-108BMH |
| Waaree | Ahnay Series Bi-33 |
| | |
| Winaico | WST & WSP Series |
| Yingli | YGE & YLM Series |
| Yotta Energy | YSM-B450-1 |
| | ZXM6-72 Series, ZXM6-NH144 |
| ZNShine | ZXM6-NHLDD144 |
| | ZXM7-SH108 Series |

• Unless otherwise noted, all modules listed above include all wattages and specific models within that series. Variable wattages are represented as "xxx"

- Items in parenthesis are those that may or may not be present in a compatible module's model ID
- Slashes "/" between one or more items indicates that either of those items may be the one that is present in a module's model ID
- The frame profile must not have any feature that might interfere with the bonding devices that are integrated into the racking system
- Use with a maximum over current protection device OCPD of 30A
- Listed models can be used to achieve a Class A fire system rating for steep slope applications. See page 30



APPENDIX A FLASHKIT PRO INSTALLATION PAGE





INSTALL L-FOOT

STEP 2



ATTACH L-FOOT TO RAIL

• Drive the lag bolt down until the L-foot is held firmly in place. It is normal for the EPDM on the underside of the stainless steel backed EPDM washer to compress and expand beyond the outside edge of the steel washer when the proper torque is applied.

TIP:

- Use caution to avoid over-torqueing the lag bolt if using an impact driver.
- Repeat Steps 1 and 2 at each roof attachment point.

STEP 3 ATTACH L-FOOT TO RAIL

- Insert the included 3/8"-16 T-bolts into the lower slot on the Rail (sold separately), spacing the bolts to match the spacing between the roof attachments.
- Position the Rail against the L-Foot and insert the threaded end of the T-Bolt through the continuous slot in the L-Foot. Apply anti-seize to bolt threads to prevent galling of the T-bolt and included 3/8" serrated flange nut. Place the 3/8" flange nut on the T-bolt and finger tighten. Repeat STEP 3 until all L-Feet are secured to the Rail with a T-bolt. Adjust the level and height of the Rail and torque each bolt to 30ft-lbs.

PRE-INSTALL

- Locate roof rafters and snap chalk lines to mark the installation point for each roof attachment.
- Drill a 7/32" pilot hole at each roof attachment. Fill each pilot hole with sealant.

STEP 1 INSTALL **FLASH**KIT PRO FLASHING

 Add a U-shaped bead of roof sealant to the underside of the flashing with the open side of the U pointing down the roof slope. Slide the aluminum flashing underneath the row of shingles directly up slope from the pilot hole as shown. Align the indicator marks on the lower end of the flashing with the chalk lines on the roof to center the raised hole in the flashing over the pilot hole in the roof. When installed correctly, the flashing will extend under the two courses of shingles above the pilot hole.

STEP 2 INSTALL L-FOOT

• Fasten L-foot and Flashing into place by passing the included lag bolt and pre-installed stainless steel-backed EPDM washer through the L-foot EPDM grommet, and the raised hole in the flashing, into the pilot hole in the roof rafter.

DocuSign Envelope ID: 4C077C38-FA98-419B-B651-E66DE9437930



1.75"

APPENDIX B Flashloc comp installation Page

PRE-INSTALL

Snap chalk lines for attachment rows. On shingle roofs, snap lines 1-3/4" below upslope edge of shingle course. Locate rafters and mark attachment locations. At each location, drill a 7/32" pilot hole. Clean roof surface of dirt, debris, snow, and ice. Next, BACKFILL ALL PILOT HOLES WITH SEALANT. NOTE: Space mounts per racking system install specifications.

STEP 1: SECURE

Place **FLASH**LOC over pilot hole with lag on down-slope side. Align indicator marks on sides of mount with chalk line. Pass included lag bolt and sealing washer through **FLASH**LOC into pilot hole. Drive lag bolt until mount is held firmly in place.

NOTE: The EPDM in the sealing washer will expand beyond the edge of the metal washer when proper torque is applied.

STEP 2: SEAL

Insert tip of UNIRAC provided sealant into port. Inject until sealant exits both vents. Follow sealant manufacturer's instructions. Follow sealant manufacturer's cold weather application guidelines, if applicable.

Continue array installation, attaching rails to mounts with provided T-bolts.



NOTE: When **FLASH**LOC is installed over gap between shingle tabs or vertical joints, fill gap/joint with sealant between mount and upslope edge of shingle course.

USE ONLY UNIRAC APPROVED SEALANTS: Chemlink Duralink 50, Chemlink M-1, Geocel 4500, or Geocel S-4





APPENDIX C Flashloc duo installation Page



PRE-INSTALL CLEAN SURFACE AND MARK LOCATION

Ensure existing roof structure is capable of supporting loads prescribed in Flashloc Duo D&E Guide. Clean roof surface of dirt, debris, snow and ice.

Snap chalk lines for attachment rows. On shingle roofs, snap lines 1/4" below upslope edge of shingle coarse. This line will be used to align the upper edge of the mount.

NOTE: Space mounts per span charts found in Flashloc Duo D&E Guide.



STEP ONE: SECURE

ATTACHING TO A RAFTER: Place FLASHLOC DUO over rafter location and align upper edge of mount with horizontal chalk line. Secure mount with the two (2) provided rafter screws. BACKFILL ALL PILOT HOLES WITH SEALANT.

ATTACHING TO SHEATHING: Place FLASHLOC DUO over desired location and align upper edge of mount with horizontal chalk line. Secure mount with the two (2) provided rafter screws. Next, secure mount with four (4) deck screws by drilling through the FLASHLOC DUO deck mount hole locations. Unirac recommends using a drill as opposed to an impact gun to prevent over-tightening or stripping roof sheathing.

IMPORTANT: SECURELY ATTACH MOUNT BUT DO NOT OVERTIGHTEN SCREWS.



STEP TWO: SEAL

Insert tip of UNIRAC approved sealant into port and inject until sealant exits vent. Continue array installation, attaching rails to mounts with provided T-bolts. Follow sealant manufacturer's instructions. Follow sealant manufacturer's cold weather application guidelines, if applicable.

NOTE: When FLASHLOC DUO is installed over gap between shingle tabs or vertical joints, fill gap/joint with sealant between mount and upslope edge of shingle course.




CUT SHINGLES AS REQUIRED: DO NOT INSTALL THE FLASHLOC SLIDER ACCROSS THICKNESS VARIATIONS GREATER THAN 1/8" SUCH AS THOSE FOUND IN HIGH DEFINITION SHINGLES.

NOTE: When installing included rail attachment hardware, torque T-bolt nut to 30 ft-lbs. NOTE: If an exploratory hole falls outside of the area covered by the sealant, flash hole accordingly.


USE ONLY UNIRAC APPROVED SEALANTS. PLEASE CONTACT UNIRAC FOR FULL LIST OF COMPATIBLE SEALANTS.




APPENDIX D 38 UNIVERSAL AF ENDCLAMP INSTALLATION GUIDE PAGE




STEP 1: Position clamp to align T-bolt with rail slot. Lower clamp and Insert T-bolt into rail slot.




STEP 2: Rotate clamp clockwise 2/3 of a turn to engage T-bolt inside rail slot.




STEP 3: Place module at least 3/4" from end of rail and position clamp against module frame.



STEP 4: While applying pressure to hold the clamp against the module, push down on the module side of the clamp cap.




STEP 5: When the cap contacts the module frame, release and it will re-engage to the clamp base.



STEP 6: Tighten bolt and torque to 15 ft-lbs.

NOTE - Universal AF End Clamps are single use.




STEP 7: Confirm clamp is engaged in correct module height position and that the top of the cap is sitting level with the module frame.

NOTE: When installing 46mm modules, loosen bolt by 1 turn before positioning clamp against module frame. Do not force clamp onto module frame as this may damage the bonding pin.


DocuSign Envelope ID: 4C077C38-FA98-419B-B651-E66DE9437930




APPENDIX D 39 UNIVERSAL AF MIDCLAMP INSTALLATION GUIDE PAGE




STEP 1: Position clamp to align T-bolt with rail slot. Lower clamp and insert T-bolt into rail slot




STEP 2: Rotate clamp clockwise 2/3 of a turn to engage T-bolt inside rail slot.



STEP3: Slide clamp into position against module.




STEP 4: Place second module.




STEP 5: Tighten bolt and torque to 15 ft-lbs.


NOTE - Universal AF Mid Clamps are single use.



NOTE: If excessive force is applied in step 2, the cap may over-rotate causing it to be mis-aligned with the module frame. If this occurs, keep rotating the cap clockwise until it returns to the original position.







SMITH, MIRANDA

2490 LONGFELLOW STREET DETROIT, MI 48206 7348589871



1192 E. DRAPER PARKWAY STE 466 DRAPER, UT 84020 (888) 985-2859

ELECTRICAL PHOTOS

PV-7

JOB #: 4184 DATE: 11/21/2023 DRAWN BY: IAN REV #1: REV #2: REV #3:



November 22, 2023

Generation Solar 1192 East Draper Parkway, Ste. 466 Draper, UT 84020

> Re: Engineering Services Smith Residence 2490 Longfellow Street, Detroit, MI 7.900 kW System

To Whom It May Concern:

We have received information regarding solar panel installation on the roof of the above referenced structure. Our evaluation of the structure is to verify the existing capacity of the roof system and its ability to support the additional loads imposed by the proposed solar system.

A. Site Assessment Information

- 1. Site visit documentation identifying attic information including size and spacing of framing for the existing roof structure.
- 2. Design drawings of the proposed system including a site plan, roof plan and connection details for the solar panels. This information will be utilized for approval and construction of the proposed system.

B. Description of Structure:

Roof Framing:2 x 6 dimensional lumber at 16" on center.Roof Material:Composite Asphalt ShinglesRoof Slope:27 degreesAttic Access:AccessibleFoundation:Permanent

C. Loading Criteria Used

- Dead Load
 - Existing Roofing and framing = 7 psf
 - New Solar Panels and Racking = 3 psf
 - TOTAL = 10 PSF
- Live Load = 20 psf (reducible) 0 psf at locations of solar panels
- Ground Snow Load = 25 psf
- Wind Load based on ASCE 7-10
 - Ultimate Wind Speed = 115 mph (based on Risk Category II)
 - Exposure Category C

Analysis performed of the existing roof structure utilizing the above loading criteria is in accordance with the 2015 International Residential Code, including provisions allowing existing structures to not require strengthening if the new loads do not exceed existing design loads by 105% for gravity elements and 110% for seismic elements. This analysis indicates that the existing framing will support the additional panel loading without damage, if installed correctly.

Page 2 of 2

D. Solar Panel Anchorage

- 1. The solar panels shall be mounted in accordance with the most recent Unirac installation manual. If during solar panel installation, the roof framing members appear unstable or deflect non-uniformly, our office should be notified before proceeding with the installation.
- 2. The maximum allowable withdrawal force for a 5/16" lag screw is 235 lbs per inch of penetration as identified in the National Design Standards (NDS) of timber construction specifications. Based on a minimum penetration depth of 2½", the allowable capacity per connection is greater than the design withdrawal force (demand). Considering the variable factors for the existing roof framing and installation tolerances, the connection using one 5/16" diameter lag screw with a minimum of 2½" embedment will be adequate and will include a sufficient factor of safety.
- 3. Considering the wind speed, roof slopes, size and spacing of framing members, and condition of the roof, the panel supports shall be placed no greater than 48" on center.

Based on the above evaluation, this office certifies that with the racking and mounting specified, the existing roof system will adequately support the additional loading imposed by the solar system. This evaluation is in conformance with the 2015 IRC, current industry standards, and is based on information supplied to us at the time of this report.

Should you have any questions regarding the above or if you require further information do not hesitate to contact me.

VOUR Scott E. Wyssling, PE Michigan License No 62 068147






SMITH RESIDENCE


PHOTOVOLTAIC SYSTEM 2490 LONGFELLOW STREET DETROIT, MI 48206

SYSTEM SIZE: 7.90 kW-DC | 5.80 kW-AC **MODULE:** (20) CS3U- 395W **INVERTER:** (20) ENPHASE IQ8+-72-2-US


| Gillow Qkingcuts | GENERAL | 11. PLUMBING AND MECHANICAL VENTS THROUGH THE ROOF 9. FOR UNGROUNDED SYSTEMS, THE INV SHALL NOT BE COVERED BY SOLAR MODULES NO WITH GROUND FAULT PROTECTION DURING AND FAULT PROTECTION |
|--|--|---|
| man and a second s | 1. UTILITY SHALL BE NOTIFIED BEFORE ACTIVATION OF PHOTOVOLTAIC SYSTEM. | BUILDING, PLUMBING OR MECHANICAL VENTS TO BE COVERED, CONSTRUCTED OR ROUTED AROUND SOLAR MODULES. 10. PV MODULE FRAMES SHALL BE BOND OR BARE COPPER GEC/GEC |
| | BE LABELED, LISTED, OR CERTIFIED BY A NATIONALLY RECOGNIZED TESTING LABORATORY ACCREDITED BY | |
| | THE UNITED STATES OCCUPATIONAL SAFETY HEALTH ADMINISTRATION 3. CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS | 12. THE PHOTOVOLTAIC INVERTER WILL I |
| C Constantion St | INSTALLATION DOCUMENTS PRIOR TO INITIATING | 1. WIRING MATERIALS SHALL COMPLY WITH MAXIMUM CONTINUOUS CURRENT OUTPUT AT 25°C AND WILL BE CONTINUOUS, EXCEPT FOR |
| | CONSTRUCTION. 5. ALL EQUIPMENT AND ASSOCIATED CONNECTIONS, ETC, AND ALL ASSOCIATED WIRING AND INTERCONNECTIONS SHALL BE INSTALLED ONLY BY | RATED AT 90°C. 2. EXPOSED PHOTOVOLTAIC SYSTEM CONDUCTORS ON |
| Edeoards | QUALIFIED PERSONNEL. 6. THE CONTRACTOR OR OWNER MUST PROVIDE ROOF ACCESS (LADDER TO ROOF) FOR ALL THE REQUIRED | 3. PHOTOVOLTAIC SYSTEM CONDUCTORS SHALL BE 16. WHEN APPLYING THE 120% RULE, T 10ENTIFIED AND GROUPED. THE MEANS OF 10ENTIFICATION SHALL BE PERMITTED BY SEPARATE 10. WHEN APPLYING THE 120% RULE, T 10ENTIFICATION SHALL BE PERMITTED BY SEPARATE 10. WHEN APPLYING THE 120% RULE, T 10ENTIFICATION SHALL BE PERMITTED BY SEPARATE |
| VICINITY MAP | INSPECTIONS. LADDERS MUST BE OSHA APPROVED, MINIMUM TYPE I WITH A 250LB. RATING, IN GOOD CONDITION AND DESIGNED FOR ITS INTENDED USE. | COLOR-CODING, MARKING TAPE, TAGGING OR OTHER APPROVED MEANS. 4. ALL EXTERIOR CONDUIT, FITTINGS, AND BOXES SHALL |
| CHARLES CON | CONTRACTOR SHALL VERIFY THAT THE ROOF STRUCTURE WILL WITHSTAND THE ADDITIONAL LOADS. LAG SCREWS SHALL PENETRATE A MINIMUM 2" INTO | BE RAIN-TIGHT AND APPROVED FOR USE IN WET LOCATIONS. |
| | SOLID SAWN STRUCTURAL MEMBERS AND SHALL NOT EXCEED MANUFACTURER RECOMMENDATIONS FOR FASTENERS INTO ENGINEERED STRUCTURAL | |
| | MEMBERS. 9. AN ACCESS POINT SHALL BE PROVIDED THAT DOES NOT PLACE THE GROUND LADDER OVER OPENINGS | OTHER EQUIPMENT SHALL NOT DISCONNECT THE |
| | SUCH AS WINDOWS OR DOORS ARE LOCATED AT STRONG POINTS OF BUILDING CONSTRUCTION AND IN LOCATIONS WHERE THE ACCESS POINT DOES NOT | BUILDING CONNECTION BETWEEN THE GROUNDING ELECTRODE CONDUCTOR AND THE PV SOURCE AND/OR OUTPUT CIRCUIT GROUNDED CONDUCTOR. 8. FOR GROUNDED SYSTEMS, THE PHOTOVOLTAIC |
| | TREE LIMBS, WIRES, OR SIGNS. 10. WHERE DC CONDUCTORS ARE RUN INSIDE BUILDING, THEY SHALL BE CONTAINED IN A METAL RACEWAY; | SOURCE AND OUTPUT CIRCUITS SHALL BE PROVIDED |
| AERIAL MAP | THEY SHALL NOT BE INSTALLED WITHIN 10" OF THE ROOF DECKING OR SHEATHING EXCEPT WHERE COVERED BY THE PV MODULES AND EQUIPMENT. | WITH A GROUND-FAULT PROTECTION DEVICE OR SYSTEM THAT DETECTS A GROUND FAULT, INDICATES THAT FAULT HAS OCCURED AND AUTOMATICALLY DISCONNECTS ALL CONDUCTORS OR CAUSES THE INVERTER TO AUTOMATICALLY CEASE SUPPLYING POWER TO OUTPUT CIRCUITS. |
| | 3 | |

| | GOVERNING CODE ALL MATERIALS, EQUIPMENT, INSTAI WORK SHALL COMPLY WITH THE FO APPLICABLE CODES: • 2014 NATIONAL ELECTRIC CODE (N • 2015 MICHIGAN BUILDING CODE • 2015 MICHIGAN PUMBING CODE • 2015 INTERNATIONAL FUEL GAS CC • 2015 INTERNATIONAL FUEL GAS CC • 2015 INTERNATIONAL MECHANICAL • 2015 INTERNATIONAL FIRE CODE (I • 2015 INTERNATIONAL FIRE CODE (I • 1CC/ANSI A117.1 - 2009 | LLATION AND LLOWING IEC) DDE _ CODE ODE FC) |
|--|--|---|
| INVERTER IS EQUIPPED ION AND A GFI FUSE ITION. NDED TO RACKING RAIL PER THE MODULE JCTION SHEET. . BE BONDED TO BARE .SCO GBL-4DBT LAY-IN L BE LISTED AS UL 1741 | SHEET INDEX: PV-1 - COVER PAGE PV-2 - PROPERTY PLAN PV-3 - SITE PLAN PV-4 - ELECTRICAL CALCULATIONS PV-5 - 1-LINE DIAGRAM PV-5.1 - 3-LINE DIAGRAM PV-6 - ELECTRICAL LABELS PV-7 - ELECTRICAL PHOTOS | |
| CTRODE CONDUCTOR OR SPLICES OR JOINTS IPMENT. E METHOD OF UTILITY ERS SHALL NOT READ THE SOLAR BREAKER DSITE END OF THE BUS ROUND THE EXISTING WELL AS THE NEW | | |
| MAINTAINED. | LICENSE NUMBER: 6218 SMITH, MIRANDA | A |
| | 2490 LONGFELLOW STRI DETROIT, MI 48206 7348589871 | |
| | COVER PAGE JOB #: 4184 REV #1: DATE: 11/21/2023 REV #2: DRAWN BY: IAN REV #3: | PV-1 |






| N | LEGEND: | | |
|--------------|---|------|--|
| | PROPERTY LINE: | | |
| \checkmark | DRIVEWAY: | | |
| | FENCE:0000 | -0 | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | SCALE: 1" = 20' | | |
| | LICENSE NUMBER: 62185 | 537 | |
| | SMITH, MIRANDA | | |
| • | 2490 LONGFELLOW STRE DETROIT, MI 48206 | :El | |
| 2 · | 7348589871 | | |
| | 5 | | |
| WINDING | GENERATION SOLAR 1192 E. DRAPER PARKWAY STE 4 DRAPER, UT 84020 (2021) ADS DSCO | 66 | |
| 111. | (888) 985-2859 PROPERTY PLAN | | |
| 1 | JOB #: 4184 REV #1: | | |
| | DATE: 11/21/2023 REV #2: DRAWN BY: IAN REV #3: | PV-2 | |
| | | | |



427.38

1533.4002



WIND UPLIFT AT ATTACHMENT POINTS IS PROVIDED WITH THE ENGINEERING LETTER.

SUPPORT LOCATIONS HAVE BEEN OPTIMIZED TO WITHSTAND UPLIFT




| | 3000 PA DOWINWARD | | | |
|----------------------------------|--|--|--|--|
| MODULE WEIGHT | 22.5 KG (49.6 LBS) | | | |
| MODULE DIMENSIONS (H X L X D) | 2000 × 992 × 35 MM (78.7 × 39.1 × 1.38 INCHES) | | | |
| MODULE AREA | 21.3692 FT ² | | | |
| MODULE MECHANICAL SPECIFICATIONS | | | | |
| DESIGN WIND SPEED | 115 MPH | | | |
| DESIGN SNOW LOAD | 35 PSF | | | |
| ROOF PITCH | 27° | | | |

TOTAL ARRAY AREA (SQ. FT)

TOTAL ROOF AREA (SQ. FT)

| MODULE INFORMATION | | | | |
|-------------------------------|--|--|--|--|
| MODULE TYPE | CS3U-395W | | | |
| MAX DESIGN LOAD (WIND & SNOW) | 5400 PA UPWARD / 3600 PA DOWNWARD | | | |
| MODULE WEIGHT | 22.5 KG (49.6 LBS) | | | |
| MODULE DIMENSIONS (H X L X D) | 2000 × 992 × 35 MM (78.7 × 39.1 × 1.38 INCHES) | | | |
| MODULE AREA | 21.3692 FT ² | | | |

| MODULE INFORMATION | | | | | | |
|-------------------------------|--|--|--|--|--|--|
| MODULE TYPE | CS3U-395W | | | | | |
| MAX DESIGN LOAD (WIND & SNOW) | 5400 PA UPWARD / 3600 PA DOWNWARD | | | | | |
| MODULE WEIGHT | 22.5 KG (49.6 LBS) | | | | | |
| MODULE DIMENSIONS (H X L X D) | 2000 × 992 × 35 MM (78.7 × 39.1 × 1.38 INCHES) | | | | | |
| MODULE AREA | 21.3692 FT ² | | | | | |



| DocuSign Envelope ID: 4C07 | 77C38-FA98-419B-B651-E66 | DE9437930 |
|----------------------------|--------------------------|-----------|
| KUUF DETAIL | GIRGUIT DETAIL | |

1

(2)

ENPHASE CIRCUITS

CIRCUIT # 1: 10 MODULES

CIRCUIT # 2: 10 MODULES

ROOF TYPE: ASPHALT SHINGLE

ROOF SECTION 1: 4 MODULES AZIMUTH: 334°


ROOF SECTION 2: 16 MODULES AZIMUTH: 154° PITCH: 27°

PITCH: 27°

| N | SYSTEM LEGEN | D | | | | | | |
|-----------------------------|---|-------------|--|--|--|--|--|--|
| Δ | PHOTOVOLTAIC SYSTEM: DC SYSTEM SIZE: 7.90 kW | | | | | | | |
| V | AC SYSTEM SIZE: 5.80 kW | | | | | | | |
| | | RVICE POINT | | | | | | |
| | MP MAIN SERVICE PANEL | | | | | | | |
| | AC UTILITY AC DISCONNECT | | | | | | | |
| | EC ENPHASE AC COMBINER PANE | E | | | | | | |
| | (20) CS3U- 395W WITH ENPH MICROINVERTERS MOUNTED MODULE | | | | | | | |
| | | | | | | | | |
| | CONDUIT RUN CONDUIT TO BE RUN IN ATTIC IF POSSIBL OTHERWISE CONDUIT BLOCKS MIN. 1"/MAX ABOVE ROOF SURFACE, CLOSE TO RIDGE LINE AND UNDER EAVES; TO BE PAINTED TO MATO EXTERIOR/EXISTING BACKGROUND COLOR OF I LOCATION; TO BE LABELED AT MAX 10' INTERVAL CONDUIT RUNS ARE APPROXIMATE AND ARE T | | | | | | | |
| | BE DETERMINED IN THE BY THE INS | _ | | | | | | |
| | ROOF ATTACHMENT P | TNIC | | | | | | |
| | RAIL | | | | | | | |
| | RAFTER | | | | | | | |
| | SCALE: 1" = 10' | | | | | | | |
| | LICENSE NUMBER: 6218 | 537 | | | | | | |
| Q . | SMITH, MIRANDA 2490 LONGFELLOW STRI DETROIT, MI 48206 7348589871 | | | | | | | |
| International International | GENERATION SOLAR 1192 E. DRAPER PARKWAY STE 4 DRAPER, UT 84020 (888) 985-2859 | 466 | | | | | | |
| | SITE PLAN | | | | | | | |
| ' | JOB #: 4184 REV #1: DATE: 11/21/2023 REV #2: DRAWN BY: IAN REV #3: | PV-3 | | | | | | |
| | | | | | | | | |


| Ampacity Calculation: | | | | | | |
|--|-------------------|-------------|-----------|--------------|------|-------|
| Wiring Location: | | rray to In | verter (D | Direct Curre | ent) | |
| | | | • | | | |
| All calculations show minimum sizing | for ampacity | | | | | |
| Actual wire sizing may be larger for w | oltage drop or ot | her factors | S | | | |
| All calculations are according the the | 2020 National E | Electric Co | de | | | |
| Initial Input Values | | | | | | |
| | | Amps | | | | Amps |
| Isc (Short Circuit Current) | | 10.25 | | | | |
| Number of circuits | | 10.25 | Х | 1 | = | 10.25 |
| Maximum Circuit Current (NEC 690.8 (A)(1+2) | | 10.25 | х | 125% | = | 12.81 |
| | | 10.25 | ^ | 125% | - | 12.01 |
| Overcurrent device rating (NEC 690.8 (B)(1) | | 12.81 | х | 125% | = | 16.02 |
| Minimum overcurrent device | | 20.00 | | | | OK |
| | SIZE AWG # | | | | | |
| Chosen Conductor Type THHN, RHW-2 or USE-2 | 10 | | | | | |
| | | | | | | |
| Conductor Derating | | | | | | |
| NEC 690.31 (C) ref (NEC 310.16) | | | | | | |
| Conductor 90°C Ampacity | | 30 | | | | |
| Conduit Fill Derating | 3 | 30.00 | Х | 1.00 | = | 30.00 |
| Temperature Derating °F | 105-113 | 30.00 | Х | .87 | = | 26.10 |
| Ampacity vs. Overcurrent Device | | | | | | |
| Conductor Ampacity Check | | 26.10 | ≥ | 12.81 | | ОК |
| Conductor to Overcurrent Check | | 26.10 | ≥ | 20.00 | | OK |

| Ampacity Calculation: | | | | | |
|---|------------------|--------------|-------|-----------|------|
| Wiring Location: | INVERTER to | Main Service | (Alte | rnating C | urre |
| | | | | | |
| All calculations show minimum sizing for | or ampacity | | | | |
| Actual wire sizing may be larger for volt | age drop or othe | r factors | | | |
| All calculations are according the the 2 | 020 National Ele | ctric Code | | | |
| Initial Input Values | | | | | |
| Inverter Continous AC ouput (Watts) | 290 | | | | |
| Minimum Operating Voltage | 240 | Watts | | Volts | |
| | | 290 | / | 240 | |
| | | | | | |
| Inverter Continious AC Amps | | 1.21 | | | |
| Number of circuits | | 1.21 | Х | 20 | |
| Overcurrent device rating | | | | | |
| NEC 690.8 (B)(3) | | 24.17 | X | 125% | |
| Minimum overcurrent device | | 40.00 | | | |
| | SIZE AWG # | | | | |
| Chosen Conductor Type | | | | | |
| THHN, RHW-2 or USE-2 | 6 | | | | |
| Conductor Derating | | | | | |
| NEC 690.31 (C) ref (NEC 310.16) | | | | | |
| Conductor 90°C Ampacity | | 75 | | | |
| Conduit Fill Derating | 3 | 75.00 | Х | 1.00 | |
| Temperature Derating °F | 105-113 | 75.00 | Х | .87 | |
| Ampacity vs. Overcurrent Device | | | | | |
| Conductor Ampacity Check | | 65.25 | ≥ | 30.21 | |
| Conductor Overcurrent Check | | 65.25 | 2 | 40.00 | |



UTILITY AC DISCONNECT MUST BE ACCESSIBLE, LOCKABLE, LABELED, BLADE-STYLE SWITCH, AND LOCATED WITHIN 5' FROM THE UTILITY METER

| | CONDUCTOR AND CONDUIT SCHEDULE | | | | | | | |
|-----|--------------------------------|-----------|-----------------|--------------|-------------------|--|--|--|
| TAG | WIRE TYPE | WIRE SIZE | # OF CONDUCTORS | CONDUIT TYPE | MIN. CONDUIT SIZE | | | |
| 1 | PV WIRE | #10 | 2 - L1 L2 | FREE AIR | N/A | | | |
| 1 | BARE COPPER | #6 | 1 - BARE | FREE AIR | N/A | | | |
| 2 | THWN-2 | #10 | 2 - L1 L2 | EMT | 3/4" | | | |
| 2 | THWN-2 EGC | #10 | 1 - GND | EMT | 3/4" | | | |
| 3 | THWN-2 | #6 | 3 - L1 L2 N | EMT | 3/4" | | | |
| 3 | THWN-2 EGC | #8 | 1 - GND | EMT | 3/4" | | | |



ENPHASE IQ8+-72-2-US

MICRO-INVERTER

| PV MODULE ELECTRICAL S | PECIFICATIONS | | | | |
|--|---------------|------------------------------|----------------------|---|-------------------------|
| | | INVERTER ELECTRICAL S | PECIFICATIONS | SYSTEM OVER-CURRENT PROTECTION DEVICE (OCPD) | |
| MODULE TYPE | CS3U- 395W | INVERTER TYPE | ENPHASE IQ8+-72-2-US | CALCULATIONS | |
| POWER MAX (P _{MAX}) | 395W | MAX INPUT DC VOLTAGE | 60V | INVERTER TYPE | ENPHASE IQ8+-72-2-US |
| OPEN CIRCUIT VOLTAGE (V _{OC}) | 48.4V | MAX DC SHORT CIRCUIT CURRENT | 15A | # OF INVERTERS | 20 |
| SHORT CIRCUIT CURRENT (I _{SC}) | 10.25A | MAXIMUM OUTPUT POWER | 290W | MAX CONTINUOUS OUTPUT CURRENT | 1.21 |
| MAX POWER-POINT VOLTAGE (VMP) | 40.6V | MAXIMUM CONT. OUTPUT CURRENT | 1.21A | MAX CONTINUOUS OUTPUT CURRENT | 1.21 |
| (WI / | | | | (# OF INVERTERS) X (MAX CONT. OUTPUT CURRENT) X 125% OCPD RATING | |
| MAX POWER-POINT CURRENT (I _{MP}) | 9.73A | CEC EFFICIENCY | 97% | | |
| SERIES FUSE RATING | 19.9A | MAX UNITS PER 20A CIRCUIT | 13 | (20 x 1.21A x 1.25)= 30.25A <= 40A, OK | |

PHOTOVOLTAIC SYSTEM: DC SYSTEM SIZE: 7.900 kW AC SYSTEM SIZE: 5.80 kW INVERTER: (20) ENPHASE IQ8+-72-2-US MODULE: (20) CS3U- 395W

NOTES

(E) 150A RATED

MAIN SERVICE

PANEL

- MODULES ARE BONDED TO RAIL USING UL 2703 RATED BONDING SYSTEM -INTEGRATED BONDING MID-CLAMPS + DIRECT-BURIAL LAY-IN-LUGS; SEE ATTACHED FOR SPECIFICATIONS IF APPLICABLE
- PV DC SYSTEM IS UNGROUNDED
- PV ARRAY WILL HAVE A GROUNDING ELECTRODE SYSTEM IN COMPLIANCE WITH NEC 250.58 AND 690.47(A)
- WITH NEC 200:50 AND 590.47(A) PV SOURCE, OUTPUT, AND INVERTER INPUT CIRCUIT WIRING METHODS SHALL COMPLY WITH NEC 690.1(G) BACKFED PV BREAKER WILL BE INSTALLED AT OPPOSITE END OF THE BUS BAR FROM THE MAIN BREAKER. A PERMANENT WARNING LABEL TO BE
- INSTALLED PER SYSTEM SIGNAGE, PAGE
- BARE COPPER IS TRANSITIONED TO THWN-2 VIA IRREVERSIBLE CRIMP WHEN PRESENT, THE GEC TO BE CONTINUOUS
- INVERTER(S) TO BE COMPLIANT WITH UL 1741 SUPPLEMENT A
- CONDUIT AND CONDUCTOR SPECIFICATIONS ARE BASED ON MINIMUM CODE REQUIREMENTS AND ARE NOT MEANT TO LIMIT UP-SIZING AS REQUIRED BY FIELD CONDITIONS
- CONDUIT AND CONDUCTOR SPECIFICATIONS ARE BASED ON MINIMUM CODE REQUIREMENTS AND ARE NOT MEANT TO LIMIT UPSIZING AS REQUIRED BY FIELD CONDITIONS.

INSTALLER NOTES:



Signed 11/24/2023

LICENSE NUMBER: 6218537

SMITH, MIRANDA

2490 LONGFELLOW STREET DETROIT, MI 48206 7348589871



1192 E. DRAPER PARKWAY STE 466 DRAPER, UT 84020 (888) 985-2859

1-LINE DIAGRAM & CALCULATIONS


PV-5

JOB #: 4184 DATE: 11/21/2023 DRAWN BY: IAN

REV #1: REV #2: REV #3:

UTILITY AC DISCONNECT MUST BE ACCESSIBLE, LOCKABLE, LABELED, BLADE-STYLE SWITCH, AND LOCATED WITHIN 5' FROM THE UTILITY METER

| | CONDUCTOR AND CONDUIT SCHEDULE | | | | | | | |
|-----|--------------------------------|-----|-----------------|--------------|-------------------|--|--|--|
| TAG | WIRE TYPE WIRE SIZE | | # OF CONDUCTORS | CONDUIT TYPE | MIN. CONDUIT SIZE | | | |
| 1 | PV WIRE | #10 | 2 - L1 L2 | FREE AIR | N/A | | | |
| 1 | BARE COPPER | #6 | 1 - BARE | FREE AIR | N/A | | | |
| 2 | THWN-2 | #10 | 2 - L1 L2 | EMT | 3/4" | | | |
| 2 | THWN-2 EGC | #10 | 1 - GND | EMT | 3/4" | | | |
| 3 | THWN-2 | #6 | 3 - L1 L2 N | EMT | 3/4" | | | |
| 3 | THWN-2 EGC | #8 | 1 - GND | EMT | 3/4" | | | |



ENPHASE IQ8+-72-2-US

MICRO-INVERTER

| PV MODULE ELECTRICAL S | DECIFICATIONS | 1 | | | |
|--|---------------|------------------------------------|----------------------|---|-------------------------|
| PV MODULE ELECTRICAL S | PECIFICATIONS | INVERTER ELECTRICAL SPECIFICATIONS | | SYSTEM OVER-CURRENT PROTECTION DEVICE (OCP | |
| MODULE TYPE | CS3U- 395W | INVERTER TYPE | ENPHASE IQ8+-72-2-US | CALCULATIONS | |
| POWER MAX (P _{MAX}) | 395W | MAX INPUT DC VOLTAGE | 60V | INVERTER TYPE | ENPHASE IQ8+-72-2-US |
| OPEN CIRCUIT VOLTAGE (V _{OC}) | 48.4V | MAX DC SHORT CIRCUIT CURRENT | 15A | # OF INVERTERS | 20 |
| SHORT CIRCUIT CURRENT (ISC) | 10.25A | MAXIMUM OUTPUT POWER | 290W | | 1.21 |
| MAX POWER-POINT VOLTAGE (VMP) | 40.6V | MAXIMUM CONT. OUTPUT CURRENT | 1.21A | MAX CONTINUOUS OUTPUT CURRENT | 1.21 |
| MAX POWER-POINT CURRENT (I _{MP}) | 9.73A | CEC EFFICIENCY | 97% | (# OF INVERTERS) X (MAX CONT. OUTPUT CURRENT) X 125% OCPD RATING | |
| SERIES FUSE RATING | 19.9A | MAX UNITS PER 20A CIRCUIT | 13 | (20 x 1.21A x 1.25)= 30.25A <= 40A, OK | |

PHOTOVOLTAIC SYSTEM: DC SYSTEM SIZE: 7.900 kW AC SYSTEM SIZE: 5.80 kW INVERTER: (20) ENPHASE IQ8+-72-2-US MODULE: (20) CS3U- 395W

NOTES

- MODULES ARE BONDED TO RAIL USING UL 2703 RATED BONDING SYSTEM -INTEGRATED BONDING MID-CLAMPS + DIRECT-BURIAL LAY-IN-LUGS; SEE ATTACHED FOR SPECIFICATIONS IF APPLICABLE
- PV DC SYSTEM IS UNGROUNDED
- PV ARRAY WILL HAVE A GROUNDING ELECTRODE SYSTEM IN COMPLIANCE WITH NEC 250.58 AND 690.47(A)
- PV SOURCE, OUTPUT, AND INVERTER INPUT CIRCUIT WIRING METHODS SHALL COMPLY WITH NEC 690.1(G)
- BACKFED PV BREAKER WILL BE INSTALLED AT OPPOSITE END OF THE BUS BAR FROM THE MAIN BREAKER. A PERMANENT WARNING LABEL TO BE INSTALLED PER SYSTEM SIGNAGE, PAGE
- BARE COPPER IS TRANSITIONED TO THWN-2 VIA IRREVERSIBLE CRIMP WHEN PRESENT, THE GEC TO BE CONTINUOUS
- INVERTER(S) TO BE COMPLIANT WITH UL 1741 SUPPLEMENT A
- CONDUIT AND CONDUCTOR SPECIFICATIONS ARE BASED ON MINIMUM CODE REQUIREMENTS AND ARE NOT MEANT TO LIMIT UP-SIZING AS REQUIRED BY FIELD CONDITIONS
- CONDUIT AND CONDUCTOR SPECIFICATIONS ARE BASED ON MINIMUM CODE REQUIREMENTS AND ARE NOT MEANT TO LIMIT UPSIZING AS REQUIRED BY FIELD CONDITIONS.

INSTALLER NOTES:



Signed 11/24/2023

LICENSE NUMBER: 6218537

SMITH, MIRANDA

2490 LONGFELLOW STREET DETROIT, MI 48206 7348589871



1192 E. DRAPER PARKWAY STE 466 DRAPER, UT 84020 (888) 985-2859

3-LINE DIAGRAM & CALCULATIONS


JOB #: 4184 DATE: 11/21/2023 DRAWN BY: IAN

REV #1: REV #2: REV #3:





(E)150A RATED MAIN SERVICE PANEL

FACILITY GROUND (E) GROUND ROD + (E) WATER PIPE BOND









SMITH, MIRANDA

2490 LONGFELLOW STREET DETROIT, MI 48206 7348589871




1192 E. DRAPER PARKWAY STE 466 DRAPER, UT 84020 (888) 985-2859

ELECTRICAL PHOTOS

PV-7

JOB #: 4184 DATE: 11/21/2023 DRAWN BY: IAN REV #1: REV #2: REV #3:



2490 LONGFELLOW STREET, DETROIT, MI 48206

Section CanadianSolar

KuMax HIGH EFFICIENCY MONO PERC MODULE CS3U-380|385|390|395|400MS (1000 V / 1500 V)


MORE POWER



Better shading tolerance

Low power loss in cell connection

Low temperature coefficient (Pmax): -0.36 % / °C



Low NMOT: 42 + 3 °C

MORE RELIABLE

Lower hot spot temperature

Minimizes micro-crack impacts

Heavy snow load up to 5400 Pa, wind load up to 3600 Pa*





linear power output warranty*



enhanced product warranty on materials and workmanship*

*According to the applicable Canadian Solar Limited Warranty Statement.

MANAGEMENT SYSTEM CERTIFICATES

ISO 9001:2015 / Quality management system ISO 14001:2015 / Standards for environmental management system OHSAS 18001:2007 / International standards for occupational health & safety

PRODUCT CERTIFICATES*

IEC 61215 / IEC 61730: VDE / CE / CQC / MCS / KS / INMETRO UL 1703 / IEC 61215 performance: CEC listed (US) / FSEC (US Florida) UL 1703: CSA / IEC 61701 ED2: VDE / IEC 62716: VDE / IEC 60068-2-68: SGS Take-e-way




* As there are different certification requirements in different markets, please contact your local Canadian Solar sales representative for the specific certificates applicable to the products in the region in which the products are to be used.

CANADIAN SOLAR INC. is committed to providing high quality solar products, solar system solutions and services to customers around the world. No. 1 module supplier for quality and performance / price ratio in IHS Module Customer Insight Survey. As a leading PV project developer and manufacturer of solar modules with over 40 GW deployed around the world since 2001.

* For detailed information, please refer to the Installation Manual.

ENGINEERING DRAWING (mm)



ELECTRICAL DATA | STC*

| CS3U | 380MS | 385MS | 390MS | 395MS | 400MS | | |
|--|------------------------|-------------|-----------|-----------|------------|--|--|
| Nominal Max. Power (Pmax) | 380 W | 385 W | 390 W | 395 W | 400 W | | |
| Opt. Operating Voltage (Vmp) | 40.0 V | 40.2 V | 40.4 V | 40.6 V | 40.8 V | | |
| Opt. Operating Current (Imp) | 9.50 A | 9.58 V | 9.66 A | 9.73 A | 9.81 A | | |
| Open Circuit Voltage (Voc) | 47.8 V | 48.0 V | 48.2 V | 48.4 V | 48.6 V | | |
| Short Circuit Current (Isc) | 10.01 A | 10.09 A | 10.17 A | 10.25 A | 10.33 A | | |
| Module Efficiency | 19.2% | 19.4% | 19.7% | 19.9% | 20.2% | | |
| Operating Temperature | -40°C ~ | +85°C | | | | | |
| Max. System Voltage | 1500V (I | (EC/UL) | or 1000 | / (IEC/UI | _) | | |
| Module Fire Performance | TYPE 1 (UL 1703) | | | | | | |
| Module Fire Performance | or Class C (IEC 61730) | | | | | | |
| Max. Series Fuse Rating | 30 A | | | | | | |
| Application Classification | Class A | | | | | | |
| Power Tolerance | 0 ~ + 10 | W | | | | | |
| * Under Standard Test Conditions (STC) | ofirradianc | o of 1000 V | V/m² spor | trum AM 1 | 5 and coll | | |


 \star Under Standard Test Conditions (STC) of irradiance of 1000 W/m², spectrum AM 1.5 and cell temperature of 25°C.

ELECTRICAL DATA | NMOT*

| CS3U | 380MS | 385MS | 390MS | 395MS | 400MS |
|------------------------------|--------|--------|--------|--------|--------|
| Nominal Max. Power (Pmax) | 283 W | 287 W | 290 W | 294 W | 298 W |
| Opt. Operating Voltage (Vmp) | 37.2 V | 37.4 V | 37.6 V | 37.8 V | 38.0 V |
| Opt. Operating Current (Imp) | 7.60 A | 7.66 A | 7.72 A | 7.78 A | 7.84 A |
| Open Circuit Voltage (Voc) | 44.8 V | 45.0 V | 45.2 V | 45.4 V | 45.6 V |
| Short Circuit Current (Isc) | 8.08 A | 8.14 A | 8.20 A | 8.27 A | 8.33 A |

 \star Under Nominal Module Operating Temperature (NMOT), irradiance of 800 W/m², spectrum AM 1.5, ambient temperature 20°C, wind speed 1 m/s.

CS3U-400MS / I-V CURVES



MECHANICAL DATA

| Specification | Data |
|---------------------------------------|---|
| Cell Type | Mono-crystalline |
| Cell Arrangement | 144 [2 X (12 X 6)] |
| Dimensione | 2000 X 992 X 35 mm |
| Dimensions | (78.7 X39.1 X1.38 in) |
| Weight | 22.5 kg (49.6 lbs) |
| Front Cover | 3.2 mm tempered glass |
| F | Anodized aluminium alloy, |
| Frame | crossbar enhanced |
| J-Box | IP68, 3 bypass diodes |
| Cable | 4 mm² (IEC), 12 AWG (UL) |
| Cable Length (Including Connector) | Portrait: 400 mm (15.7 in) (+) / 280 mm (11.0 in) (-); landscape: 1250 mm (49.2 in); leap-frog connection: 1670 mm (65.7 in)* |
| Connector | T4 series or H4 UTX or MC4-EVO2 |
| Per Pallet | 30 pieces |
| Per Container (40' HO) | 660 pieces |

Per Container (40' HQ) 660 pieces

* For detailed information, please contact your local Canadian Solar sales and technical representatives.

TEMPERATURE CHARACTERISTICS

| Specification | Data |
|--------------------------------------|--------------|
| Temperature Coefficient (Pmax) | -0.36 % / °C |
| Temperature Coefficient (Voc) | -0.29 % / °C |
| Temperature Coefficient (Isc) | 0.05 % / °C |
| Nominal Module Operating Temperature | 42 ± 3°C |

PARTNER SECTION

* The specifications and key features contained in this datasheet may deviate slightly from our actual products due to the on-going innovation and product enhancement. Canadian Solar Inc. reserves the right to make necessary adjustments to the information described herein at any time without further notice. Please be kindly advised that PV modules should be handled and installed by qualified people who have professional skills and please carefully read the safety and installation instructions before using our PV modules.

CANADIAN SOLAR INC.

545 Speedvale Avenue West, Guelph, Ontario N1K 1E6, Canada, www.canadiansolar.com, support@canadiansolar.com

Data Sheet Enphase Networking

Enphase IQ Combiner 4/4C

X-IQ-AM1-240-4 X-IQ-AM1-240-4C



The Enphase IQ Combiner 4/4C with Enphase IQ Gateway and integrated LTE-M1 cell modem (included only with IQ Combiner 4C) consolidates interconnection equipment into a single enclosure and streamlines IQ microinverters and storage installations by providing a consistent, pre-wired solution for residential applications. It offers up to four 2-pole input circuits and Eaton BR series busbar assembly.

Smart

- Includes IQ Gateway for communication and control
- Includes Enphase Mobile Connect cellular modem (CELLMODEM-M1-06-SP-05), included only with IQ Combiner 4C
- Includes solar shield to match Enphase IQ Battery aesthetics and deflect heat
- Flexible networking supports Wi-Fi, Ethernet, or cellular
- · Optional AC receptacle available for PLC bridge
- Provides production metering and consumption monitoring

Simple

- Centered mounting brackets support single stud mounting
- · Supports bottom, back and side conduit entry
- Up to four 2-pole branch circuits for 240 VAC plug-in breakers (not included)
- · 80A total PV or storage branch circuits

Reliable

- Durable NRTL-certified NEMA type 3R enclosure
- · Five-year limited warranty
- Two years labor reimbursement program coverage included for both the IQ Combiner SKU's
- UL listed



To learn more about Enphase offerings, visit enphase.com

| MODEL NUMBER | |
|---|---|
| IQ Combiner 4 (X-IQ-AM1-240-4) | IQ Combiner 4 with Enphase IQ Gateway printed circuit board for integrated revenue grade PV production metering (ANS C12.20 +/- 0.5%) and consumption monitoring (+/- 2.5%). Includes a silver solar shield to match the IQ Battery system and IQ System Controller 2 and to deflect heat. |
| IQ Combiner 4C (X-IQ-AM1-240-4C) | IQ Combiner 4C with Enphase IQ Gateway printed circuit board for integrated revenue grade PV production metering (ANSI C12.20 +/- 0.5%) and consumption monitoring (+/- 2.5%). Includes Enphase Mobile Connect cellular modem (CELLMODEM-M1-06-SP-05), a plug-and-play industrial-grade cell modem for systems up to 60 microinverters. (Available in the US, Canada, Mexico, Puerto Rico, and the US Virgin Islands, where there is adequate cellular service in the installation area.) Includes a silver solar shield to match the IQ Battery and IQ System Controller and to deflect heat |
| ACCESSORIES AND REPLACEMENT PARTS | (not included, order separately) |
| Ensemble Communications Kit COMMS-CELLMODEM-M1-06 CELLMODEM-M1-06-SP-05 CELLMODEM-M1-06-AT-05 | Includes COMMS-KIT-01 and CELLMODEM-M1-06-SP-05 with 5-year Sprint data plan for Ensemble sites 4G based LTE-M1 cellular modem with 5-year Sprint data plan 4G based LTE-M1 cellular modem with 5-year AT&T data plan |
| Circuit Breakers BRK-10A-2-240V BRK-15A-2-240V BRK-20A-2P-240V BRK-15A-2P-240V-B BRK-20A-2P-240V-B | Supports Eaton BR210, BR215, BR220, BR230, BR240, BR250, and BR260 circuit breakers. Circuit breaker, 2 pole, 10A, Eaton BR210 Circuit breaker, 2 pole, 15A, Eaton BR215 Circuit breaker, 2 pole, 20A, Eaton BR220 Circuit breaker, 2 pole, 15A, Eaton BR215B with hold down kit support Circuit breaker, 2 pole, 20A, Eaton BR220B with hold down kit support |
| EPLC-01 | Power line carrier (communication bridge pair), quantity - one pair |
| XA-SOLARSHIELD-ES | Replacement solar shield for IQ Combiner 4/4C |
| XA-PLUG-120-3 | Accessory receptacle for Power Line Carrier in IQ Combiner 4/4C (required for EPLC-01) |
| XA-ENV-PCBA-3 | Replacement IQ Gateway printed circuit board (PCB) for Combiner 4/4C |
| X-IQ-NA-HD-125A | Hold down kit for Eaton circuit breaker with screws. |
| ELECTRICAL SPECIFICATIONS | |
| Rating | Continuous duty |
| System voltage | 120/240 VAC, 60 Hz |
| Eaton BR series busbar rating | 125 A |
| Max. continuous current rating | 65 A |
| Max. continuous current rating (input from PV/storage) | 64 A |
| Max. fuse/circuit rating (output) | 90 A |
| Branch circuits (solar and/or storage) | Up to four 2-pole Eaton BR series Distributed Generation (DG) breakers only (not included) |
| Max. total branch circuit breaker rating (input) | 80A of distributed generation / 95A with IQ Gateway breaker included |
| Envoy breaker | 10A or 15A rating GE/Siemens/Eaton included |
| Production metering CT | 200 A solid core pre-installed and wired to IQ Gateway |
| Consumption monitoring CT (CT-200-SPLIT) | A pair of 200 A split core current transformers |
| MECHANICAL DATA | |
| Dimensions (WxHxD) | 37.5 x 49.5 x 16.8 cm (14.75" x 19.5" x 6.63"). Height is 21.06" (53.5 cm) with mounting brackets. |
| Weight | 7.5 kg (16.5 lbs) |
| Ambient temperature range | -40° C to +46° C (-40° to 115° F) |
| Cooling | Natural convection, plus heat shield |
| Enclosure environmental rating | Outdoor, NRTL-certified, NEMA type 3R, polycarbonate construction |
| Wire sizes | 20 A to 50 A breaker inputs: 14 to 4 AWG copper conductors 60 A breaker branch input: 4 to 1/0 AWG copper conductors Main lug combined output: 10 to 2/0 AWG copper conductors Neutral and ground: 14 to 1/0 copper conductors Always follow local code requirements for conductor sizing. |
| Altitude | To 2000 meters (6,560 feet) |
| INTERNET CONNECTION OPTIONS | |
| | 802.11b/g/n |
| Integrated Wi-Fi | |
| Cellular | CELLMODEM-M1-06-SP-05, CELLMODEM-M1-06-AT-05 (4G based LTE-M1 cellular modem). Note that an Enphase Mobile Connect cellular modem is required for all Ensemble installations |
| - | CELLMODEM-M1-06-SP-05, CELLMODEM-M1-06-AT-05 (4G based LTE-M1 cellular modem). Note that an Enphase Mobile Connect cellular modem is required for all Ensemble installations. Optional, 802.3, Cat5E (or Cat 6) UTP Ethernet cable (not included) |
| Cellular | Mobile Connect cellular modem is required for all Ensemble installations. |
| Cellular Ethernet | Mobile Connect cellular modem is required for all Ensemble installations. |



To learn more about Enphase offerings, visit enphase.com

© 2022 Enphase Energy. All rights reserved. Enphase, the Enphase logo, IQ Combiner 4/4C, and other names are trademarks of Enphase Energy, Inc. Data subject to change. 02-14-2022

\ominus ENPHASE.





IQ8 and IQ8+ Microinverters

Our newest IQ8 Microinverters are the industry's first microgrid-forming, softwaredefined microinverters with split-phase power conversion capability to convert DC power to AC power efficiently. The brain of the semiconductor-based microinverter is our proprietary application-specific integrated circuit (ASIC) which enables the microinverter to operate in grid-tied or off-grid modes. This chip is built in advanced 55nm technology with high speed digital logic and has super-fast response times to changing loads and grid events, alleviating constraints on battery sizing for home energy systems.



Part of the Enphase Energy System, IQ8 Series Microinverters integrate with the Enphase IQ Battery, Enphase IQ Gateway, and the Enphase App monitoring and analysis software.



Connect PV modules quickly and easily to IQ8 Series Microinverters using the included Q-DCC-2 adapter cable with plug-n-play MC4 connectors.



IQ8 Series Microinverters redefine reliability standards with more than one million cumulative hours of power-on testing, enabling an industryleading limited warranty of up to 25 years.



IQ8 Series Microinverters are UL Listed as PV Rapid Shut Down Equipment and conform with various regulations, when installed according to manufacturer's instructions.

© 2022 Enphase Energy. All rights reserved. Enphase, the Enphase logo, IQ8 Microinverters, and other names are trademarks of Enphase Energy, Inc. Data subject to change.

Easy to install

- Lightweight and compact with plug-n-play connectors
- Power Line Communication (PLC) between components
- Faster installation with simple two-wire cabling

High productivity and reliability

- Produce power even when the grid is down*
- More than one million cumulative hours of testing
- Class II double-insulated
 enclosure
- Optimized for the latest highpowered PV modules

Microgrid-forming

- Complies with the latest advanced grid support**
- Remote automatic updates for the latest grid requirements
- Configurable to support a wide
 range of grid profiles
- Meets CA Rule 21 (UL 1741-SA)
 requirements
- * Only when installed with IQ System Controller 2, meets UL 1741.
- ** IQ8 and IQ8Plus supports split phase, 240V installations only.

IQ8 and IQ8+ Microinverters

| w v v | 235 - 350 60-cell/120 half-cell | 235 – 440 60-cell/120 half-cell, 66-cell/132 half-cell and 72-cell/144 | | |
|-------------|---|---|--|--|
| | 60-cell/120 half-cell | 60-cell/120 half-cell, 66-cell/132 half-cell and 72-cell/144 | | |
| | | half-cell | | |
| v | 27 - 37 | 29 - 45 | | |
| | 25 - 48 | 25 – 58 | | |
| v | 30 / 48 | 30 / 58 | | |
| v | 50 | 60 | | |
| A | 15 | 5 | | |
| | " | I Contraction of the second | | |
| mA | c |) | | |
| | 1x1 Ungrounded array; No additional DC side protection requi | ired; AC side protection requires max 20A per branch circuit | | |
| | IQ8-60-2-US | IQ8PLUS-72-2-US | | |
| VA | 245 | 300 | | |
| VA | 240 | 290 | | |
| V | 240 / 21 | 11 - 264 | | |
| Α | 1.0 | 1.21 | | |
| Hz | 60 | 0 | | |
| Hz | 50 - | - 68 | | |
| Arms | 2 | 2 | | |
| | 16 | 13 | | |
| | <5% | | | |
| | 11 | | | |
| mA | 30 | | | |
| | 1.0 | | | |
| | 0.85 leading - | 0.85 lagging | | |
| % | 97.5 | 97.6 | | |
| % | 97 | 97 | | |
| mW | 60 | 0 | | |
| | | | | |
| | -40°C to +60°C (| -40°F to +140°F) | | |
| | 4% to 100% (| condensing) | | |
| | МС | 24 | | |
| | 212 mm (8.3") x 175 mm | (6.9") x 30.2 mm (1.2") | | |
| | 1.08 kg (2.38 lbs) | | | |
| | Natural convection – no fans | | | |
| | Yes | | | |
| | PD3 | | | |
| | Class II double-insulated, corrosi | on resistant polymeric enclosure | | |
| | NEMA Туре (| 6 / outdoor | | |
| | | | | |
| (| CA Rule 21 (UL 1741-SA), UL 62109-1, UL1741/IEEE1547, FCC Part 1 | 5 Class B, ICES-0003 Class B, CAN/CSA-C22.2 NO. 107.1-01 | | |
| 6 | 690.12 and C22.1-2018 Rule 64-218 Rapid Shutdown of PV System | | | |
| | mA 1 VA 1 VA <td>Image: Amage: Amage:</td> | Image: Amage: | | |

 No enforced DC/AC ratio. See the compatibility calculator at https://link.enphase.com/module-compatibility
 Maximum continuous input DC current is 10.6A (3) Nominal voltage range can be extended beyond nominal if required by the utility. (4) Limits may vary. Refer to local requirements to define the number of microinverters per branch in your area. LSCO

TYPE

IPC

Insulation Piercing Connectors Dual Rated



Features

- Body is molded from tough, resilient glass-filled nylon
 Compact design
 Tin plated copper contact teeth
 Insulation piercing
 Per forated end tabs
 Provided with different kubricant

- Pre-filled with silicone lubricant
- Versatile
- Increased safety
- Horizontal line grid
 Temperature rating 90° C



Fig. 1





• Provides high degree of breakage resistance and long dependable use

Contains no external energized parts. Can be installed "hot" on energized con-ductors providing tap conductor is not under load.

Easily penetrates most types of insulation
No need to strip the conductor which saves installation time
Break out easily by hand
Prevents oxidation and moisture from entering the contact area
Can be used as a splice or tap connector
Contain and entering the contact area

Provides a visual guide for proper installation of conductors



Benefits

Saves space

| Catalog | Figure | Wire | Range | | Current | Rating | D | imension | S | Torque | Bolt Head |
|-------------|--------|-------------------|-------------------|-----------------------------|---------|--------|---------|----------|---------|----------|-----------|
| Number | Number | Main | Тар | Volts | CU | AL | L | W | H | Ft. Lbs. | Size |
| IPC-1/0-2 | 3 | 1/0-8 | 2-8 | 300 (480 Grounded Y System) | 130 | 100 | 1-7/32 | 1-15/32 | 2-5/16 | 16 | 1/2 |
| IPC-4/0-6 | 2 | 4/0-4 | 6-14 | 600 | 75 | 60 | 1-27/64 | 1 | 1-7/8 | 13 | 1/2 |
| IPC-4/0-2/0 | 3 | 4/0-2 | 2/0-6 | 600 | 195 | 150 | 1-21/32 | 1-7/8 | 2-7/8 | 25 | 1/2 |
| IPC-250-4/0 | 2 | 250kcmil-1 | 4/0-6 | 600 | 260 | 205 | 1-7/8 | 2-11/32 | 3-11/32 | 30 | 5/8 |
| IPC-350-4/0 | 3 | 350kcmil-4/0 | 4/0-10 | 300 (480 Grounded Y System) | 260 | 205 | 1-43/64 | 2-7/16 | 3-1/8 | 25 | 5/8 |
| IPC-350-350 | 4 | 350kcmil-4/0 | 350kcmil-4/0 | 300 (480 Grounded Y System) | 350 | 280 | 2-43/64 | 2-23/32 | 3-1/4 | 25 | 5/8 |
| IPC-500-12 | 1 | 500kcmil-250kcmil | 10-12 | 300 (480 Grounded Y System) | 40 | 35 | 1-43/64 | 2-7/16 | 3-1/4 | 25 | 5/8 |
| IPC-500-250 | 1 | 500kcmil-250kcmil | 250kcmil-4 | 600 | 290 | 230 | 2-27/64 | 2-29/32 | 3-3/4 | 55 | 5/8-11/16 |
| IPC-500-500 | 1 | 500kcmil-300kcmil | 500kcmil-250kcmil | 600 | 430 | 350 | 3-3/16 | 3-5/8 | 5 | 75 | 7/8-7/8 |
| IPC-750-500 | 1 | 750kcmil-500kcmil | 500kcmil-350kcmil | 600 | 430 | 350 | 3-3/16 | 3-5/8 | 5 | 75 | 7/8-7/8 |

All wire sizes, unless noted otherwise, are American Wire Gauge (AWG) Tested to UL 486A/B, UL File E6207







BETTER SOLAR STARTS HERE

UNIRAC Code-Compliant Installation Manual

© 2022 by Unirac, Inc. All rights reserved.

UNIRAC welcomes input concerning the accuracy and user-friendliness of this publication. Please write to publications@unirac.com.

PUB2023FEB10



INSTALLATION GUIDE

TABLE OF CONTENTS


PRO SERIES SYSTEM

| PRO SERIES SYSTEM COMPONENTS 1 |
|---------------------------------------|
| SYSTEM COMPONENTS 2-3 |
| THERMAL BREAK |
| SYSTEM LAYOUT |
| ROOF ATTACHMENT & L-FEET |
| SPLICE |
| ATTACH RAIL TO L-FEET |
| MICROINVERTER MOUNTING |
| MICROINVERTER SYSTEM GROUNDING |
| SPLICE & THERMAL BREAK 11 |
| STANDARD SYSTEM GROUNDING12 |
| ENDCLAMP, FIRST MODULE |
| BONDING MIDCLAMP 14 |
| REMAINING MODULES |
| BONDING CONNECTION GROUND PATHS 16-17 |
| TRIM AND END CAP INSTALLATION |

STANDARD SERIES SYSTEM

| STANDARD SERIES SYSTEM COMPONENTS1 | 9 |
|--|---|
| STANDARD SERIES END & MID CLAMPS | 0 |
| ATTACH RAIL TO L-FEET | 1 |
| ENDCLAMP & FIRST MODULE | 2 |
| BONDING MIDCLAMP & TRIM | 3 |
| REMAINING MODULES & TRIM | 4 |
| TRIM RETROFIT INSTALLATION | 5 |
| BONDING CONNECTION GROUND PATHS 26-2 | |
| CODE COMPLIANCE NOTES | 8 |
| MECHANICAL LOAD TEST | 9 |
| SYSTEM LEVEL FIRE CLASSIFICATION | 0 |
| COMPATIBLE MODULES | 4 |
| APPENDIX A: FLASHKIT PRO INSTALLATION | 5 |
| APPENDIX B: FLASHLOC COMP INSTALLATION | 6 |
| APPENDIX C: FLASHLOC DUO INSTALLATION | 7 |
| APPENDIX D: UAF END & MID CLAMP INSTALLATION 38-34 | 9 |
| | |





| Wrenches and Torque | | | | | |
|---------------------|-----------------------|--------------------------------|--|--|--|
| | Wrench or Socket Size | Recommended Torque (ft-lbs) | | | |
| Mid Clamp 🛽 | 1/2" | 11 | | | |
| MLPE Mount 9 | 1/2" | 10 | | | |
| End Clamp 🛛 | 1/2" | 5 | | | |
| L-Foot to Rail 🗿 | 1/2" | 30 | | | |
| Rail Splice 🖲 | 1/2" | 10 | | | |

Anti-Seize OO

Stainless steel hardware can seize up, a process called galling. To significantly reduce its likelihood: 1. Apply minimal lubricant to bolts only where indicated in installation process, preferably Anti-Seize commonly found at auto parts stores (Anti-seize has been factory applied to mid clamp bolts) 2. Shade hardware prior to installation, and 3. Avoid spinning stainless nuts onto bolts at high speed. **ORAIL**: Supports PV modules. Use at least two per row of modules. Aluminum extrusion, available in mill, clear anodized, or dark anodized.

OORAIL SPLICE: Non structural splice joins, aligns, and electrically bonds rail sections into single length of rail. Forms a rigid splice joint, 4 inches long, preassembled with bonding hardware. Available in dark anodized or mill finish.

QL-FOOT: Use to secure rails through roofing material to building structure. Refer to loading tables or U-Builder for spacing.

● L-FOOT T- BOLT: (3/8" x ¾" or 1") – Use one per L-foot to secure rail to L-foot. Stainless steel. Supplied with L-foot in combination with flange nut, provides electrical bond between L-foot and rail. OSERRATED FLANGE NUT : Use one per L-foot to secure and bond rail to L-foot. Stainless steel. Sup-

plied with L-foot. **MODULE ENDCLAMP**: Pre-assembled universal clamp that secures module to rail at module flange by tightening 1/2" hex head bolt.

©MODULE MIDCLAMP: Pre-assembled clamp provides module to module and module to rail bond. Aluminum clamp with stainless steel bonding pins and T-bolt. Available in clear or dark finish. **@MICROINVERTER MOUNTING BOLT**: Preassembled bolt, nut, and captive star washer attaches and bonds microinverter to rail.

NOTE - POSITION INDICATOR: T-bolts have a slot in the hardware end corresponding to the direction of the T-Head.

NOTE - Pro Series Mid and End Clamps are single use only



SYSTEM COMPONENTS | 2 INSTALLATION GUIDE | PAGE

RAILS

| ТҮРЕ | PART NUMBER | DESCRIPTION |
|-----------------|-------------|-------------------------|
| | 315168M | SM LIGHT RAIL 168" MILL |
| | 315168D | SM LIGHT RAIL 168" DRK |
| | 315208M | SM LIGHT RAIL 208" MILL |
| LIGHT RAIL | 315208D | SM LIGHT RAIL 208" DRK |
| | 315246M | SM LIGHT RAIL 246" MILL |
| | 315246D | SM LIGHT RAIL 246" DRK |
| | 320132M | SM RAIL 132" MILL |
| | 310132C | SM RAIL 132" CLR |
| | 320168M | SM RAIL 168" MILL |
| | 310168C | SM RAIL 168" CLR |
| STANDARD RAIL | 310168D | SM RAIL 168" DRK |
| STANDARD RAIL | 320208M | SM RAIL 208" MILL |
| | 310208C | SM RAIL 208" CLR |
| | 320246M | SM RAIL 246" MILL |
| | 310246C | SM RAIL 246" CLR |
| | 310246D | SM RAIL 246" DRK |
| | 410144M | SMHD, RAIL 144" MILL |
| HEAVY DUTY RAIL | 410168M | SMHD, RAIL 168" MILL |
| HLAVI DUTI KAIL | 410204M | SMHD RAIL 204" MILL |
| | 410246M | SMHD, RAIL 246" MILL |

| SYMBOL | DESCRIPTION | LETTER | SUPPORTED MODULE | | |
|----------|----------------------|--------|------------------|--|--|
| AL | ALUMINUM | | THICKNESS | | |
| CLR | CLEAR ANODIZED | В | 30MM - 32MM | | |
| DRK | DARK BRONZE ANODIZED | С | 33MM -36MM | | |
| SS | STAINLESS STEEL | D | 38MM -40MM | | |
| | BLACK OXIDE COATED | К | 39MM -41MM | | |
| DRK SS | SS STAINLESS STEEL | | 45MM -47MM | | |
| <u> </u> | 1 | E | 50MM - 51MM | | |

MID CLAMPS AND END CLAMPS

| S.NO. | PART NUMBER | DESCRIPTION | |
|-------|-------------|-----------------------------|--|
| 1 | 302021C | SM ENDCLAMP B CLR AL | |
| 2 | 302021D | SM ENDCLAMP B DRK AL | |
| 3 | 302022C | SM ENDCLAMP C CLR AL | |
| 4 | 302022D | SM ENDCLAMP C DRK AL | |
| 5 | 302023C | SM ENDCLAMP D CLR AL | |
| 6 | 302023D | SM ENDCLAMP D DRK AL | |
| 7 | 302024C | SM ENDCLAMP E CLR AL | |
| 8 | 302024D | SM ENDCLAMP E DRK AL | |
| 9 | 302025C | SM ENDCLAMP F CLR AL | |
| 10 | 302025D | SM ENDCLAMP F DRK AL | |
| 11 | 302026C | SM ENDCLAMP K CLR AL | |
| 12 | 302026D | SM ENDCLAMP K DRK AL | |
| 13 | 302027C | SM BND MIDCLAMP BC SS | |
| 14 | 302027D | SM BND MIDCLAMP BC DRK SS | |
| 15 | 302028C | SM BND MIDCLAMP EF SS | |
| 16 | 302028D | SM BND MIDCLAMP EF DRK SS | |
| 17 | 302029C | SM BND MIDCLAMP DK SS | |
| 18 | 302029D | SM BND MIDCLAMP DK DRK SS | |
| 19 | 302030D | SM MIDCLAMP PRO DRK | |
| 20 | 302030M | SM MIDCLAMP PRO MILL | |
| 21 | 302035M | SM ENDCLAMP PRO W/CAP | |
| 22 | 302045D | UNIVERSAL AF MID CLAMP DRK | |
| 23 | 302045M | UNIVERSAL AF MID CLAMP MILL | |
| 24 | 302050D | UNIVERSAL AF END CLAMP DRK | |
| 25 | 302050M | UNIVERSAL AF END CLAMP MILL | |



SYSTEM COMPONENTS | 3 INSTALLATION GUIDE | PAGE

COMPONENTS

| S.NO. | PART NUMBER | DESCRIPTION | |
|-------|-------------|----------------------------------|--|
| 1 | 303019M | BND SPLICE BAR PRO SERIES MILL | |
| 2 | 303019D | BND SPLICE BAR PRO SERIES DRK | |
| 3 | 304001C | L-FOOT SERR W/ T-BOLT, CLR | |
| 4 | 304001D | L-FOOT SERR W/ T-BOLT, DRK | |
| 5 | 0090105 | SPLICE TEK SCRW #12-14X3/4" SS | |
| 6 | 0090205 | BND T-BOLT&NUT 3/8" X 3/4" SS | |
| 7 | 0090215 | BND T-BOLT&NUT 3/8" X 1" SS | |
| 8 | 004055M | FLASHKIT PRO, MILL 10 PK | |
| 9 | 004055D | FLASHKIT PRO, DRK 10 PK | |
| 10 | 004015D | SOLARMOUNT FLASHKIT PRO SB, DARK | |
| 11 | 004015M | SOLARMOUNT FLASHKIT PRO SB, MILL | |
| 12 | 004085M | FLASHLOC COMP KIT MILL | |
| 13 | 004085D | FLASHLOC COMP KIT DRK | |
| 14 | 004275M | FLASHLOC DUO MILL | |
| 15 | 004275D | FLASHLOC DUO DARK | |
| 16 | 003250W | #12-14 X 2.50 SCREW HDW SS SD | |
| 17 | 004CT5H | SOLARHOOK UNIV SIDE MT CT5 | |
| 18 | 004CT1H | SOLARHOOK SPANISH 7" BASE | |
| 19 | 004CT2H | SOLARHOOK SPANISH 9" BASE | |
| 20 | 004FLAT | SOLARHOOK FLASHING FLAT | |
| 21 | 004FLCT | SOLARHOOK FLASHING SPANISH FLCT | |
| 22 | 004AT1H | SOLARHOOK FLAT TILE | |
| 23 | 004ST1S | SOLARHOOK STONE COATED MT ST1 | |
| 24 | 004AST1 | SOLARHOOK ADJ STONE COATED ST1 | |
| 25 | 004300M | STANDOFF 3" 2 PIECE AL, MILL | |
| 26 | 004300D | STANDOFF 3" 2 PIECE AL, DRK | |
| 27 | 004400M | STANDOFF 4" 2 PIECE AL, MILL | |

| S.NO. | PART NUMBER | DESCRIPTION |
|-------|-------------|---------------------------------|
| 28 | 004400D | STANDOFF 4" 2 PIECE AL, DRK |
| 29 | 004600M | STANDOFF 6" 2 PIECE AL, MILL |
| 30 | 004600D | STANDOFF 6" 2 PIECE AL, DRK |
| 31 | 004700M | STANDOFF 7" 2 PIECE AL, MILL |
| 32 | 004700D | STANDOFF 7" 2 PIECE AL, DRK |
| 33 | 330007M | AL STNDOFF 3/8" BOLT&EPDMWSHR |
| 34 | 004013C | FLASH SOFT AL 18X18 OATEY 12836 |




THERMAL BREAK4INSTALLATION GUIDEPAGE

EXPANSION JOINT USED AS THERMAL BREAK

Expansion joints prevent buckling of rails or system failure due to thermal expansion. Determine location of expansion joints prior to installation of L-feet and rails. To create a thermal expansion joint, set gap between rails that is sufficient for proper installation of end clamps and tooling to achieve required torque. A thermal break is required when a continuous length of spliced rails exceeds the length, in feet, shown in the table to the right. For additional concerns on thermal breaks in your specific project, please consult a licensed structural engineer.

Rails in expansion joint configurations are considered cantilevered and must follow the cantilever rule, on both sides of the expansion joint, which states that the maximum amount of rail that can be cantilevered is 1/3 the respective adjacent span. An expansion joint must not be spanned by a PV module. Installing a module over an expansion joint would defeat the goal of a thermal break and could result in damage to the array.

Bonding connection for splice used as a thermal break. Option shown uses two Ilsco lugs (Model No. GBL-4DBT P/N GBL-4DBT - see product data sheet for more details) and solid copper wire. Optional grounding may be achieved through Enphase microinverter. See page 11.



| | Maximum Continuous Length (ft.) of Spliced Rails | | | |
|---------|---|-----|---------------------|-----|
| | Solarmount Standard | | Solarmount Light | |
| | Attachment Span | | Attachment Span | |
| ΔT (°F) | 48" | 72" | 48" | 72" |
| 0-40 | 86 | 105 | 70 | 81 |
| 40-50 | 70 | 93 | 62 | 81 |
| 50-60 | 70 | 81 | 54 | 69 |
| 60-70 | 62 | 69 | 54 | 69 |
| 70-80 | 54 | 69 | 46 | 57 |
| 80-90 | 54 | 69 | 46 | 57 |
| 90-100 | 54 | 57 | 46 | 57 |
| 100-120 | 46 | 57 | 38 | 45 |
| 120-140 | 38 | 45 | 38 | 45 |

The values displayed are the maximum allowed rail length, in feet, without a thermal break.

These values apply only to the Flashkit Pro L-foot. For Flashloc Comp Mount, or if your span is less than 48", refer to the Solarmount Design & Engineering Guide for max lengths of continuous rail before a thermal break is required. The installer is responsible for determining the maximum temperature difference (ΔT) used to establish the maximum rail length, without expansion joint, at the install location.

As spans increase, so does the maximum reaction force that the rail exerts on the L-foot. It is the responsibility of the installer to ensure that Maximum Reaction Force does not exceed the shear capacity of the roof connection. See SM Design and Engineering Guide for corresponding reaction forces.

 ΔT refers to the maximum difference in the temperature of the rail between installation and the extreme high or low temperature. The Extreme Annual Design Conditions table at the following url can be used as a reference when determining ΔT .

http://ashrae-meteo.info/



SYSTEM LAYOUT INSTALLATION GUIDE PAGE

PLANNING YOUR SOLARMOUNT INSTALLATIONS

The installation can be laid out with rails parallel to the rafters or perpendicular to the rafters. Note that SOLARMOUNT rails make excellent straight edges for doing layouts.

Center the installation area over the structural members as much as possible. Leave enough room to safely move around the array during installation. Some building codes and fire codes require minimum clearances around such installations, and the installer should check local building code requirements for compliance.

The length of the installation area is equal to:


Standard Series:

- the total width of the modules,
- plus 1/4" inch for each space between modules (for mid- clamp),
- plus approximately 3" (11/2 inches for each Endclamp)

Pro Series:

- the total width of the modules,
- plus 1" inch for each space between modules (for mid- clamp),
- plus 0 to 1" (0 to 1/2 inches for each Endclamp)

RAILS MAY BE PLACED PARALLEL OR PERPENDICULAR TO RAFTERS



LAYING OUT L-FEET FOR TOP CLAMPS

L-feet, in conjunction with proper flashing equipment and techniques, can be used for attachment through existing roofing material, such as asphalt shingles, sheathing or sheet metal to the building structure.


Locate and mark the position of the L-feet lag screw holes within the installation area as shown below. Follow manufacturer module installation guide for rail spacing based on appropriate mounting locations

NOTE: For expansion joint requirements, refer to page 4. Rail Lengths and locations of l-feet for expansion joints will need to be determined at this stage in planning system layout.

If multiple rows are to be installed adjacent to one another, it is not likely that each row will be centered above the rafters. Adjust as needed, following the guidelines below as closely as possible.


Refer to Unirac Solarmount D&E Guide & U-Builder for allowable spans and cantilevers.

LAYOUT WITH RAILS PERPENDICULAR TO RAFTERS (RECOMMENDED)






ROOF ATTACHMENT & L-FEET INSTALLATION GUIDE PAGE




ROOF PREPARATION: Layout and install flashing at rafter locations determined per Design and Engineering Guide.




DRILL PILOT HOLES: Center the roof attachment over the rafter and drill a pilot hole(s) for the lag bolt(s).

NOTE: Determine lag bolt size and embedment depth.

Quick Tip: Pre-drill the pilot hole through the flat flashing lag bolt location for easier installation.





FLASHING INSTALLATION: Insert the flashing so the top part is under the next row of shingles and the hole lines up with the pilot hole.



INSTALL LAG BOLTS & L-FOOT: Insert the lag bolt through the L-Foot in the order shown in the illustration. Verify proper orientation before tightening lag bolts.

For high snow load conditions, install the L-foot as shown above, and install the rail on the downslope face of the L-Foot





2 PIECE ALUMINUM STANDOFF WITH FLASHING & L-FOOT:

- If necessary cut an opening in the roofing material over a rafter to accommodate the flashing riser.
- Install the standoff, ensuring that both lag bolts are screwed into the rafter.
- Insert the flashing under the shingle above and over the shaft of the standoff. (No-Calk[™] collar does not require sealing of the flashing and standoff shaft)
- Add L-Foot to top with bolt that secures the EPDM washer to the top of the standoff. See Standoffs Installation Manual for Additional Details.

Side MOUNT SOLARHOOK:

- Remove or slide up the roof tile, position the roof hook above the roof rafter
- Place SolarHook in the middle of the underlying interlocking tile's valley. Drill 3/16 inch pilot holes through the underlayment into the center of the rafters. Securely fasten each tile hook to the rafters using included lag screws.
- Slide down or re-insert the tile.

See Unirac Solarhook Installation Manual for Additional Information.



SPLICE 7 INSTALLATION GUIDE


SPLICE INSTALLATION (IF REQUIRED PER SYSTEM DESIGN)

If your installation uses SOLARMOUNT splice bars, attach the rails together before mounting to the L-feet/footings. Use splice bars only with flush installation and those that use low-profile tilt legs. A rail must be supported by more than one footing on both sides of the splice. There can be a gap between rails, up to 3/16" at the splice connections. To install, slide T-feature on splice into the T-slot on each rail, centering the splice between the two rails. Tighten each bolt until the bolt-head is flush against the splice and torqued to 10 ft-lbs. Installation is complete when the bonding hardware penetrates the opposite side of the rail and the assembly torque is achieved. T-bolts should not be placed less than a distance of 1" from the end of the rail regardless of a splice.

TORQUE VALUE


Hex head socket size $\frac{1}{2}$ " – Do not exceed 10 ft-lbs. Do not use Anti-Seize. See table on page 4 for max length of spliced rails. An expansion joint is required above the lengths published in the table.


Rails in splice joint configurations are considered cantilevered and must follow the cantilever rule, on both sides of the splice, which states that the maximum amount of rail that can be cantilevered is 1/3 the respective adjacent span. See table on page 4.






ATTACH RAIL TO L-FEET 8 INSTALLATION GUIDE PAGE





PLACE T-BOLT INTO RAIL & SECURE BOLT: Insert 3/8" T-bolt into rail at L-foot locations. Apply Anti-Seize to bolt. Rotate T-bolt into position.

SECURE T-BOLT: Apply Anti-Seize to bolt. Rotate T-bolt into position.




ALIGN POSITION INDICATOR: Hand tighten nut until rail alignment is complete. Verify that position indicator on bolt is vertical (perpendicular to rail)

TORQUE VALUE: 3/8" nut to 30 ft-lbs

ALIGN RAILS: Align one pair of rail ends to the edge of the installation area. The opposite pair of rail ends will overhang installation area. Do not Trim them off until the installation is complete. If the rails are perpendicular to the rafters, either end of the rails can be aligned, but the first module must be installed at the aligned end.


If the rails are parallel to the rafters, the aligned end of the rails must face the lower edge of the roof. Securely tighten all hardware after alignment is complete.

Mount modules to the rails as soon as possible. Large temperature changes may bow the rails within a few hours if module placement is delayed.







MICROINVERTER MOUNTING 9 INSTALLATION GUIDE PAGE



INSTALL MICROINVERTER MOUNT T-BOLT: Apply Anti-Seize and install pre-assembled ¼" dia. bonding T-bolts into top ¼" rail slot at microinverter locations. Rotate bolts into position.




INSTALL MICROINVERTER: Install microinverter on to rail. Engage with bolt.




INSTALL MICROINVERTER:

TORQUE VALUE 1/4" nut to 10 ft-lbs with Anti-Seize.



ALIGN POSITION INDICATOR: Verify that position indicator on bolt is perpendicular to rail.

MICROINVERTER SYSTEM GROUNDING Installation guide Page



SM EQUIPMENT GROUNDING THROUGH ENPHASE MICROINVERTERS


The Enphase M215 and M250 microinverters have integrated grounding capabilities built in. In this case, the DC circuit is isolated from the AC circuit, and the AC equipment grounding conductor (EGC) is built into the Enphase Engage integrated grounding (IG) cabling.

In order to ground the SOLARMOUNT racking system through the Enphase microinverter and Engage cable assembly, there must be a minimum of three PV modules connected to the same trunk cable within a continuous row. Continuous row is defined as a grouping of modules installed and bonded per the requirements of this installation guide sharing the same two rails. The microinverters are bonded to the SOLARMOUNT rail via the mounting hardware. Complete equipment grounding is achieved through the Enphase Engage cabling with integrated grounding (IG). No additional EGC grounding cables are required, as all fault current is carried to ground through the Engage cable.






ELECTRICAL GROUNDING W/ SPLICE & THERMAL BREAK ENPHASE MICROINVERTER FOR SPLICE & THERMAL BREAK ENPHASE FOR SPLICE & THERMA ENPHASE FOR SPLICE & THERMAL BREAK ENPHASE FOR SPLICE & THERMA ENPHASE FOR SPLICE



ELECTRICAL BONDING SPLICE

EXPANSION JOINT USED AS THERMAL BREAK W/ GROUNDING LUGS & COPPER JUMPER EXPANSION JOINT USED AS THERMAL BREAK W/O ELECTRICAL BONDING CONNECTION





GROUNDING LUG MOUNTING DETAILS:


Details are provided for both the WEEB and Ilsco products. The WEEBLug has a grounding symbol located on the lug assembly. The Ilsco lug has a green colored set screw for grounding indication purposes. Installation must be in accordance with NFPA NEC 70, however the electrical designer of record should refer to the latest revision of NEC for actual grounding conductor cable size.

Required if not using approved integrated grounding microinveters

| GROUNDING LUG - BOLT SIZE & DRILL SIZE | | | |
|--|-----------|---------------------------------|--|
| GROUND LUG | BOLT SIZE | DRILL SIZE | |
| WEEBLug | 1/4" | N/A - Place in Top SM Rail Slot | |
| ILSCO Lug | #10-32 | 7/32" | |

• Torque value depends on conductor size.


• See product data sheet for torque value.



WEEBLUG CONDUCTOR - UNIRAC P/N 008002S:

Apply Anti Seize and insert a bolt in the aluminum rail and through the clearance hole in the stainless steel flat washer. Place the stainless steel flat washer on the bolt, oriented so the dimples will contact the aluminum rail. Place the lug portion on the bolt and stainless steel flat washer. Install stainless steel flat washer, lock washer and nut. Tighten the nut until the dimples are completely embedded into the rail and lug.

TORQUE VALUE 10 ft lbs. See product data sheet for more details, Model No. WEEB-LUG-6.7




ILSCO LAY-IN LUG CONDUCTOR - UNIRAC P/N 008009P: Alternate Grounding Lug - Drill, deburr hole and bolt thru both rail walls per table. TORQUE VALUE 5 ft lbs.

See ILSCO product data sheet for more details, Model No. GBL-4DBT.

NOTE: ISOLATE COPPER FROM ALUMINUM CONTACT TO PREVENT CORROSION




INSTALL MODULE END CLAMPS: The End clamp is supplied as an assembly with a 1/2" hex head bolt Slide end clamp on to rail by that is accessible at the ends of rails. The clamp should be installed on the rails prior to installing end modules.



INSTALL END CLAMPS ON RAIL: engaging the two t-guide brackets with the top slot of the rails. Ensure bolt is extended as far as possible so that clamp is positioned at max. distance from end of rail.




POSITION END CLAMPS: Slide end clamp assembly on to rail until bolt head engages with end of rail End clamps are positioned on rails prior to the first end module and prior to the last end module.




ENDCLAMP, FIRST MODULE INSTALLATION GUIDE PAGE


NOTE: To assist insertion of clamp into rail slot, Pressure may be applied to top or side of bracket as shown. Do not force clamp into rail by pushing on bolt with excessive force.




INSTALL FIRST MODULE:

Install the first end module onto rails with the flange of the module frame positioned between end clamps an ends of rails.






ENGAGE CLAMP: While holding module in position and with flange in full contact with rail, rotate end clamp bolt until clamp engages with flange to provide clamp force. To ensure bolt is not over-torqued, use low torque setting on drill or If using an impact driver, stop rotation as soon as impact action of driver begins. **TORQUE VALUE** End clamp bolt to 5 ft-lbs, No anti-seize







BONDING MIDCLAMP INSTALLATION GUIDE PAGE




INSTALL MIDCLAMPS: Midclamp is supplied as an assembly with a T-bolt for module installation. Clamp assemblies may be positioned in rail near point of use prior to module placement.




INSERT MIDCLAMP ASSEMBLY: Insert 1/4" T-Bolt into top slot of rail



MIDCLAMP: Rotate midclamp assembly and slide until clamp is against module frame. Do not tighten nut until next module is in position. Ensure bolt is perpendicular to rail.



PLACE ADJACENT MODULE AGAINST CLAMPS: Modules must be tight against clamps with no gaps. Tighten nut to required torque.




POSITION INDICATOR - SERRATED T-BOLT: Verify the T-bolt position indicator is perpendicular to the rail.


TORQUE VALUE: 11 ft-lbs. No anti-seize.



REMAINING MODULES INSTALLATION GUIDE PAGE




INSTALL REMAINING MID-CLAMPS: Proceed with module installation. Engage each module with previously positioned Midclamp assemblies.




POSITION T-BOLT ALIGNMENT MARKS: Verify that the position indicator(s) & T-bolt shaft(s) are angled in the correct position. Tighten to final torque.

TORQUE VALUE: 11 ft-lbs. No anti-seize.



FINISH MODULE INSTALLATION: Proceed with module installation. Engage each module with the previously positioned clamp assembly:

SMSOLAR BONDING CONNECTION GROUND PATHS INSTALLATION GUIDE PAGE






BONDING MIDCLAMP ASSEMBLY

BONDING MIDCLAMP ASSEMBLY


- 1 Aluminum mid clamp with stainless steel bonding pins that pierce module frame anodization to bond module to module through clamp
- 2 Stainless steel nut bonds aluminum clamp to stainless steel T-bolt
- Serrated T-bolt head penetrates rail anodization to bond T-bolt, nut, clamp, and modules to SM rail



BONDING RAIL SPLICE BAR


- Bonding Hardware creates bond between splice bar and each rail section
- 2 Aluminum splice bar spans across rail gap to create rail to rail bond. Rail on at least one side of splice will be grounded.


Note: Splice bar and bolted connection are non-structural. The splice bar function is rail alignment and bonding.



RAIL TO L-FOOT w/BONDING T-BOLT


- Serrated flange nut removes L-foot anodization to bond L-Foot to stainless steel T-bolt
- Serrated T-bolt head penetrates rail anodization to bond T-bolt, nut, and L-foot to grounded SM rail





BONDING MICROINVERTER MOUNT

- Hex nut with captive lock washer bonds metal microinverter flange to stainless steel T-bolt
- Serrated T-bolt head penetrates rail anodization to bond T-bolt, nut, and L-foot to grounded SM rail System ground including racking and modules may be achieved through the trunk cable of approved microinverter systems. See page 11 for details





RACK SYSTEM GROUND

WEEB washer dimples pierce anodized rail to create bond between rail and lug

Solid copper wire connected to lug is routed to provide final system ground connection. NOTE: Ilsco lug can also be used when secured to the side of the rail. See page 12 for details

SMSOLAR BONDING CONNECTION GROUND PATHS INSTALLATION GUIDE PAGE





TEMPORARY BONDING CONNECTION DURING ARRAY MAINTENANCE

When removing modules for replacement or system maintenance, any module left in place that is secured with a bonding Midclamp will be properly grounded. If a module adjacent to the end module of a row is removed or if any other maintenance condition leaves a module without a bonding mid clamp, a temporary bonding connection must be installed as shown

- Attach Ilsco SGB4 to wall of rail
- Attach Ilsco SGB4 to module frame
- Install solid copper wire jumper to Ilsco lugs

ELECTRICAL CONSIDERATIONS

SOLARMOUNT is intended to be used with PV modules that have a system voltage less than or equal to that allowable by NEC. For standard system grounding a minimum 10AWG, 105°C copper grounding conductor should be used to ground a system, according to the National Electric Code (NEC). It is the installer's responsibility to check local codes, which may vary. See below for interconnection information.

INTERCONNECTION INFORMATION

There is no size limit on how many SOLARMOUNT & PV modules can be mechanically interconnected for any given configuration, provided that the installation meets the requirements of applicable building and fire codes.

GROUNDING NOTES

The installation must be conducted in accordance with the National Electric Code (NEC) and the authority having jurisdiction. Please refer to these resources in your location for required grounding lug quantities specific to your project.


The grounding / bonding components may overhang parts of the array so care must be made when walking around the array to avoid damage.

Conductor fastener torque values depend on conductor size. See product data sheets for correct torque values.

PERIODIC INSPECTION: Conduct periodic inspections for loose components, loose fasteners or any corrosion, immediately replace any affected components.




TRIM AND END CAP INSTALLATION18INSTALLATION GUIDEPAGE




TRIM MIDCLAMPS: Ensure Trim lip is in contact with module face and verify alignment marks on T-bolts are in proper position, tighten midclamp on Trim, repeat at each gap between modules.

TORQUE VALUE: 11 ft-lbs. No anti-seize.



FINISH TRIM INSTALLATION. CUT EXCESS TRIM AND INSTALL TRIM CLIPS:


Attach trim to modules with at least one trim clip at each end of array and at locations where additional support is needed. Each section of trim must be attached to modules with at least one mid clamp.



INSTALL END CAPS: End caps install as supplied on SM standard rail and SM light rail. If desired for SM light rail, the end cap may be modified as shown by hand, or by using a cutting tool.



STANDARD SYSTEM COMPONENTS SERIES INSTALLATION GUIDE PAGE



| Wrenches and Torque | | | |
|---------------------|--------------------------------|--|--|
| Wrench Size | Recommended Torque (ft-lbs) | | |
| 7/16" | *10 | | |
| 9/16" | *30 | | |
| 5/16" | 10 | | |
| | Wrench Size 7/16" 9/16" | | |

Torques are not designed for use with wood connectors *w/Anti-Seize.

Anti-Seize*

Stainless steel hardware can seize up, a process called galling. To significantly reduce its likelihood: 1. Apply minimal lubricant to bolts, preferably Anti-Seize commonly found at auto parts stores 2. Shade hardware prior to installation, and 3. Avoid spinning stainless nuts onto bolts at high speed. **ORAIL**: Supports PV modules. Use at least two per row of modules. Aluminum extrusion, available in mill, clear anodized, or dark anodized.

ORAIL SPLICE: Non structural splice joins, aligns, and electrically bonds rail sections into single length of rail. Forms a rigid splice joint, 4 inches long, preassembled with bonding hardware. Available in dark anodized or mill finish.

QL-FOOT: Use to secure rails through roofing material to building structure. Refer to loading tables or U-Builder for spacing.

OMODULE ENDCLAMP: Provides bond from rail to endclamp. Pre-assembled aluminum clamp available in clear or dark finish. Supplied washer keeps clamp and bolt upright for ease of assembly.

©MODULE MIDCLAMP: Pre-assembled clamp provides module to module and module to rail bond. Stainless steel clamp and T-bolt. Available in clear or dark finish.


OMICROINVERTER MOUNTING BOLT: Pre-assembled bolt and nut attaches and bonds microinverter to rail. Washer at base keeps bolt upright for ease of assembly.

NOTE - POSITION INDICATOR: T-bolts have a slot in the hardware end corresponding to the direction of the T-Head.

NOTE - Standard Series Mid and End Clamps are single use.





SM SOLAR MOUNT






ATTACH RAIL TO L-FEET 21 INSTALLATION GUIDE PAGE





PLACE T-BOLT INTO RAIL & SECURE BOLT: Insert 3/8" T-bolt into rail at L-foot locations. Apply Anti-Seize to bolt. Rotate T-bolt into position.

SECURE T-BOLT: Apply Anti-Seize to bolt. Rotate T-bolt into position.




ALIGN POSITION INDICATOR: Hand tighten nut until rail alignment is complete. Verify that position indicator on bolt is vertical (perpendicular to rail)

TORQUE VALUE: 3/8" nut to 30 ft-lbs

ALIGN RAILS: Align one pair of rail ends to the edge of the installation area. The opposite pair of rail ends will overhang installation area. Do not Trim them off until the installation is complete. If the rails are perpendicular to the rafters, either end of the rails can be aligned, but the first module must be installed at the aligned end.


If the rails are parallel to the rafters, the aligned end of the rails must face the lower edge of the roof. Securely tighten all hardware after alignment is complete.

Mount modules to the rails as soon as possible. Large temperature changes may bow the rails within a few hours if module placement is delayed.







ENDCLAMP & FIRST MODULE INSTALLATION GUIDE PAGE



INSTALL MODULE ENDCLAMPS: The Endclamp is supplied as an assembly with a T-bolt, serrated flange nut, and washer. The washer retains the clamp at the top of the assembly. This will enable the clamp to remain upright for module installation.




INSERT ENDCLAMP T-BOLT: Insert 1/4" T-bolt into rail.




ROTATE ENDCLAMP T-BOLT: Rotate T-bolt into position. Verify that the position indicator & T-bolt shaft are angled in the correct position.

End clamps are positioned on rails prior to the first end module and installed after the last end module.




INSTALL FIRST MODULE: Install the first end module onto rails. Engage module frame with Endclamps. Verify that the position indicator & T-bolt shaft are angled in the correct position.






POSITION INDICATOR - SERRATED T-BOLT: Verify the T-bolt position indicator is perpendicular to the rail.




POSITION INDICATOR - NON-SERRATED T-BOLT: Verify the T-bolt position indicator is angled as shown. **FOR USE WITH MILL FINISH RAIL ONLY**.




BONDING MIDCLAMP & TRIM INSTALLATION GUIDE PAGE




INSTALL MIDCLAMPS: Midclamp is supplied as an assembly with a T-bolt for module installation. Clamp assemblies may be positioned in rail near point of use prior to module placement.



INSERT MIDCLAMP T-BOLT: Apply Anti-Seize and insert 1/4" T-bolt into rail.




ROTATE MIDCLAMP T-BOLT: Rotate bolt into position and slide until bolt and clamp are against module frame. Do not tighten nut until next module is in position. Verify that the position indicator & T-bolt shaft are angled in the correct position.



POSITION INDICATOR - SERRATED T-BOLT: Verify the T-bolt position indicator is perpendicular to the rail.

TRIM INSTALLATION INSTRUCTIONS




TRIM MIDCLAMPS: Ensure Trim lip is in contact with module face and verify alignment marks on T-bolts are in proper position, tighten midclamp on Trim, repeat at each gap between modules.

TORQUE VALUE: 1/4" nuts to 10 ft-lbs with Anti Seize




REMAINING MODULES & TRIM INSTALLATION GUIDE PAGE




INSTALL REMAINING MID-CLAMPS: Proceed with module installation. Engage each module with previously positioned Midclamp assemblies.

NOTE: Apply Anti-Seize to each Mid Clamp prior to installation.




POSITION T-BOLT ALIGNMENT MARKS: Verify that the position indicator(s) & T-bolt shaft(s) are angled in the correct position.

TORQUE VALUE: 1/4" nuts to 10 ft-lbs. with Anti Seize




INSTALL ENDCLAMPS: Apply Anti-Seize and install final Endclamps in same manner as first Endclamps. Slide clamps against module.

TORQUE VALUE: 1/4" nuts to 10 ft-lbs. with Anti Seize.




POSITION T-BOLT ALIGNMENT MARKS & CUT RAIL: Verify that the position indicator(s) & T-bolt shaft(s) are angled in the correct position. Trim off any excess rail, being careful not to cut into the roof. Allow ½" between the Endclamp and the end of the rail.



FINISH MODULE INSTALLATION: Proceed with module installation. Engage each module with the previously positioned clamp assembly:

- Install second module
- Install remaining Midclamps & modules & position alignment marks
- Install Endclamps & position alignment marks
- Cut rail to desired length

TRIM INSTALLATION INSTRUCTIONS




FINISH TRIM INSTALLATION, INSTALL ENDCLAMP & CUT EXCESS RAIL:

Install final endclamp & Cut away excess Trim at end of array or where required for proper cantilevers. See D&E Guide or U-Builder for allowable cantilevers.


TORQUE VALUE 1/4" nuts to 10 ft-lbs with Anti Seize



TRIM RETROFIT INSTALLATION GUIDE25INSTALLATION GUIDEPAGE




PREPARATION: At front edge of array, ensure at least 3.25 inches of space between modules and roof surface and that modules are aligned to within 3/8". Plan for Trim length so that Endclamps can be properly installed.




1ST MIDCLAMP: Position Trim in front of array. Insert Midclamp into the Trim slot, aligned with the gap between the 1st two modules at either end of array.

NOTE: Apply Anti-Seize to Each Mid-Clamp prior to installation




MOUNT TRIM: Position Trim beneath modules by sliding T-bolt into gap between modules and tighten. Midclamp should stay in position and support Trim. Tighten snugly enough so that Trim is held firmly in place.


TORQUE VALUE: Do not exceed specified torque value (10 ft-lbs)



CLEAR T-BOLT SLOT: Rotate unattached end of Trim out and away from array so T-bolt slot (at next T-bolt insertion point) is clear of modules. This may require force to deflect the Trim slightly. Deflect only enough to insert T-bolt.




INSERT MIDCLAMPS: Insert T-bolt into slot and slide clamp (rotating Trim) into position between modules and leave loose. Continue to work down array, inserting Midclamps and positioning in gaps between modules.




FASTEN MIDCLAMPS: Return to each inserted Midclamp. Ensuring Trim lip is in contact with module face and verifying alignment marks on T-bolts are in proper position, tighten clamp.

TORQUE VALUE 1/4" nuts to 10 ft-lbs w/ Anti Seize




ENDCLAMPS: Install Endclamps per previous Endclamp install instructions

TORQUE VALUE 1/4" nuts to 10 ft-lbs w/ Anti Seize




CUT EXCESS TRIM: Mark excess Trim and cut at end of array or where required for proper cantilevers.

SMSOLAR BONDING CONNECTION GROUND PATHS INSTALLATION GUIDE PAGE



BONDING MIDCLAMP ASSEMBLY

- Stainless steel Midclamp points, 2 per module, pierce module frame anodization to bond module to module through clamp.
- 2 Serrated flange nut bonds stainless steel clamp to stainless steel T-bolt
- Serrated T-bolt head penetrates rail anodization to bond T-bolt, nut, clamp, and modules to grounded SM rail.




ENDCLAMP ASSEMBLY

Serrated flange nut bonds aluminum Endclamp
to stainless steel T-bolt

 Serrated T-bolt head penetrates rail anodization
 to bond T-bolt, nut, and Endclamp to grounded SM rail

Note: End clamp does not bond to module frame.




BONDING RAIL SPLICE BAR

Bonding Hardware creates bond between splice bar and each rail section


Aluminum splice bar spans across rail gap to create rail to rail bond. Rail on at least one side of splice will be grounded.


Note: Splice bar and bolted connection are non-structural. The splice bar function is rail alignment and bonding.



RAIL TO L-FOOT w/BONDING T-BOLT

- Serrated flange nut removes L-foot anodization to bond L-Foot to stainless steel T-bolt
- Serrated T-bolt head penetrates rail anodization to bond T-bolt, nut, and L-foot to grounded SM rail






BONDING MICROINVERTER MOUNT

Hex nut with captive lock washer bonds metal microinverter flange to stainless steel T-bolt

Serrated T-bolt head penetrates rail anodization to bond T-bolt, nut, and L-foot to grounded SM rail System ground including racking and modules may be achieved through the trunk cable of approved microinverter systems. See page 11 for details




RACK SYSTEM GROUND

1 WEEB washer dimples pierce anodized rail to create bond between rail and lug

2 Solid copper wire connected to lug is routed to provide final system ground connection.

NOTE: Ilsco lug can also be used when secured to the side of the rail. See page 11 for details

SMSOLAR BONDING CONNECTION GROUND PATHS INSTALLATION GUIDE PAGE



TEMPORARY BONDING CONNECTION DURING ARRAY MAINTENANCE

When removing modules for replacement or system maintenance, any module left in place that is secured with a bonding Midclamp will be properly grounded. If a module adjacent to the end module of a row is removed or if any other maintenance condition leaves a module without a bonding mid clamp, a temporary bonding connection must be installed as shown

- Attach Ilsco SGB4 to wall of rail
- Attach Ilsco SGB4 to module frame
- Install solid copper wire jumper to Ilsco lugs

ELECTRICAL CONSIDERATIONS

SOLARMOUNT is intended to be used with PV modules that have a system voltage less than or equal to that allowable by the NEC. For standard system grounding a minimum 10AWG, 105°C copper grounding conductor should be used to ground a 1000 VDC system, according to the National Electric Code (NEC). It is the installer's responsibility to check local codes, which may vary. See below for interconnection information.

INTERCONNECTION INFORMATION

There is no size limit on how many SOLARMOUNT & PV modules can be mechanically interconnected for any given configuration, provided that the installation meets the requirements of applicable building and fire codes.

GROUNDING NOTES

The installation must be conducted in accordance with the National Electric Code (NEC) and the authority having jurisdiction. Please refer to these resources in your location for required grounding lug quantities specific to your project.

The grounding / bonding components may overhang parts of the array so care must be made when walking around the array to avoid damage.

Conductor fastener torque values depend on conductor size. See product data sheets for correct torque values.




CODE COMPLIANCE NOTES INSTALLATION GUIDE **28** PAGE

UL2703 CERTIFICATION MARKING LABEL

Unirac SOLARMOUNT is listed to UL 2703. Certification marking is embossed on all mid clamps as shown. Labels with additional information will be provided . After the racking system is fully assembled, a single label should be applied to the SOLARMOUNT rail at the edge of the array. Before applying the label, the corners of the label that do not pertain to the system being installed must be removed so that only the installed system type is showing. **Note: The sticker label should be placed such that it is visible, but not outward facing.**









MECHANICAL LOAD TEST SYSTEM CERTIFICATION PAGE

The SOLARMOUNT system has been certified and listed to the UL 2703 standard (Rack Mounting Systems and Clamping Devices for Flat-Plate Photovoltaic Modules and Panels). This standard included electrical grounding, electrical bonding, mechanical load and fire resistance testing.

In conducting these tests, specific modules are selected for their physical properties so that the certifications can be broadly applied. The following lists the specific modules that were tested and the applicability of those certifications to other modules that might come onto the market. PV modules may have a reduced mechanical load rating, independent of the SM load rating. Please consult the PV module manufacturer's installation guide for more information.

In addition to UL 2703 certification, Unirac performs internal testing beyond the requirements of certification tests in order to establish system functional limits, allowable loads, and factors of safety. These tests include functional system tests, and destructive load testing.

MECHANICAL LOAD TEST MODULES

The modules selected for UL 2703 mechanical load testing were selected to represent the broadest range possible for modules on the market. The tests performed cover the following basic module parameters:

Frame thicknesses greater than or equal to 1.0 mm

Basic single and double wall frame profiles (some complex frame profiles could require further analysis to determine applicability) Clear and dark anodized aluminum frames`

| Tested Modules | | | | |
|------------------------|-----------------|----------------|--|--|
| Module Manufacturer | Model/Series | Area [sqft] | UL2703 Certification Load Ratings | |
| Hyundai | HiS-S325TI | 21.06 | Down– 113 PSF, Up – 50 PSF Down-Slope – 15 PSF | |
| SunPower | SPR-P19-395-COM | 22.20 | Down– 113 PSF, Up – 50 PSF Down-Slope – 15 PSF | |
| First Solar | FS-6xxx-P | 27.12 | Down– 33.9 PSF, Up – 33.9 PSF Down-Slope – 16.5 PSF | |



SYSTEM LEVEL FIRE CLASSIFICATION SYSTEM CERTIFICATION PAGE

SYSTEM LEVEL FIRE CLASSIFICATION

The system fire class rating requires installation in the manner specified in the SOLARMOUNT Installation Guide. SOLARMOUNT has been classified to the system level fire portion of UL2703. SOLARMOUNT has achieved system level performance for steep sloped roofs and low sloped roofs. See table below for definition of steep sloped and low sloped roofs. The system is to be mounted over fire resistant roof covering rated for the application. There is no required minimum or maximum height limitation above the roof deck to maintain the system fire rating for SOLARMOUNT. Module Types, System Level Fire Ratings, & Mitigation Requirements are listed below:

| ROOF TYPE | Rail Type | Module Fire Type | System Level Fire Rating | Rail Direction | Module Orientation | Mitigation Required |
|---|-------------------------------|---|-----------------------------|---|--------------------------|--|
| Steep Slope - roof pitches ≥ 2 in/ft | Standard & HD Rail | 1, 2, 3 with metal frame, 10 with metal frame, 19, 22, 25, 29, & 30 | Class A | Parallel OR Perpendic- ular to Ridge | Landscape OR Portrait | None Required |
| | Light Rail | 1 & 2 | | | | None Required |
| | Standard, Light, & HD Rail | 4 & 5 | | | | Trim installation per Solar Mount Installation Guide |
| | Standard & HD Rail | - | Class A | Parallel OR Perpendic- ular to Ridge | Landscape OR Portrait | |
| Low Slope - roof | Light Rail | | | | | None Required |
| pitches < 2in/ft | Standard, Light, & HD Rail | .,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,, | | | | |

This racking system may be used to ground and/or mount a PV module complying with UL1703 or UL61730 only when the specific module has been evaluated for grounding and/or mounting in compliance with the included instructions.



Electrical Bonding and Grounding Test Modules

The list below is not exhaustive of compliant modules but shows those that have been evaluated and found to be electrically compatible with the SOLARMOUNT system.

| Manufacture | Module Model / Series | Manufacture | Module Model / Series | Manufacture | Module Model / Series |
|--|---|---|--|----------------|--|
| Aionrise | AION60G1, AION72G1 | | CS5A-M CS6K-(M/MS/MS AllBlack/P/P HE) CS6P-(M/P) CS6R-MS CS6U-(M/P/P HE) CS6W-(MS/MB-AG) CS6X-P, CSX-P ELPS CS6(A/P)-MM | HT-SAAE | HT60-156M-C HT60-156M(V)-C HT72-156(M/P) HT72-156P-C, HT72-156P(V)-C HT72-156M(PDV)-BF, HT72-156M(PD)-BF HT72-166M, HT72-18X |
| | P-Series & S-Series DNA-120-(MF/BF)10-xxxW DNA-120-MF10 DNA-120-(MF/BF)23 DNA-144 (MF/F)23 | Canadian Solar (cont.) | | | |
| Aptos Solar | DNA-144-(MF/BF)23 DNA-120-(MF/BF)26 | | | Hyperion Solar | HY-DH108P8 |
| | DNA-144-(MF/BF)26 DNA-108-(MF/BF)10-xxxW | Centrosolar America | C-Series & E-Series | _ | KG, MG, RW, TG, RI, RG, TI, KI, HI Series HiA-SxxxHG, HiD-SxxxRG(BK), HiS-S400PI |
| Astronergy | CHSM6612 M, M/HV CHSM6612P Series CHSM6612P/HV Series | CertainTeed | CT2xxMxx-01, CT2xxPxx-01, CTxxxMxx-01 CTxxxPxx-01, CTxxxMxx-02, CTxxxMxx-03 CTxxxMxx-04, CTxxxHC11-04 | Hyundai | HIA-SXXXHG, HID-SXXXKG(BK), HIS-S400PI HIS-SxxXYH(BK) HIS-SxxXG(BK) HIN-SxxXXG(BK) |
| 57 | CHSM72M-HC | Eco Solargy | Orion 1000 & Apollo 1000 | | |
| CHSM72M(DG)/F-BH Auxin AXN6M610T AXN6P610T AXN6M612T AXN6M612T AXN6P612T | EMMVEE | ExxxP72-B ExxxM72-B ExxxH CM120-B | ITEK | iT-SE Series | |
| | | ET Solar | ET AC Module, ET Module ET-M772BH520-550WW/WB | Japan Solar | JPS-60 & JPS-72 Series |
| Ac-xxx(M/P)/60S, AC-xxx(M/P)/72S AC-xxxP/156-60S AC-xxxMH/120(S/V/SB/VB) Ac-xxXMH/144(S/V/SB/VB) | AC-xxxP/156-60S | First Solar | FS-6XXX(A) FS-6XXX(A)-P,FS-6XXX(A)-P-I | | JAM72D30MB, JAM78D10MB JAM72S30 /MR JAP6 60-xxx JAM6(K)-60/xxx, JAP6(k)-72-xxx/4BB JAP72S##-xxx/** JAP6(k)-60-xxx/4BB, JAP60S##-xxx/** JAM6(k)-72-xxx/*, JAM72S#-xxx/** JAM6(k)-60-xxx/*, JAM60S##-xxx/** i. ##: 01, 02, 03, 09, 10 ii. **: SC, PR, BP, HiT, IB, MW, MR ** = Backsheet, ## Cell technology |
| | | Flextronics | FXS-xxxBB | | |
| Boviet | BVM6610, BVM6612 | Freedom Forever | FF-MP-BBB-xxx, FF-MP1-BBB-xxx | | |
| BYD | P6K & MHK-36 Series | FreeVolt | PVGraf | JA Solar | |
| Canadian Solar | CS1(H/K/U/Y)-MS CS3K-(MB/MB-AG/MS/P/P HE/PB-AG) CS3L-(MS/P) CS3N-MS CS3U-(MB/MB-AG/MS/P/P HE/PB/PB-AG) CS3W-(MS/MB-AG/P/P-PB-AG) CS3Y-MB-AG | GCL | GCL-P6 & GCL-M6 Series | | |
| | | Hansol | TD-AN3, TD-AN4 UB-AN1, UD-AN1 | | |
| | | Hanwha SolarOne | HSL 60 | | |
| | | Heliene | 36M, 36P 60M, 60P, 72M & 72P Series 144HC M6 144HC M10 SL Bifacial | | |

• Unless otherwise noted, all modules listed above include all wattages and specific models within that series. Variable wattages are represented as "xxx"

• Items in parenthesis are those that may or may not be present in a compatible module's model ID

• Slashes "/" between one or more items indicates that either of those items may be the one that is present in a module's model ID

• The frame profile must not have any feature that might interfere with the bonding devices that are integrated into the racking system

• Use with a maximum over current protection device OCPD of 30A

• Listed models can be used to achieve a Class A fire system rating for steep slope applications. See page 30



Electrical Bonding and Grounding Test Modules

The list below is not exhaustive of compliant modules but shows those that have been evaluated and found to be electrically compatible with the SOLARMOUNT system.

| Manufacture | Module Model / Series | Manufacture | Module Model / Series | Manufacture | Module Model / Series |
|-----------------------------|--|----------------------|--|-------------|---|
| Jinko | JKM & JKMS Series JKMxxxM-72HL-V JKMxxxM-72HL4-(T)V JKMxxxM-72HLM-TV JKMxxxM-7RL3-V JKMxxxM-72HL4-TV KD-F & KU Series | LONGi | LR4-60(HPB/HPH) LR4-72(HPH) LR6-60 LR6-60(BK/HPB/HPH/HV/PB/PE/PH) LR6-72 LR6-72(BK/HV/PB/PE/PH) RealBlack LR4-60HPB RealBlack LR6-60HPB | Peimar | SGxxxM (FB/BF) SMxxxM |
| | | | | Phono Solar | PSxxxM1-20/U PSxxxM1H-20/U PSxxxM1H-20UH PSxxxM4(H)-24/TH PSxxxM1-20/UH PSxxxM1-20/UH PSxxxM1-20/UH PSxxxM1-24/T PSxxxM-24/T PSxxxM-24/TH PSxxxM-24/TH |
| Kyocera | | Maxeon | SPR-MAX3-xxx-COM | | |
| | LSxxxHC(166) | Meyer Burger | Meyer Burger Black, Meyer Burger White Meyer Burger Glass | | |
| LA Solar LSxxxBL LSxxxHC | | Mission Solar Energy | MSE Mono, MSE Perc MSExxx(SR8T/SR8K/SR9S/SX5T) MSExxx(SX5K/SX6W) | | |
| | LGxxx(E1C/E1K/N1C/N1K/N2T/N2W/S1C/ S2W/Q1C/Q1K)-A5 LGxxx(A1C/M1C/M1K/N1C/N1K/Q1C/Q1K/ QAC/QAK)-A6 LGxxxN2W-B3 LGxxxN2T-B5 LGxxxN1C/N1K/N2T/N2W)-E6 LGxxx(N1C/N1K/N2T/N2W)-E6 LGxxx(N1C/N1K/N2W/S1C/S2W)-G4 LGxxx(N1K/N1W/N2T/N2W)-L5 LGxxx(N1C/N1C/Q1C/Q1K)-N5 LGxxx(N1C/N1K/N2W/Q1C/Q1K)-V5 LGxxxN3K-V6 | | | Prism Solar | P72 Series, P72X-xxx |
| | | Mitrex | Mxxx-L3H, Mxxx-I3H | Q.Cells | Plus, Pro, Peak, G3, G4, Peak G5(SC) , G6(+)(SC)(AC), G7, G8(+), Plus, Pro, Peak L-G2, L-G4, L-G5 Peak L-G5, L-G6, L-G7, L-G8(BFF) Q.PEAK DUO(BLK)-G6+ Q.PEAK DUO BLK-G6+/TS Q.PEAK DUO (BLK)-G7 |
| | | Mitsubishi | MJE & MLE Series | | |
| | | Neo Solar Power Co. | D6M Series | | |
| LG Electronics | | NE Solar | NESE xxx-72MHB-M10 NESE xxx-60MH-M6 | | |
| | | Panasonic | VBHNxxxSA06/SA06B/SA11/SA11B VBHNxxxSA15/SA15B/SA16/SA16B, VBHNxxxKA, VBHNxxxKA03/04, VBHNxxxSA17/SA17G/SA17E/SA18/SA18E, VBHNxxxZA01/ZA02/ZA03/VBHNxxxZA04 EVPVxxx EVPVxxx(H/K/PK/HK) | | |

• Unless otherwise noted, all modules listed above include all wattages and specific models within that series. Variable wattages are represented as "xxx"

- Items in parenthesis are those that may or may not be present in a compatible module's model ID
- Slashes "/" between one or more items indicates that either of those items may be the one that is present in a module's model ID
- The frame profile must not have any feature that might interfere with the bonding devices that are integrated into the racking system
- Use with a maximum over current protection device OCPD of 30A
- Listed models can be used to achieve a Class A fire system rating for steep slope applications. See page 30



Electrical Bonding and Grounding Test Modules

The list below is not exhaustive of compliant modules but shows those that have been evaluated and found to be electrically compatible with the SOLARMOUNT system.

| Manufacture | Module Model / Series | Manufacture | Module Model / Series | Manufacture | Module Model / Series |
|--|---|---|---|--|--|
| Q. Q. Q. | Q.PEAK DUO L-(G7/G7.1/G7.2/G7.3/G7.7) | S-Energy SN72 & SN60 Series | | Sunmac Solar | M754SH-BB Series |
| | Q.PEAK DUO (BLK) G8(+) Q.PEAK DUO L-(G8/G8.1/G8.2/G8.3) Q.PEAK DUO L-G8.3 (BFF/BFG/BGT) | | SN72 & SN60 Series | SunPower | AC, X-Series, E-Series & P-Series SPR E20 435 COM (G4 Frame) Axxx-BLK-G-AC, SPR-Mxxx-H-AC SPR-Mxxx-H-AC |
| | Q.PEAK DUO (BLK) ML-G9(+) Q.PEAK DUO XL-(G9/G9.2/G9.3) | Seraphim | SEG-(6PA/6PB/6MA/6MA-HV/6MB/E01/E11) SRP-(6QA/6QB) SRP-xxx-6MB-HV, SRP-320-375-BMB-HV, SRP-xxx-BMC-HV, SRP-390-450-BMA-HV, SRP-xxx-BMZ-HV, SRP-390-405-BMD-HV | | |
| | Q.PEAK DUO XL-G9.3/BFG | | | SunTech | STP, STPXXXS - B60/Wnhb |
| Q.Cells (cont.) | Q.PEAK DUO-G10+ Q.PEAK DUO BLK G10(+) Q.PEAK DUO BLK G10+ /AC | | | Talesun | TP572, TP596, TP654, TP660 TP672, Hipor M, Smart, TD6172M |
| | Q.PEAK DUO (BLK) ML-G10(a)(+) | Sharp | NU-SA & NU-SC Series | Tesla | SC, SC B, SC B1, SC B2, TxxxS, TxxxH |
| Q.PEAK DUO XL-(G10/G10.2/G10.3/G10.c/ G10.d) Q.PEAK DUO XL-G10.3/BFG Q.PEAK DUO XL-G10.d/BFG Q.PEAK DUO XL-(G11.2/G11.3) Q.PEAK DUO XL-G11.3/BFG REC YYYAA (RLK /Pure) | G10.d) Q.PEAK DUO XL-G10.3/BFG | Silfab | SLA-M, SLA-P, SLG-M, SLG-P & BC Series SIL-xxx(BK/BL/HC/HC+/HL/HM/HN/ML/NL/ NT/NX/NU) | Trina | PA05, PD05, DD05, DD05, DD06, DE06, DE09.05 PD14, PE14, DD14, DE14, DE15, DE15V(II) DEG15HC.20(II), DEG15MC.20(II) DEG15VC.20(II), DE18M(II), DEG18MC.20(II) DE19, DEG19C.20 |
| | - | Solar4America | S4Axxx-108MH10BB, S4Axxx-72MH5BB | | |
| | - , , , | SolarEver USA | SE-166*83-xxxM-120N | | |
| | RECxxxAA (BLK/Pure) | | SE-182*91-xxxM-108N | TSMC | TS-150C2 CIGSw |
| RECXXXX (BCIVINE) RECXXXNP (N-PEAK) RECXXXNP2 (Black) RECXXXPE, RECXXXPF72 REC RECXXXTP, RECXXXTP72 RECXXXTP2(M/BLK2) RECXXXTP25(M)72 RECXXTP3M (Black) RECXXTP4 (Black) | Solaria | PowerXT-xxxR-(AC/PD/BD) PowerXT-xxxC-PD PowerXT-xxxR-PM (AC) PowerX-400R | Universal Solar | UNI4xx-144BMH-DG UNI5xx-144BMH-DG UNIxxx-108M-BB UNIxxx-120M-BB | |
| | RECxxxTP2S(M)72 | Solartech | STU HJT, STU PERC & Quantum PERC | | UNIxxx-120MH |
| | | SolarWorld | Sunmodule Protect, Sunmodule Plus/Pro | Upsolar | UP-MxxxP, UP-MxxxM(-B) |
| | | SS-M-360 to 390 Series | | D7Kxxx(H7A/H8A), D7Mxxx(H7A/H8A) | |
| Renesola | All 60-cell modules | Sonali | SS-M-390 to 400 Series SS-M-440 to 460 Series SS-M-430 to 460 BiFacial Series | URECO | FAKxxx(C8G/E8G), FAMxxxE7G-BB FAMxxxE8G(-BB), FBKxxxM8G F6MxxxE7G-BB FBMxxxMFG-BB |
| Risen | RSM Series, RSM110-8-xxxBMDG |] | | | |
| SEG Solar | SEG-xxx-BMD-HV/TB | Sun Edison | F-Series, R-Series | | Eldora, Somera, Ultima |
| | | Suniva | MV Series & Optimus Series (35mm) | Vikram | PREXOS VSMDHT.60.AAA.05 PREXOS VSMDHT.72.AAA.05 |

• Unless otherwise noted, all modules listed above include all wattages and specific models within that series. Variable wattages are represented as "xxx"

• Items in parenthesis are those that may or may not be present in a compatible module's model ID

• Slashes "/" between one or more items indicates that either of those items may be the one that is present in a module's model ID

• The frame profile must not have any feature that might interfere with the bonding devices that are integrated into the racking system

• Use with a maximum over current protection device OCPD of 30A

• Listed models can be used to achieve a Class A fire system rating for steep slope applications. See page 30



Electrical Bonding and Grounding Test Modules

The list below is not exhaustive of compliant modules but shows those that have been evaluated and found to be electrically compatible with the SOLARMOUNT system.

| Manufacture | Module Model / Series |
|--------------|------------------------------------|
| | VNS-72M1-5-xxxW-1.5, |
| | VNS-72M3-5-xxxW-1.5, |
| Vina | VNS-144M1-5-xxxW-1.5, |
| | VNS-144M3-5-xxxW-1.5, |
| | VNS-120M3-5-xxxW-1.0 |
| | VSUNxxx-60M-BB, VSUNxxx-72MH |
| | VSUN4xx-144BMH |
| | VSUN4xx-144BMH-DG |
| | VSUN5xx-144BMH-DG |
| VSUN | VSUNxxx-108M-BB VSUNxxx-120M-BB |
| | VSUNxxx-120M-BB |
| | VSUNXXX-120DMIN VSUNXXX-132BMH |
| | VSUNXXX-132BMH VSUNXXX-108BMH |
| Waaree | Ahnay Series Bi-33 |
| | |
| Winaico | WST & WSP Series |
| Yingli | YGE & YLM Series |
| Yotta Energy | YSM-B450-1 |
| | ZXM6-72 Series, ZXM6-NH144 |
| ZNShine | ZXM6-NHLDD144 |
| | ZXM7-SH108 Series |

• Unless otherwise noted, all modules listed above include all wattages and specific models within that series. Variable wattages are represented as "xxx"

- Items in parenthesis are those that may or may not be present in a compatible module's model ID
- Slashes "/" between one or more items indicates that either of those items may be the one that is present in a module's model ID
- The frame profile must not have any feature that might interfere with the bonding devices that are integrated into the racking system
- Use with a maximum over current protection device OCPD of 30A
- Listed models can be used to achieve a Class A fire system rating for steep slope applications. See page 30



APPENDIX A FLASHKIT PRO INSTALLATION PAGE





INSTALL L-FOOT

STEP 2



ATTACH L-FOOT TO RAIL

• Drive the lag bolt down until the L-foot is held firmly in place. It is normal for the EPDM on the underside of the stainless steel backed EPDM washer to compress and expand beyond the outside edge of the steel washer when the proper torque is applied.

TIP:

- Use caution to avoid over-torqueing the lag bolt if using an impact driver.
- Repeat Steps 1 and 2 at each roof attachment point.

STEP 3 ATTACH L-FOOT TO RAIL

- Insert the included 3/8"-16 T-bolts into the lower slot on the Rail (sold separately), spacing the bolts to match the spacing between the roof attachments.
- Position the Rail against the L-Foot and insert the threaded end of the T-Bolt through the continuous slot in the L-Foot. Apply anti-seize to bolt threads to prevent galling of the T-bolt and included 3/8" serrated flange nut. Place the 3/8" flange nut on the T-bolt and finger tighten. Repeat STEP 3 until all L-Feet are secured to the Rail with a T-bolt. Adjust the level and height of the Rail and torque each bolt to 30ft-lbs.

PRE-INSTALL

- Locate roof rafters and snap chalk lines to mark the installation point for each roof attachment.
- Drill a 7/32" pilot hole at each roof attachment. Fill each pilot hole with sealant.

STEP 1 INSTALL **FLASH**KIT PRO FLASHING

 Add a U-shaped bead of roof sealant to the underside of the flashing with the open side of the U pointing down the roof slope. Slide the aluminum flashing underneath the row of shingles directly up slope from the pilot hole as shown. Align the indicator marks on the lower end of the flashing with the chalk lines on the roof to center the raised hole in the flashing over the pilot hole in the roof. When installed correctly, the flashing will extend under the two courses of shingles above the pilot hole.

STEP 2 INSTALL L-FOOT

• Fasten L-foot and Flashing into place by passing the included lag bolt and pre-installed stainless steel-backed EPDM washer through the L-foot EPDM grommet, and the raised hole in the flashing, into the pilot hole in the roof rafter.

DocuSign Envelope ID: 4C077C38-FA98-419B-B651-E66DE9437930



1.75"

APPENDIX B Flashloc comp installation Page

PRE-INSTALL

Snap chalk lines for attachment rows. On shingle roofs, snap lines 1-3/4" below upslope edge of shingle course. Locate rafters and mark attachment locations. At each location, drill a 7/32" pilot hole. Clean roof surface of dirt, debris, snow, and ice. Next, BACKFILL ALL PILOT HOLES WITH SEALANT. NOTE: Space mounts per racking system install specifications.

STEP 1: SECURE

Place **FLASH**LOC over pilot hole with lag on down-slope side. Align indicator marks on sides of mount with chalk line. Pass included lag bolt and sealing washer through **FLASH**LOC into pilot hole. Drive lag bolt until mount is held firmly in place.

NOTE: The EPDM in the sealing washer will expand beyond the edge of the metal washer when proper torque is applied.

STEP 2: SEAL

Insert tip of UNIRAC provided sealant into port. Inject until sealant exits both vents. Follow sealant manufacturer's instructions. Follow sealant manufacturer's cold weather application guidelines, if applicable.

Continue array installation, attaching rails to mounts with provided T-bolts.



NOTE: When **FLASH**LOC is installed over gap between shingle tabs or vertical joints, fill gap/joint with sealant between mount and upslope edge of shingle course.

USE ONLY UNIRAC APPROVED SEALANTS: Chemlink Duralink 50, Chemlink M-1, Geocel 4500, or Geocel S-4





APPENDIX C Flashloc duo installation Page



PRE-INSTALL CLEAN SURFACE AND MARK LOCATION

Ensure existing roof structure is capable of supporting loads prescribed in Flashloc Duo D&E Guide. Clean roof surface of dirt, debris, snow and ice.

Snap chalk lines for attachment rows. On shingle roofs, snap lines 1/4" below upslope edge of shingle coarse. This line will be used to align the upper edge of the mount.

NOTE: Space mounts per span charts found in Flashloc Duo D&E Guide.



STEP ONE: SECURE

ATTACHING TO A RAFTER: Place FLASHLOC DUO over rafter location and align upper edge of mount with horizontal chalk line. Secure mount with the two (2) provided rafter screws. BACKFILL ALL PILOT HOLES WITH SEALANT.

ATTACHING TO SHEATHING: Place FLASHLOC DUO over desired location and align upper edge of mount with horizontal chalk line. Secure mount with the two (2) provided rafter screws. Next, secure mount with four (4) deck screws by drilling through the FLASHLOC DUO deck mount hole locations. Unirac recommends using a drill as opposed to an impact gun to prevent over-tightening or stripping roof sheathing.

IMPORTANT: SECURELY ATTACH MOUNT BUT DO NOT OVERTIGHTEN SCREWS.



STEP TWO: SEAL

Insert tip of UNIRAC approved sealant into port and inject until sealant exits vent. Continue array installation, attaching rails to mounts with provided T-bolts. Follow sealant manufacturer's instructions. Follow sealant manufacturer's cold weather application guidelines, if applicable.

NOTE: When FLASHLOC DUO is installed over gap between shingle tabs or vertical joints, fill gap/joint with sealant between mount and upslope edge of shingle course.




CUT SHINGLES AS REQUIRED: DO NOT INSTALL THE FLASHLOC SLIDER ACCROSS THICKNESS VARIATIONS GREATER THAN 1/8" SUCH AS THOSE FOUND IN HIGH DEFINITION SHINGLES.

NOTE: When installing included rail attachment hardware, torque T-bolt nut to 30 ft-lbs. NOTE: If an exploratory hole falls outside of the area covered by the sealant, flash hole accordingly.


USE ONLY UNIRAC APPROVED SEALANTS. PLEASE CONTACT UNIRAC FOR FULL LIST OF COMPATIBLE SEALANTS.




APPENDIX D 38 UNIVERSAL AF ENDCLAMP INSTALLATION GUIDE PAGE




STEP 1: Position clamp to align T-bolt with rail slot. Lower clamp and Insert T-bolt into rail slot.




STEP 2: Rotate clamp clockwise 2/3 of a turn to engage T-bolt inside rail slot.




STEP 3: Place module at least 3/4" from end of rail and position clamp against module frame.



STEP 4: While applying pressure to hold the clamp against the module, push down on the module side of the clamp cap.




STEP 5: When the cap contacts the module frame, release and it will re-engage to the clamp base.



STEP 6: Tighten bolt and torque to 15 ft-lbs.

NOTE - Universal AF End Clamps are single use.




STEP 7: Confirm clamp is engaged in correct module height position and that the top of the cap is sitting level with the module frame.

NOTE: When installing 46mm modules, loosen bolt by 1 turn before positioning clamp against module frame. Do not force clamp onto module frame as this may damage the bonding pin.


DocuSign Envelope ID: 4C077C38-FA98-419B-B651-E66DE9437930




APPENDIX D 39 UNIVERSAL AF MIDCLAMP INSTALLATION GUIDE PAGE




STEP 1: Position clamp to align T-bolt with rail slot. Lower clamp and insert T-bolt into rail slot




STEP 2: Rotate clamp clockwise 2/3 of a turn to engage T-bolt inside rail slot.



STEP3: Slide clamp into position against module.




STEP 4: Place second module.



STEP 5: Tighten bolt and torque to 15 ft-lbs.

NOTE - Universal AF Mid Clamps are single use.



NOTE: If excessive force is applied in step 2, the cap may over-rotate causing it to be mis-aligned with the module frame. If this occurs, keep rotating the cap clockwise until it returns to the original position.