Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7

HISTORIC DISTRICT COMMISSION
APPLICATION FOR WORK APPROVAL

City of Detroit - Planning & Development Department
2 Woodward Avenue, Suite 808
Detroit, Michigan 48226

APPLICATION ID
HDC2026-00383

PROPERTY INFORMATION

ADDRESS(ES): 808-816 Virginia Park

HISTORIC DISTRICT: New Center Area

SCOPE OF WORK: (Check ALL that apply)

- [x] Windows/ Doors
- [x] Walls/ Siding
- [x] Painting
- [ ] Roof/Gutters/ Chimney
- [x] Porch/Deck/Balcony
- [ ] Other
- [ ] Demolition
- [ ] Signage
- [x] New Building
- [ ] Addition
- [x] Site Improvements (landscape, trees, fences, patios, etc.)

BRIEF PROJECT DESCRIPTION:
New Construction of attached residential duplexes. Total of 14 units in two buildings

APPLICANT IDENTIFICATION

TYPE OF APPLICANT: Architect/Engineer/Consultant

NAME: Steven Flum	**COMPANY NAME:** Steven C. Flum, Inc.		
ADDRESS: 3105 Holbrook	**CITY:** HAMTRAMCK	**STATE:** MI	**ZIP:** 48212
PHONE: +1 (313) 831-2844	**EMAIL:** SFLUM@STEVENCFLUM.COM		

I AGREE TO AND AFFIRM THE FOLLOWING:

- [x] I understand that the failure to upload all required documentation may result in extended review times for my project and/or a denied application.
- [x] I understand that the review of this application by the Historic District Commission does not waive my responsibility to comply with any other applicable ordinances including obtaining appropriate permits (building, sign, etc.) or other department approvals prior to beginning the work.
- [x] I hereby certify that the information on this application is true and correct. I certify that the proposed work is authorized by the owner of record and I have been authorized to make this application as the property owner(s) authorized agent.
- [x] As required by the state Local Historic Districts Act, Act 169 of 1970 (MCL399.205), I hereby certify that the property where work will be undertaken has, or will have before the proposed project completion date, a fire alarm system or a smoke alarm complying with the requirements of the Stille-DeRossett-Hale single state construction code act, 1972 PA 230, MCL 125.1501 to 125.1531

DocuSigned by:
Steven Flum
01E13EE84B08483...
SIGNATURE

07/20/2026
DATE

NOTE: Based on the scope of work, additional documentation may be required. See www/detroitmi.gov/hdc **for scope-specific requirements.**

PROJECT DETAILS – TELL US ABOUT YOUR PROJECT

Instructions: Add project details using the text box in each section. If your details exceed the space provided, attach the details via the attachment icon for that section.

ePLANS PERMIT NUMBER:
(only applicable if you've already applied for permits through ePLANS) N/A

GENERAL

1. DESCRIPTION OF EXISTING CONDITION
Please tell us about the current appearance and conditions of the areas you want to change. You may use a few sentences or attach a separate prepared document on the right. (For example, "existing roof on my garage is covered in gray asphalt shingles in poor condition.")

2. PHOTOGRAPHS
Help us understand your project. Please attach photographs of all areas where work is proposed.

3. DESCRIPTION OF PROJECT
In this box, tell us about what you want to do at the areas described above in box #1. (For example, Install new asphalt shingle roofing at garage.)

4. DETAILED SCOPE OF WORK
In this box, please describe all steps necessary to complete the work described in box #3. (For example, "remove existing shingles, replace wood deck as necessary, replace wood eaves, install roof vents, replace rotted fascia boards, paint, clean worksite.")

5. BROCHURES/CUT SHEETS
Please provide information on the products or materials you are proposing to install. For example, a brochure on the brand and color of the shingles proposed.


ADDITIONAL DETAILS

6. WINDOWS/DOORS *Detailed photographs of window(s) and/or door(s) proposed for replacement showing the condition of the interior and exterior of the window(s) and/or door(s)*	
8. SITE IMPROVEMENTS *If site improvements are proposed, please provide any relevant site improvement plans pertaining to your project.*	

Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7

DESCRIPTION OF EXISTING CONDITION

The existing 20,000 square foot vacant lot is located on a street corner with an alley to the rear. There is an existing adjacent three-story brick single family residence to the west and two-story townhouses to the north. The lot is covered with grass and no pavement. Refer to the Civil Survey and Architectural Existing Site Plan for additional photos of the site and demolition notes.



Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7

ENVIRONMENTAL SITE ASSESSMENT

The developer retained the services of Pinchin, Environmental and Engineering Solutions, to conduct environmental phases 1 and 2. The full reports can be forwarded upon request.

Environmental Phase 1

Originally a large single-family home and garage were built approximately 1911. The home was converted for use as a convalescent home in 1957. The home and garage were demolished, and the property was redeveloped with a parking lot for the hospital across the street between 1968 and 1972. The parking lot was removed between 2012 and 2016, and the property has consisted of vacant land since that time. It was recommended that an environmental phase 2 be conducted.

Environmental Phase 2

Excerpts from the report:

"The subject property was historically developed with a residential dwelling, which contained a basement. Additionally, historical records document the former dwelling previously utilized fuel oil for heating, including two (2) 220-gallon fuel oil aboveground storage tanks (ASTs) in at least 1934. It is Pinchin's experience that a common practice in Detroit during the timeframe of demolition was to demolish the building into the basement and leave all building materials present. Building materials associated with the former dwelling may have been pushed into the basement during and/or after demolition and utilized as fill material. Additionally, the ASTs may not have been removed prior to demolition and may have been buried along with other building materials."

8.0 CONCLUSIONS AND RECOMMENDATIONS

On December 22, 2025, Pinchin completed subsurface investigation activities at the subject property that consisted of advancing two (2) soil borings (PSB-1 and PSB-2) to a maximum depth of 16.0 feet bgs and collecting four (4) soil samples (including a QA/QC sample) for laboratory analysis of VOCs, PNAs, PCBs, and Michigan-10 metals to assess the BER identified in Pinchin's June 2023 Phase I

Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7

ESA. **Several PNAs compounds and Michigan-10 metals (including fluoranthene, phenanthrene, lead, mercury, and zinc) were detected in soil samples** PSB-1 (4-6') and PSB-2 (4-6') at concentrations exceeding EGLE's Parts 201/213 Residential and Nonresidential DC, DWP, and/or GSIP cleanup criteria/RBSLs, and/or the applicable EGLE Residential VIAP screening levels. **Based on the results of the current investigation and the presence of target analytes exceeding the most restrictive Part 201 Residential Cleanup Criteria, the subject property is a "facility,"** as defined in Section 20101(1)(r) of Part 201, of P.A. 451 of 1994, as amended. **Due to the status of the subject property as a "facility", Virginia Park Townes LLC, as owner of the property, is required to undertake Due Care obligations pertaining to the subject property. Therefore, the preparation of a Due Care Plan is recommended.**

Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7

L{{¦ !b/9 hC bh¢L/9 ¢h twh/995

. lˇăŠŘ 2y˝űKŝ conclusions 2ŦűKŝ environmental site assessment phase 2 reportΣ űKŝ lot is a hazard to the safety of the public or the occupants. Based on this we recommend the Historic District Commission issuance of notice to proceed

Section taken from the City of Detroit Zoning Ordinance:Sec. 21-2-75. Issuance of notice to proceed.

Pursuant to the Act, an application for inappropriate work adversely affecting the exterior appearance of a resource, which work cannot be granted a certificate of appropriateness, shall be permitted by the Historic District Commission through the issuance of a notice to proceed if any of the following conditions prevail and if the Historic District Commission finds that the work is necessary to substantially improve or correct any of these conditions:

(1) **The resource constitutes a hazard to the safety of the public or the occupants;**

(2) The resource is a deterrent to a major improvement program that will be of substantial benefit to the community. Substantial benefit shall be found only if the applicant proposing the work has obtained all necessary planning and zoning approvals, financing, and environmental clearances, and the improvement program is otherwise feasible;

(3) Retention of the resource would cause undue financial hardship to the owner. Undue financial hardship shall be found only when a governmental action, an act of God, or other events beyond the owner's control created the hardship, and all feasible alternatives to eliminate the financial hardship, which may include offering the resource for sale at its fair market value or moving the resource to an appropriate vacant site within the historic district, have been attempted and exhausted by the owner;

(4) Retention of the resource would not be in the interest of the majority of the community.

Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7

Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7

Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7



LOOKING NORTHEAST ALONG VIRGINIA PARK



LOOKING NORTHWEST FROM VIRGINIA PARK



LOOKING SOUTHWEST ALONG 3RD AVENUE



LOOKING SOUTHEAST AT ALLEY



LOOKING SOUTH AT VIRGINIA PARK

PROPOSED RENOVATION KEY


Site Demolition Notes

1. EXISTING IVY/TREES AND VEGETATION IN PLACE TO REMOVE ALONG ENTIRE SITE WITHIN PROPERTY BOUNDARY.
2. EXISTING CONDITIONS TO REMAIN.
3. REMOVE CONCRETE PAVING, RoW CURBS AND SIDEWALK AT SOUTH BOUNDARY ONLY AND CONCRETE DRIVES/CURB CUTS EXISTING AT ALL LOCATIONS SHOWN.
4. EXISTING CATCH BASIN INTACT, CROCK, TRAP AND UNDERGROUND CONNECTIONS TO REMOVE ENTIRELY. CAP AT SEWER WITHIN ALLEY PRIOR TO DEMOLITION.
5. AREA OF PREVIOUS BUILDING FOUNDATIONS POSSIBLE. ASSESS FOLLOWING SURFACE DEMOLITION.
6. EXISTING CONCRETE RETAINING KNEE WALL TO DEMOLISH ALONG ALLEY, INCLUDING FOOTINGS WITHIN PROPERTY BOUNDARY ONLY. THAT EXISTING ADJACENT WEST TO RETAIN. REMOVE FOLLOWING SITE EXCAVATION, CLEARING.

LEGEND

- COMBINED STORM/ SANITARY SEWER
- OVERHEAD ELECTR.
- WATER
- GAS
- LIGHT POLE
- UTILITY POLE
- CATCH BASIN
- FIRE HYDRANT
- PERSONHOLE
- EXISTING GRADE (112.4)
- NEW GRADE (113.25)

NOTE:
MATCH EXISTING GRADES WHERE NO PROPOSED GRADES ARE SHOWN



Virginia Park Townes LLC

808 and 816 Virginia Park Ave.
Detroit, MI 48202

VIRGINIA PARK CONDOMINIUMS

Proposed Residential development

Existing Conditions site demolition plan

NORTH

0 10' 20' 40'
SCALE: 1"= 20'

STEVEN C. FLUM, INC.
architecture urban planning
3105 Holbrook Street, Hamtramck, MI 48212
VM: 313.831.2844 WEB: stevenflum.com

Existing Conditions Site Demolition Plan

SCALE: 1" = 20'-0" New Center Area Historic District, Detroit MI

issued for: REVISED HDC Design Review
06 May 2025

Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7



Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7

Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7

Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7

Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7

VIRGINIA PARK TOWNES

DESCRIPTION OF PROJECT

Create residential development consisting of three story duplexes that are attached in groups of two duplexes and five duplexes. The two buildings will have a total of 14 units. One building will face Virginia Park Ave. and the other building will face Third Ave. All the off street parking will be in the rear of the building. Attached garages will have 14 parking spaces and 5 parking spaces will be under carports.

The basis of the proposed design was taken from the Rosa Parks-Clairmount Neighborhood Revitalization Framework completed by the City of Detroit. The city's design was for the vacant lot across the street from the proposed development parcel. The city's design used a combination of townhomes facing Virginia Park Ave. and a multiple family structure on the corner and along Third Ave. Design elements that were used are the three story townhouse, raised stoop, taller than wide windows, the expression of brick and the front yard setback.



CONCEPTUAL VIEW OF ROWHOUSES ON VIRGINIA PARK AVE.



CONCEPTIONAL PLAN OF DEVELOPMENT POTENTIAL VIRGINIA PARK AVE.

Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7

Community and City of Detroit Review

The community supports the removal of the environmental hazard and the new construction of residential housing on the vacant parcel.

We met with the community and the city, made presentations, listen to feed back on the development. The following is an outline of steps we have taken to advance the project forward:

1. The original design was for a four story, 30 unit multi-family building.
2. The community and city's response to the proposed design was they were unwilling to offer support based on the building massing and the number of units.
3. New designs for the development were presented reducing the massing and number of units. There will be two smaller multi-family buildings, three story tall and only having 21 units. The project was submitted to the Historic District Commission in February 2025 and it was denied.
4. Continued meeting with the community and community representatives to reduce the number of units and changes the site and exterior design were made. The following are the changes to the site and building design:
    - The number of units has been decreased from 21 to 14 units. This was achieved by changing the stacked three-unit configuration to two-unit (duplex) configuration
    - The front yard setback on the Virginia Park building has been increased to 30', matching the front yard setback of the adjacent home.
    - The buildings footprint has decreased from the revised front yard setback. We also decreased the 3rd street building to match the front yard setback of the existing townhouse across the alley.
    - The lower "garden level" unit will have a garden patio and entry to the unit. The upper unit entry will be from the raised stoop previously shown
    - We have created an additional entrance to the parking area from the alley. We have also changed the two-way vehicular drive to a one-way direction
    - The zoning code review has been updated and we now only need 2 dimensional variances; Floor Area Ratio and the Recreational Space Requirement. Previously there were 5 dimensional variances being requested
    - The buildings have a mansard roof to compliment the adjacent homes pitched roofs.

Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7

- The exterior façade colors were updated
- The casement and awning windows shown before were replaced with a more traditional single hung window

If the Historic District Commission finds that the development does not meet the Elements of Design. The developer request it to be reviewed under the Section 21-2-75 of the City of Detroit Zoning Ordinance, “Issuance of notice to proceed”. The conditions that prevail is (1) the vacant parcel constitutes a hazard to the safety of the public or the neighborhood. See Description Of Existing Condition section for information from Environmental Sited Assessment Reports

Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7

VIRGINIA PARK TOWNES

Review of Elements of Design

1. Height: Six of the adjoining structures on the same face shall be used to determine an average height. The height of the two adjoining houses shall be added into the total twice. Any new building must have a height of the main roof of at least 80 percent of the resulting average; in no case shall a new building be taller than the tallest roof height.
Average height of 6 Virginia Park homes

830 42.66' x2
850 29.37 x2
866 39.37'
874 36.09
888 39.37'
918 32.81'
291.7 subtotal divided by 8 = 36.46' resulting average roof height.

The resulting average minimum roof height 36.46' < 40.16" proposed roof height OK
The maximum roof height is 42.66' > 40.16' proposed roof height OK

2. Proportion of the buildings' front facades: "….. row house buildings are wider than tall; apartment buildings appear taller than wide although some are wider than tall due to projecting and receding wall surface that emphasize the vertical." The proposed building design has bays that create projecting and receding façade. The façade has a vertical expression with the following elements; bays extending into the mansard roof, brick wall and vertical windows.

3. Proportion of openings within the facades: "Areas of voids generally constitute between 15 percent and 35 percent of the front façade, excluding the roof" The proposed design front elevation has 28 percentage, within the range required. The windows are generally taller than wide but are frequently grouped into combinations wider than tall.

4. Rhythm of solids to voids in front facades: The proposed facades arrangement of openings is balanced composition and symmetrical.

5. Rhythm of spacing of building on streets: The building facing Virginia Park Ave. takes up most of the frontage but still leaves side yard setbacks. Including able separation of the existing single residential home to the west. The rhythm of the buildings facing Third Street is adequate to have a vehicular drive between the buildings and spacing with the existing townhouse to the north.

6. Rhythm of entrance and/or porch projections: The front stoop at each entry creates a rhythm in the façade and leads to a consistency of the streetscape.

Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7

7. Relationship of materials: There is a combination of brick and stucco siding on the front and side elevations. The rear is all stucco siding. Stone is used at sills of windows when brick is present. The front entry stoop roof trim and supports painted wood.

8. Relationship of textures: The brick is a smooth brick with concave mortar joints that contrast nicely with the smooth fiber cement stucco board.

9. Relationship of colors: The brick has natural brick colors similar to homes on the block. Natural limestone is used. The projecting bays smooth white stucco panel siding and trim are contrasted with the black window frame and sashes. The front door and railings are black to contrast the white stoop columns and canopies. The rear metal balconies will be black to match the window and door at the balcony.

10. Relationship of architectural details: The contemporary building design has architectural details used in the front entry stoop. Neighboring existing entry stoop details were used in the design. Both gable and flat roof coverings with supporting columns and brackets are used.

11. Relationship of roof shapes: The roof has a flat roof and a mansard roof. The mansard roofs face the street. The front entry stoops do have roofs similar to neighboring homes. Gabled and shed entry roofs are shown.

12. Walls of continuity: The front yard setback on Virginia Park Ave matches the setback of the adjacent home. The front yard setback for the building on Third Ave. matches the townhouses to the north across the alley. We are keeping the existing trees and adding additional trees to maintain the minor wall of continuity.

13. Relationship of significant landscaping features and surface treatments: The development is retaining all the existing street trees and adding additional trees where there are none. There will be additional trees along Virginia Park Ave. sidewalk in the front yard setback. Hedges and shrubs will also be planted in the front yard closer to the building, each creating a linear planting.

14. Relationship of open space to structures: There will be a large open space between the Virginia Park building and street curb that measures 55' x 140'. Currently there is a large open space across the street on Virginia Park Ave. The vacant lot formerly had the Detroit Hope Hospital on it.

15. Scale of facades and façade elements: The buildings have a moderate scale facade with small, scaled elements.

16. Directional expression of front elevations: The Virginia Park Ave. building directional expressed as wider than tall but has a vertical expression with its design elements. The Third Ave. building directional expression is certainly taller than wide.

Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7

17. Rhythm of building setbacks: See item 12.

18. Relationship of lot coverage: The proposed buildings have a lot coverage of 44%, which is similar to neighboring homes / lots.

19. Degree of complexity within the façade: The front facades have simple shapes that are made of 5 different materials. Architectural details are shown at the front stoops.

20. Orientation, vistas, overviews: The buildings are oriented to the south and to the east. The garages and exterior parking spaces are oriented away from the street view. The units take advantage of the dramatic view of the Fisher building, especially the units facing south.

21. Symmetric or asymmetric appearance: The front facades are symmetrical.

22. General environmental character: The character is strengthening by developing this vacant lot with urban, moderate density housing.

Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7



Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7



Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7



Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7

VIRGINIA PARK TOWNES

DETAILED SCOPE OF WORK


Site

- Construction of a new two attached duplexes total 4-units, 6,457 gsf
- Construction of a new five attached duplexes total 10-units, 20,457 gsf
- New vehicular drive and entry off third avenue and the alley
- New car port for 4 cars (14 cars in attached garages)
- New dumpster enclosure and site landscaping


Building

- Wood framed three story structures, two buildings total 14-units
- Membrane roof pitch to rear to gutters and downspouts
- Mansard roof facing the street to complement the existing pitched roofs in the historic district and to screen view of roof top AC units
- Front entry stoop with brick walls and concrete cap, metal guard and handrail
- Front entry stoop will be cover with supporting columns and roof
- Attached 5-two car garages and 2-one car garage
- Partial brick façade with concave mortar joints
- Partial fiber cement stucco panels with wood trim, painted
- Aluminum clad wood windows
- Metal front entry and sectional overhead garage doors.
- Metal suspended balcony with tension rods at rear bedrooms second and third floor


Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7



Grade/First Floor Unit Plan
SCALE: 1/4" = 1'-0"



Second Floor Plan
SCALE: 1/4" = 1'-0"



Third Floor Plan
SCALE: 1/4" = 1'-0"

3RD Avenue

Virginia Park Townes LLC

808 and 816 Virginia Park Avenue
Detroit, MI 48202

VIRGINIA PARK CONDOMINIUMS

Proposed Residential development

Enlarged Proposed 4-Unit Floor Plans 3rd Ave

NORTH

0 2' 4' 8'

SCALE: 1/4" = 1'-0"

STEVEN C. FLUM, INC.
architecture•urban planning
3105 Holbrook Street, Hamtramck, MI 48212
VM: 313.831.2844 WEB: stevenflum.com

issued for: Owner REVISED Design Review
15 July 2o26

Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7

Virginia Park Townes LLC

808 and 816 Virginia Park Ave.
Detroit, MI 48202

PROJECT SCOPE OF WORK:

NEW CONSTRUCTION OF 14-UNIT RESIDENTIAL GROUPED TWO-FAMILY DEVELOPMENT AT 808/816 VIRGINIA PARK WITHIN THE NEW CENTER AREA HISTORIC DISTRICT. VACANT LOTS TO BE COMBINED PROPERTIES, *816 VIRGINIA PARK*- AS PROPOSED DEVELOPMENT. PARKING WILL BE ENCLOSED WITHIN 1 AND 2-CAR SHARED GARAGES ON GRADE LEVEL AND COVERED SURFACE SPACES ON SITE. THE DEVELOPMENT CONSISTS OF (2) INDIVIDUAL BUILDING STRUCTURES UPON ONE SITE. THREE-STORY RESIDENTIAL BUILDINGS ARE WOOD FRAME CONSTRUCTION. EACH FRONT BUILDING ENTRY WILL ACCESS INDIVIDUAL DWELLING UNITS. SITE WORK CONSISTS OF NEW WALKWAYS, CONCRETE DRIVE, TRASH ENCLOSURE AND LANDSCAPING.

LEGAL DESCRIPTION

816 VIRGINIA PARK =
ALL OF LOT 32 AND A PORTION OF LOT 31, 25 FEET EAST OF NORTH VIRGINIA PARK OF "PEERLESS ADDITION NO. 3 SUBDIVISION", ACCORDING TO THE PLAT THEREOF, AS RECORDED IN LIBER 18, PAGE 40 OF PLATS, WAYNE COUNTY RECORDS 4/80. DESCRIBED AS THE WEST LINE OF 3RD AVENUE 75' X 163'.

PARCEL #04001907 **VIRGINIA PARK TOWNES**

808 VIRGINIA PARK =
LOT 33, NORTH VIRGINIA PARK OF "PEERLESS ADDITION NO. 3 SUBDIVISION", ACCORDING TO THE PLAT THEREOF, AS RECORDED IN LIBER 18, PAGE 40 OF PLATS, WAYNE COUNTY RECORDS 4/80. DESCRIBED AS THE WEST LINE OF 3RD AVENUE 50' X 163'.

PARCEL #04001908 ***DETROIT LAND BANK PROPERTY***

SITE DATA

VACANT, NO EXISTING STRUCTURES

PARCEL AREAS:

816 VIRGINIA PARK:	12,225 SF (EXISTING) (0.2806 ACRE)
808 VIRGINIA PARK:	8,150 SF (EXISTING) (0.1871 ACRE)
	20,375 SF *SUBTOTAL*

COMBINED PARCELS CONTAINING 0.4677 ACRES OF LAND.

ZONING CODE REVIEW

ZONING:	R3-H' LOW DENSITY RESIDENTIAL- HISTORIC NEW CENTER AREA HISTORIC DISTRICT
BUILDING TYPE:	RESIDENTIAL TWO-FAMILY DUPLEX, *BY RIGHT*
816 VIRGINIA PARK COMBINED	125' x 163'
LOT SIZE:	20,375 SF (0.4677 ACRE)
LOT AREA MINIMUM:	7,000 SF MAX < 20,375 SF OK
WIDTH MINIMUM:	70' <125' OK

SETBACKS:

BUILDING 1 VIRGINIA PARK

FRONT MINIMUM	20' MIN. > 30' PROPOSED, ***EXCEEDS***
REAR MINIMUM	30' MIN. < 87' PROPOSED, OK
SIDE YARD FORMULA A:	(BUILDING DEPTH + 2 x HEIGHT)/15 =65' + 80'/15 = 9.67' MIN.< 10' *PROPOSED, OK*
HEIGHT MAXIMUM:	RESULTING MINIMUM HEIGHT OF 36.46', *TOP OF ROOF RIDGE = 40'-2" OK*

BUILDING 2 3RD AVENUE

FRONT MINIMUM	10' MIN. = 10' PROPOSED, (SEC. 50-13-210***) OK***
REAR MINIMUM	30' MIN. < 50' PROPOSED, ***OK***
SIDE YARD FORMULA A:	(BUILDING DEPTH + 2 x HEIGHT)/15 = 65' + 80'/15 = 9.67' MIN.< 50' *PROPOSED, OK*
HEIGHT MAXIMUM:	RESULTING MINIMUM HEIGHT OF 36.46', *TOP OF ROOF RIDGE = 40'-2" OK*

RECREATIONAL SPACE REQUIRED (RSR):	0.12 x 25,301 GSF = 3,036 SF MIN.
UNIT PRIVATE BALCONIES (14) x 71 SF :	***994 TOTAL SF***
UNIT PATIOS (7) VARIOUS SIZES:	***718 TOTAL SF***
RESIDENCE RECREATION SPACE:	3,036 SF MINIMUM > 1,718 TOTAL SF (BALCONIES AND PATIOS), ***DEFICIENT 1,318 SF*** ***BZA VARIANCE REQUESTED***


BUILDING DATA:

SUM OF 2 BUILDINGS		VIRGINIA PARK	3RD AVE
8,981 GSF	2ND FLOOR	6,825 GSF	2,156 GSF
8,981 GSF	3RD FLOOR	6,825 GSF	2,156 GSF
6,191 GSF	GRADE FLOOR	4,725 GSF	1,466 GSF
2,779 GSF	ATTACHED GARAGES	2,100 GSF	679 GSF
TOTAL 26,932 GSF	BUILDING GROSS SF	20,475 GSF	6,457 GSF
25,301 NSF	RESIDENTIAL NET SF		

LOT COVERAGE PROPOSED:	6,191 GSF/20,375 GSF = 0.30 (30%)
FLOOR AREA RATIO (FAR):	0.70 x 20,375 SF (LOT AREA) = 14,262 SF MAX < ***25,725 SF*** ***DEFICIENT 11,463 SF - BZA VARIANCE REQUESTED***
OFF STREET PARKING:	14 UNITS x 0.75 SPACES/DWELLING UNIT= 10.50 11 SPACES MINIMUM< 16 SPACES PROVIDED
816 VIRGINIA PARK REQUIRED (R-2)=	**NOTE: BUS RAPID TRANSIT ON WOODWARD AVENUE 0.34 MILES DISTANCE.* *SPECIAL DISTRICT ALLOWS A PARKING REDUCTION FOR THIS AREA; MINIMUM PARKING 0.75 PER DWELLING UNIT. THEREFORE-*
TOTAL PARKING REQUIRED:	11 SPACES MINIMUM
ACCESSIBLE PARKING:	0 PROVIDED (PER SECTION R320.1.1 ***EXCEPTION***)
TOTAL PARKING PROVIDED:	12 GARAGE SPACES + 4 SURFACE CARPORT SPACES = 16 SPACES
LOADING AREA:	0 REQUIRED PER FOR PARKING LESS THAN 25 SPACES

BUILDING CODE REVIEW

APPLICABLE CODES:	2015 MICHIGAN RESIDENTIAL CODE 2015 NFPA1 FIRE PREVENTION AND PROTECTION CODE 2019 DETROIT CITY CODE PART IV, CHAPTER 8 2015 MICHIGAN ENERGY CODE
PROPOSED USE GROUP:	RESIDENTIAL
PROPOSED OCCUPANCY:	RESIDENTIAL TWO-FAMILY




Location Map
NO SCALE

LEGEND

- COMBINED STORM/ SANITARY SEWER
- OVERHEAD ELECTR.
- WATER
- GAS
- LIGHT POLE
- UTILITY POLE
- CATCH BASIN
- FIRE HYDRANT
- PERSONHOLE
- EXISTING GRADE 112.4
- NEW GRADE 111.25

NOTE:
MATCH EXISTING GRADES WHERE NO PROPOSED GRADES ARE SHOWN



VIRGINIA PARK CONDOMINIUMS

Proposed Residential development

Proposed overall site plan


NORTH

0 10' 20' 40'
SCALE: 1"= 20'

STEVEN C. FLUM, INC.
architecture•urban planning
3105 Holbrook Street, Hamtramck, MI 48212
VM: 313.831.2844 WEB: stevenflum.com

issued for: Owner REVISED Review
15 July 2o26

Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7



LEGEND

- EX. SPOT ELEVATION
- EX. STORM SEWER MANHOLE
- EX. SANITARY SEWER MANHOLE
- EX. CATCH BASIN
- EX. LIGHT POLE
- EX. UTILITY POLE
- EX. ELEVATION CONTOUR
- EX. STORM SEWER
- EX. SANITARY SEWER
- EX. WATER MAIN
- EX. GAS MAIN
- EX. UNDERGROUND ELECTRIC/PHONE/CATV
- PROP. STORM SEWER
- PROP. SANITARY SEWER SERVICE LEAD
- PROP. WATER SERVICE LEAD
- PROP. CATCH BASIN
- PROP. CONCRETE PAVEMENT
- PROP. ASPHALT PAVEMENT
- PROP. SPOT ELEVATION
- PROP. ELEVATION CONTOUR
- PROP. SILT FENCE
- TEMP. INLET PROTECTION FILTER



LOCATION MAP
(NO SCALE)

LEGAL DESCRIPTION *(PER CITY RECORDS)*

LAND IN THE CITY OF DETROIT, WAYNE COUNTY, MICHIGAN, DESCRIBED AS:
ALL OF LOTS 31 AND 32 AND THE EASTERLY 25 FEET OF LOT 33, "PEERLESS ADDITION No. 3" AS RECORDED IN LIBER 18 OF PLATS, PAGE 40, WAYNE COUNTY RECORDS

WE HEREBY CERTIFY THAT WE HAVE SURVEYED THE HEREON DESCRIBED SITE AND THAT ALL MEASUREMENTS AS SHOWN ON THE PLAN ARE CORRECT, AND THAT THERE ARE NO ENCROACHMENTS, UNLESS OTHERWISE SHOWN.

STATE OF MICHIGAN
NEAL TONNEMACHER
PROFESSIONAL SURVEYOR
No. 4001049332
LICENSED PROFESSIONAL ENGINEER

811
Know what's **below.**
Call before you dig.

MASON BROWNS ASSOCIATES, LLC
CIVIL ENGINEERS & SURVEYORS
2708 BRIDLE ROAD
BLOOMFIELD HILLS, MICHIGAN 48304
(248) 425-9789 mason_brown@sbcglobal.net

PROPOSED DEVELOPMENT
PLAN OF EXISTING CONDITIONS

STEVEN C. FLUM, INC.
3105 Holbrook Avenue Hamtramck, Michigan 48212

REVISIONS:


DESIGN: ---
DRAWN: mb
CHECKED: MB
24-033.DWG
FIELD CK: net

SCALE: 1"=20'
DATE: 07-26-2024
JOB NO. 24-033
SHEET 1

Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7


Virginia Park Townes LLC
808 and 816 Virginia Park Avenue
Detroit, MI 48202

VIRGINIA PARK CONDOMINIUMS
Proposed Residential development
Enlarged Proposed 10-Unit Floor Plans Virg Park




Grade/First Floor Unit Plan
SCALE: 1/4" = 1'-0"

Grade/First Floor Typical Unit Plan
SCALE: 1/4" = 1'-0"



Second Floor Plan
SCALE: 1/4" = 1'-0"



Third Floor Plan
SCALE: 1/4" = 1'-0"

Virginia Park Avenue



SCALE: 1/4" = 1'-0"


STEVEN C. FLUM, INC.
architecture•urban planning
3105 Holbrook Street, Hamtramck, MI 48212
VM: 313.831.2844 WEB: stevenflum.com

issued for: Owner REVISED Design Review
17 July 2026

Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7


Virginia Park Townes LLC

808 and 816 Virginia Park Avenue
Detroit, MI 48202



Side - East Elevation

SCALE: 1/8" = 1'-0" — 3RD AVENUE



Front - South Elevation - Building 1

SCALE: 1/8" = 1'-0" — VIRGINIA PARK AVENUE 10-UNIT BUILDING

VIRGINIA PARK CONDOMINIUMS

Proposed Residential development

Proposed Exterior Elevations

0 4' 8' 16'

SCALE: 1/8" = 1'-0"


STEVEN C. FLUM, INC.
architecture•urban planning
3105 Holbrook Street, Hamtramck, MI 48212
VM: 313.831.2844 WEB: stevenflum.com

issued for: Owner REVISED Design Review
17 July 2026

Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7

Virginia Park Townes LLC

808 and 816 Virginia Park Avenue
Detroit, MI 48202



Side Building 1 - West Elevation

SCALE: 1/8" = 1'-0" 10-UNIT BUILDING



Rear Building 1- North Elevation

SCALE: 1/8" = 1'-0" 10-UNIT BUILDING

VIRGINIA PARK CONDOMINIUMS

Proposed Residential development

Proposed Exterior Elevations

0 4' 8' 16'

SCALE: 1/8" = 1'-0"

STEVEN C. FLUM, INC.
architecture•urban planning
3105 Holbrook Street, Hamtramck, MI 48212
VM: 313.831.2844 WEB: stevenflum.com

issued for: Owner REVISED Design Review
15 July 2o26

Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7


Virginia Park Townes LLC

808 and 816 Virginia Park Avenue
Detroit, MI 48202

VIRGINIA PARK CONDOMINIUMS


Proposed Residential development

Conceptual Building and Site Section, Elevations




Side Building 2 - South Elevation Vehicle Drive

SCALE: 1/8" = 1'-0" 4 -UNIT BUILDING



Side Building 2 - North Alley Elevation

SCALE: 1/8" = 1'-0" 3RD AVENUE 4 -UNIT BUILDING



Building Section N/S - Looking West

SCALE: 1/8" = 1'-0" BUILDING #1, VIRGINIA PARK

0 4' 8' 16'

SCALE: 1/8" = 1'-0"

STEVEN C. FLUM, INC.
architecture•urban planning
3105 Holbrook Street, Hamtramck, MI 48212
VM: 313.831.2844 WEB: stevenflum.com

issued for: Owner REVISED Design Review
15 July 2026

Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7

Exterior Building Materials and Colors

Color palette of exterior materials and colors

1. Brick with concave gray mortar joints
2. Fiber cement cc panels a , white
3. al l
4. Front entry metal guard and handrail, black
5. Aluminum gutters and downspouts, black
6. Windows: Pella Lifestyle Series wood /aluminum clad color: Black
7. Front entry doors: hollow metal with windows, black
8. Aluminum sectional garage door with windows: 16’ wide x 8’ high
9. Rear bedroom metal suspended balcony with tension rods

Exterior Site Materials

A. Front entry light, wall mounted
B. Front entry lighted address plate
C. Area light above garages and on façade along the alley
D. Metal car port

Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7

Bay Stucco Panel Color

SW 7757
High Reflective White
Interior
Location Number: 256-C1



Badlands Smooth

Trim Colors

SW 6168
Moderne White
Interior / Exterior
Location Number: 258-C6



Black Pella Windows
Color to match

- **Exterior doors**
- **Metal railings and guards**
- **Gutters + downspouts**

Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7

Glen-Gery



Badlands Smooth

Contains Recycled Content

Save Product Compare Brick

Where To Buy Contact Us

See this on your house

Download seamless tileable image

Product Information:

Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7

Type: Facebrick

Color: Tan

Style: Extruded

Plant: Sergeant Bluff

Series: Cosmopolitan Series

Texture/Finish: Smooth

Sizes | **Technical Information**

General Availability	T	H	L		Brick per sq ft
Modular	3-5/8	2-1/4	7-5/8	in.	6.86
Utility	3-5/8	3-5/8	11-5/8	in.	3.00
Norman	3-5/8	2-1/4	11-5/8	in.	4.57

You May Also Like

Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7

insite.™
Building design. Streamlined.

FEBRUARY 2024

JamesHardie™

Hardie® Panel vertical siding Submittal Form 02

Submitted to: Steven Flum

Project Name: Virginia Park Townes

Submitted by:

Date:

☑ **HZ5® Product Zone** ☐ **HZ10® Product Zone**

Product Width: ☐ **4x8ft** ☐ **4x9ft** ☑ **4x10ft** ☐ **16inx12ft**

Product Finish: ☑ **Primed** ☐ **ColorPlus® Technology**

Product Texture: ☑ **Smooth** ☐ **Select Cedarmill®** ☐ **Sierra 8** ☐ **Stucco**

Hardie® Panel vertical siding Specification Sheet 02

DIVISION: 07 00 00 THERMAL AND MOISTURE PROTECTION | SECTION: 07 46 46 FIBER CEMENT SIDING

HARDIE® PANEL VERTICAL SIDING

Manufacturer

James Hardie Building Products Inc.

The products are manufactured at the following locations, with quality control inspections by ICC-ES:

- Cleburne, Texas
- Plant City, Florida
- Reno, Nevada
- Waxahachie, Texas
- Prattville, Alabama
- Peru, Illinois
- Pulaski, Virginia
- Tacoma, Washington
- Fontana, California
- Summerville, South Carolina

Compliance with the following codes

- 2006 thru 2021 International Building Code (IBC)
- 2006 thru 2021 International Residential Code (IRC)

For more information about other compliances and applicable uses, refer to the ESR-1844

Features

- Noncombustible
- Dimensionally Stable
- Resistant to damage caused by pests
- Weather Resistant-Engineered for Climate®
- Impact resistant
- Sustainable

Use

James Hardie fiber-cement panels are used as exterior wall covering. The product complies with IBC Section 1403.9 and IRC Section R703.10. The product may be used on exterior walls of buildings of Type I, II, III and IV construction (IBC).

Description

Hardie® Panel vertical siding is a single-faced, cellulose fiber-reinforced cement (fiber-cement) product. Hardie® Panel vertical siding complies with ASTM C1186, as Grade II, Type A; has a flame-spread index of 0 and a smoke-developed index of 5 when tested in accordance with ASTM E84; and is classified as noncombustible when tested in accordance with ASTM E136.

Available Sizes

Product	Width (inches)	Length (feet)	Thickness (inches)
Hardie® Panel vertical siding	48	8, 9*, 10	5/16

** Size not available in ColorPlus® Technology, primed only.*


Weight: 2.40 lbs. per square foot

Texture & Finish

Hardie® Panel vertical siding comes in a variety of textures and finishes. The product is available in smooth, wood grain, Sierra 8, or stucco. Finish options are primed for field paint, or factory finished with ColorPlus® Technology. Color availability varies by region.

Engineered for Climate®

Hardie® Panel vertical siding is engineered for performance to specific weather conditions by climate zones as identified by the following map.



Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7





Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7

Nature's Aesthetic. Our Expertise. 3.

WOODCREST® & WOODMOOR®

These shingle collections offer a timeless design inspired by nature for truly engineered elegance.

Seamlessly blending rustic style with technical excellence, these shingles are thoughtfully crafted to capture the charm of wood shake while guarding against the elements. Providing everything you expect from an Owens Corning® roof—and more.

NATURALLY STRIKING
UNSHAKABLY STRONG

Limited Lifetime Warranty*/‡ (for as long as you own your home)

130-MPH Wind Resistance Limited Warranty*


StreakGuard® Protection with a 25-year Algae Resistance Limited Warranty3/§

Class 4 impact resistant4 – UL 2218



The textured cut of Woodcrest® exudes a rugged, handcrafted feel that brings warmth and character to any roofline. For those looking to make an even bolder statement, the thicker profile of Woodmoor® shingles adds striking dimension and a more dramatic shadow line. Enhanced with added granules and layered detailing, Woodmoor® shingles offer rich contrast and a refined finish for that added curb appeal.





4 Woodcrest® and Woodmoor® are tested in a laboratory setting and classified as a UL 2218 Class 4 Impact-Resistant shingle. The results of this test do not guarantee that the shingle will resist all weather conditions. Hail damage is specifically excluded from coverage under the terms of its warranty.

Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7



WOODCREST® CARBON

Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7

TOTAL PROTECTION ROOFING SYSTEM^

TOTAL PROTECTION SIMPLIFIED®

It takes more than just shingles to protect a home. It takes an integrated system of components and layers designed to perform in three critical areas. The Owens Corning® Total Protection Roofing System®^ gives you the assurance that all of your Owens Corning roofing components are working together to help increase the performance of your roof.


PROTECCIÓN TOTAL SIMPLIFICADA®

Se necesita más que simplemente tejas para proteger su vivienda. Se necesita un sistema integral de componentes y capas diseñadas para desempeñarse en tres áreas críticas. El Total Protection Roofing System® de Owens Corning® le garantiza que todos sus componentes para cubiertas de Owens Corning funcionan en conjunto para mejorar el desempeño de su techo.

SEAL. SELLAR.
Helps create a waterproof barrier
Ayuda a crear una barrera impermeable

DEFEND. DEFENDER.
Helps protect against nature's elements
Protege contra los elementos climáticos

BREATHE. RESPIRAR.
For balanced attic ventilation
Para una ventilación equilibrada del ático



§§ For intake ventilation, use approved Owens Corning® Vent Sure® InFlow ventilation or soffit ventilation. Do not use both intake ventilation options in one roofing application. See install instructions for more details.
§§ Para la ventilación de entrada, utilice la ventilación aprobada por Owens Corning® Vent Sure® InFlow o ventilación de sofito. No utilice ambas opciones de ventilación de entrada en una misma aplicación para techos. Consulte las instrucciones de instalación para obtener más detalles.

OWENS CORNING® COOL ROOF COLLECTION | COOL ROOF COLLECTION

In our premium offering of Woodcrest® and Woodmoor® Shingles, there are Cool Roof Collection colors that are specially designed to reflect the sun's rays, helping to make your home more comfortable and energy efficient.

- Meet the prescriptive Cool Roof requirements of California Title 24, Part 6
- Are Cool Roof Rating Council (CRRC) rated
- Meet Property Assessed Clean Energy (PACE) financing program requirements
- May help lower household energy consumption by keeping the roof cooler; also may help decrease CO_2 emissions

En la línea premium de tejas Woodcrest®, hay colores de COOL Roof Collection que están especialmente diseñados para reflejar los rayos del sol, ayudando a que su hogar sea más acogedor y con un consumo de energía más eficiente.

- Cumple con los requisitos prescriptivos de Cool Roof del Título 24, Parte 6 de California
- ¿Están clasificados por el Cool Roof Rating Council (CRRC)?
- Cumple con los requisitos del programa de financiamiento de energía limpia evaluada por la propiedad (Propiedad Assessed Clean Energy, PACE)
- Puede ayudar a reducir el consumo de energía del hogar al mantener el techo más fresco; también puede ayudar a disminuir las emisiones de CO_2

COOL ROOF COLLECTION | COOL ROOF COLLECTION

	Color Colores	CRRC Product ID ID de producto CRRC	Warranty Length Duración de la garantía	Solar Reflectance Reflectancia solar	Thermal Emittance Emisión térmica	Solar Reflectance Index (SRI) Índice de reflectancia solar (SRI)
Woodcrest® & Woodmoor®	Mountainside	0890-0027	Limited Lifetime*‡ (for as long as you own your home) Limitada de por vida*‡ (durante el tiempo que sea propietario de su vivienda)	0.19	0.91	18
	Night Sky	0890-0028	Limited Lifetime*‡ (for as long as you own your home) Limitada de por vida*‡ (durante el tiempo que sea propietario de su vivienda)	0.19	0.91	18
	Sand Castle	0890-0029	Limited Lifetime*‡ (for as long as you own your home) Limitada de por vida*‡ (durante el tiempo que sea propietario de su vivienda)	0.19	0.91	18

Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7


Product Attributes

Warranty Length*/‡
Limited Lifetime
(for as long as you own your home)

Wind Resistance Limited Warranty*
130-MPH

Algae Resistance Limited Warranty*/§
25 Years

TRU PROtection® Non-Prorated Limited Warranty* Period
10 Years



Cool Roof Collection colors available in areas shown in gray.


Atributos del producto

Duración de la garantía*/‡
Limitada de por vida (durante el tiempo que seas propietario de tu vivienda)

Garantía limitada de resistencia a vientos*
130 mph (177/209 km/h)

Garantía limitada de resistencia a las algas*/§
25 años

Periodo de garantía limitada* no prorrateada TRU PROtection®*
10 años



Los colores de la Cool Roof Collection están disponibles en las áreas que se muestran en gris.

Woodcrest® and Woodmoor® Collection Shingles Product Specifications

	Woodcrest®	Woodmoor®
Size	14¼" x 40"	14¼" x 40"
Weight	350 lbs.	465 lbs.
Application Exposure	4"	4"
Shingles per Bundle	15	15
Shingle Count per 6 Bundles	90	90
Coverage per 6 Bundles	100 sq. ft.	100 sq. ft.

Especificaciones del producto de tejas de la colección Woodcrest® y Woodmoor®

	Woodcrest®	Woodmoor®
Tamaño	14¼" x 40"	14¼" x 40"
Peso de	350 lbs.	465 lbs.
Exposición de la aplicación	4"	4"
Tejas por paquete	15	15
Recuento de tejas por paquete 6 tejas	90	90
Cobertura promedio por 6 paquetes	100 pies cuadrados	100 pies cuadrados

WoodStart® Starter Strip Shingle Product Specifications

Nominal Size	40" x 13 ½"
Pieces per Bundle	16
Lineal Feet per Bundle	53.33

Especificaciones del producto tira de tejas de arranque WoodStart®

Tamaño nominal	40" x 13½"
Piezas por paquete	16
Pies lineales por paquete	53.33

Applicable Standards and Codes

ASTM D3462
CSA A123.5++
ASTM D228
ASTM D3018 (Type 1)
ICC-ES AC438#
ASTM D3161 (Class F Wind Resistance)
ASTM D7158 (Class H Wind Resistance)
ASTM E108/UL 790 (Class A Fire Resistance)
UL 2218 (Class 4 Impact Resistance)4
PRI ER 1378E01

Normas y códigos aplicables

ASTM D3462
CSA A123.5++
ASTM D228
ASTM D3018 (tipo 1)
ICC-ES AC438#
ASTM D3161 (resistencia al viento clase F)
ASTM D7158 (resistencia al viento clase H)
ASTM E108/UL 790 (resistencia al fuego clase A)
UL 2218 (Resistencia a impactos de clase 4)4
PRI ER 1378E01

* See actual warranty for complete details, limitations and requirements.
‡ 40-year Limited Warranty on commercial projects.
++ Only on product sold in Canada.
International Code Council Evaluation Services Acceptance Criteria for Alternative Asphalt Shingles.
^ Excludes non-Owens Corning® roofing products such as flashing, fasteners, pipe boots and wood decking.
1 See Color Disclaimer Information on page 26 for additional details.
3 Shingles are algae resistant to help control growth of algae and discoloration.
4 Woodcrest®, Woodmoor®, and WoodStart® are tested in a laboratory setting and classified as a UL 2218 Class 4 Impact-Resistant shingle. The results of this test do not guarantee that the shingle will resist all weather conditions. Hail damage is specifically excluded from coverage under the terms of its warranty.
§ Installation must include use of an approved Owens Corning® Hip & Ridge Shingle product. See actual warranty for details.

* Consulta la garantía para conocer todos los detalles, limitaciones y requisitos.
‡ Garantía limitada de 40 años para proyectos comerciales.
++ Solo para productos vendidos en Canadá.
Criterios de aceptación de los servicios de evaluación del Consejo de Código Internacional para tejas de asfalto alternativo.
^ No incluye productos de tejados que no sean de Owens Corning®, como tapajuntas, sujetadores, fundas de tuberías y terrazas de madera.
1 Consulte la sección Información de exención de responsabilidad de color en la página 26 para obtener más detalles.
3 Las tejas son resistentes a las algas para ayudar a controlar el crecimiento de las algas y la decoloración.
4 Woodcrest® Woodmoor®, y WoodStart® se prueba en un entorno de laboratorio y está clasificada como una teja resistente a impactos UL 2218 Clase 4. Los resultados de esta prueba no garantizan que la teja resista a todas las condiciones climáticas. Los daños por granizo quedan expresamente excluidos de la cobertura conforme a los términos de su garantía.
§ La instalación debe incluir el uso de un producto de tejas aprobado Owens Corning® Hip & Ridge. Consulta la garantía real para obtener más detalles.

OWENS CORNING ROOFING AND ASPHALT, LLC
ONE OWENS CORNING PARKWAY
TOLEDO, OH 43659 USA
1-800-GET-PINK®
www.owenscorning.com/roofing


Pub. No. 10028020-A. Printed in U.S.A. February 2026
THE PINK PANTHER™ & © 1964–2026 Metro-Goldwyn-Mayer Studios Inc. All Rights Reserved.
The color PINK is a registered trademark of Owens Corning.
© 2026 Owens Corning. All Rights Reserved.

(Compton, Denver, Portland)

Pub. N.º 10028020-A, impreso en EE. UU. Febrero de 2026.
THE PINK PANTHER™ & © 1964–2026 Metro-Goldwyn-Mayer Studios Inc.
Todos los derechos reservados. El color PINK es una marca comercial registrada de Owens Corning.
© 2026 Owens Corning. Todos los derechos reservados.

Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7

4. FRONT METAL GUARD AND HANDRAIL





Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7

8″ Aluminum Box Gutter







$6.50

Minimum order 20′. Our 8″ x .040″ Aluminum Box Gutter can be shipped in lengths of 6, 10, 15 and 19 feet. Gutter can also be shipped at 20 & 26 foot lengths, but is considered and rated as excessive length by freight companies. (6′ maximum lengths shipped via UPS)

Available in low gloss white, almond, dark bronze, and royal brown (see Aluminum Color Chart below).

*Price shown is **per foot**, please enter the **total number of feet needed** in the Quantity box. IMPORTANT: When you're checking out, you'll have the opportunity to specify the quantity of each length of gutter you need. You'll enter this info in the "Order Notes" box at checkout.*

Gutter orders LONGER than 6′ will be shipped via truck and subject to a MINIMUM shipping fee of $150.00

One to five pieces of gutter can be sent UPS in 6′ sections. UPS charges will run in the $100 range. Please indicate in the "Order Notes" area at checkout whether you want a UPS or freight quote.

Each gutter and downspout order is unique at Classic Gutter Systems. Once you've placed your order on this website, you'll be contacted within 48 hours with a complete, detailed quote including packaging and shipping costs.

Color

Choose an option

- 1 + Add to cart

Categories: 8" Box Gutter & Accessories, Bulky SKU: N/A

Tag: Gutter Systems

Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7

4″ x .024 Aluminum Corrugated Round Downspout, Select Colors







We recommend corrugated downspout for areas of the country that experience snow and ice. Corrugation allows for expansion in the event of ice build-up in the downspout, and also helps hide nicks and dents from daily exposure.

Note: Select Color corrugated aluminum downspout, shown here in Grecian Green, is priced the same per 10-foot length as our Standard Colors (see Aluminum Color Chart below).

Due to the machine setup required to produce Select Color Corrugated Downspout and Elbows, there is a $100.00 up charge (one up charge per color, per order).

Downspout sections are available in 10′ pre-cut lengths. Each box holds 60 ft. of 4″ downspout. Don't forget to order additional downspout for elbow offsets and future repairs.

You will need to reduce the size of the opening on the elbows and downspout.

Downspout orders LONGER than 6′ will be shipped via truck and subject to a MINIMUM shipping fee of $150.00

One to three pieces of downspout can be sent UPS. The 10′ downspout will be cut into 6′ & 4′ sections. UPS charges will run in the $100 range. Please indicate in the "Order Notes" area at checkout whether you want a UPS or freight quote.

To order Corrugated Select Color Downspout, please call us at 269.665.2700.

Categories: 4" Round Downspout, Round Downspout SKU: DS4SC

Tag: Downspout Systems

Description Additional information

Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7



Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7

Pella® Lifestyle Series

Clad/Wood

7.

#1 performing wood window and patio door for the combination of energy, sound and value.[1]

Triple-pane casement




Dual-pane casement



- **Performance redefined**
  You don't have to compromise on any aspect of performance. Available performance solutions offer an unbeatable combination of energy efficiency, sound control and value.[1]
- **ENERGY STAR® certified[2]**
  Pella products offer energy-efficient options that will meet or exceed ENERGY STAR guidelines in all 50 states. Pella Lifestyle Series products with triple-pane glass have been awarded ENERGY STAR Most Efficient Mark in 2023.
- **Enhanced sound control**
  Our patented, triple-pane design with Advanced Low-E glass allows for mixed glass thickness for enhanced sound dampening resulting in an average 52% noise reduction versus single-pane windows.[3]
- **Popular features and options**
  Low-maintenance aluminum-clad exteriors. Factory prefinish with a choice of several paints and stains, or choose primed or unfinished. Several grille types and patterns and high-transparency screens are also available.
- **Intentional design for improved durability**
  Intentional jamb/sill design helps seal the end grain of the wood and elevates it off the rough opening, reducing the potential for moisture.
- **Durable 3-way corner joint**
  Three-way corner joints are made up of mortise-and-tenon, metal fasteners and commercial adhesive for added strength and durability.
- **Low-maintenance exteriors**
  Aluminum-clad exteriors with EnduraClad® finish resists fading and chalking. It is applied in an overlapping fashion for exceptional protection.
- **Exclusive wood protection**
  Pella's exclusive EnduraGuard® wood protection is applied after the pieces have been cut and milled, but prior to final assembly. It provides advanced protection against the effects of moisture, decay, stains from mold and mildew — as well as termite damage.
- **Best limited lifetime warranty[4]**
  Pella Lifestyle Series products are covered by the best limited lifetime warranty in the industry for wood windows and patio doors.[4]
- **Testing beyond requirements**
  At Pella, our products are tested beyond requirements to help ensure they have long-lasting performance and reduce call-backs for you.

Available in these window and patio door styles:[5]



Special shape windows also available.

[1,2,3,4,5] See back cover for disclosures.

Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7

Extruded Aluminum-Clad Exteriors

- Extruded aluminum-clad exteriors provide exceptional durability.
- Extruded aluminum-clad wood products are available with Pella's high performance EnduraClad® protective finishes to help keep your vision fresh and crisp for years.
- Durable, low-maintenance EnduraClad aluminum cladding with EnduraClad protective finish for most projects where resistance to fading, chalking, chemicals and abrasion is needed. Meets the performance requirements of AAMA 2603.
- Seacoast EnduraClad protective finish for coastal projects with high salt exposure

Exterior Finishes

Your windows and patio doors arrive with Pella's low-maintenance, aluminum-clad exterior finish in the color of your choice. The finish resists fading and helps protect the exterior for years.



Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7

Date	1/21/2025

Style Option = TS81RCL-FF

Steel Single



Impact Rating : None
Call Width : 3'0"
Call Height : 8'0"
Door Collection : Traditions Steel
Line : Pulse
Glass Shape : Pulse Linea
Style Shape : Pulse 8' Linea Offset Right
Glass Type : Clear Glass
Glass Design : Clear
Grille Pattern : None
Grille Style : None
Low-E? : No
Caming : None
Frame Profile : Flat Profile
Door Prefinish : Paint 1 Color
Door Paint Color : Granite
Jamb Prefinish : Paint 1 Color
Jamb Paint Color : Granite
Hardware : No Hardware
Would you like to include a storm door? : No

Copyright © 2023 Therma Tru Corp. All Rights Reserved.
www.thermatru.com

Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7

Home / Details

Insulated Steel Garage Doors

THERMACORE® COLLECTION - MODELS 5720, 5740 & 5760



VIEW FULL GALLERY

Thermacore® Collection insulated steel doors are the ideal choice for premium construction and maximum thermal efficiency. This series of doors feature construction of steel-polyurethane-steel as well as between-section seals with thermal breaks to reduce air infiltration. With several panel designs to choose [illegible]hese doors offer design flexibility, durability and thermal efficiency that will help keep your home [illegible]rtable in cold or hot climates.

Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7

Thermacore® Collection premium insulated garage doors deliver maximum thermal efficiency and design flexibility.

Learn more about our new Artisan Wood Grain™ finish options!

DOORDREAMER™: VIEW THIS DOOR ON YOUR HOME

REQUEST A QUOTE

FIND A DISTRIBUTOR

Overview | Garage Door Designs | Colors | Windows & Hardware | Documents

Construction

Product Specifications

5 Panel Options Available	Standard, Flush, Long, Microgroove, Vertical Short and Vertical Lo
Thermacore® Construction	Provides a continuous layer of foamed-in-place, CFC-free polyuret door insulation sandwiched between two layers of corrosion-resis maximum thermal efficiency
Polyurethane Garage Door Insulation	Provides thermal efficiency U-factor* of .20 (9.31 R-value**): Model 5720 U-factor* of .15 (12.76 R-value**): Model 5740 U-factor* of .10 (17.5 R-value**): Model 5760
Multiple Surface Options	Embossed wood grain, microgroove wave pattern and smooth
Steel Backing	For clean, finished interior appearance
Durable Finish	Hot-dipped galvanized steel with two coats of baked-on polyester

Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7

Product Specifications

In-between Section Seals	Seals provide superior resistance to the elements
Bulb-type Bottom Weatherseal	Guards against wind and rain while providing a cushion when closi
Wind Load	Our WindStorm™ wind load rated system is available on selected p regulations for a variety of wind speeds, ensuring your door is built varying wind conditions, including hurricane-force winds, and mee stringent local building codes.

**U-factor values are independently tested and verified per ANSI/DASMA 105.*

***Overhead Door™ Brand uses a calculated door section R-value for our insulated doors.*

Overhead Door™ Brand participates in the DASMA Thermal Performance Verification Program. The program verifies the thermal performance of sectional doors. The lower the U-factor rating, the better the thermal performance.

Symbol indicates verified U-factor rating in accordance with the DASMA Thermal Performance Verification Program.

Warranty

- 20-year limited warranty on Models 5720
- Limited lifetime warranty on door Models 5740 and Model 5760

Residential garage door and opener system limited warranty

- (when purchased together) - features 3 year on components (see warranty for details)

Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7

Thermacore® Collection premium insulated garage doors deliver maximum thermal efficiency and design flexibility.

Learn more about our new Artisan Wood Grain™ finish options!

DOORDREAMER™: VIEW THIS DOOR ON YOUR HOME

REQUEST A QUOTE

FIND A DISTRIBUTOR

FIND A DISTRIBUTOR

Color

Painted Finishes


White


Almond


Desert Tan


Sandstone


Brown


Terra Bronze


Forest Geen


Gray


Black

Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7



Standard Balconies


We fabricate our standard alumiLAST® balconies using aluminum tube construction. We can combine these balconies with our aluminum decking or composite decking. These balconies feature welded aluminum railing supports with a variety of panels, and we deliver it to your site with the decking already installed and the railing and panels or pickets cut to fit and ready for easy installation.

These all-aluminum balconies usually attach to the building with lag bolts and threaded rods. However, alternative designs such as cantilevering, bolt-on or attaching with only knifeplates are possible. We match the attachment technique to meet your plan requirements.

Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7

Product Description

ENDURABLE® Building Products



alumiLAST® Decking General Information

PRODUCT DESCRIPTION

Endurable Building Products, the manufacturer of alumiLAST® deck and balcony frames, introduces alumiLAST® Decking, a line of powder coated aluminum decking. alumiLAST® decking features interlocking boards designed to be virtually watertight, and with the addition of a custom gasket, the boards can be completely watertight. Custom engineered starter strips and edge trim pieces are also available.


alumiLAST® DECKING FEATURES AND BENEFITS

Non-slip textured powder coat finish.

- Light weight. Boards weigh approximately 1 pound per foot.
- Low maintenance. Boards will not crack or split.
- Non-combustible. Aluminum will not burn.
- Five standard colors: Bronze, Black, Light Gray,Storm Gray & Wheat *(Custom colors also available)*.
- Limited Lifetime Warranty.
- 5 year powder coat finish warranty.

DECKING STANDARD COLORS





6500 Shingle Creek Parkway • Brooklyn Center, MN 55430

800.933.2060 www.endurable.com

Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7

PROGRESS LIGHTING™

Project:

Fixture Type:

Location:

Contact:

Z-1080 LED

Wall Mounted Vertical Only • Wet Location Listed PROGRESS LED

Description:

Transform the mundane everyday with the sophisticated styling of this LED outdoor sconce. A smooth, elongated frame with a black finish dominates the design and exudes a modern attitude perfect for indoor or outdoor spaces. A beautiful, acrylic shade stretches into a rectangular form, held in place by simple metal bars at each end for a picture-perfect finish. Vertical mount only.

Specifications:

- White acrylic Diffuser
- A beautiful, acrylic shade stretches into a rectangular form, held in place by simple metal bars at each end for a picture-perfect finish.
- A smooth, elongated frame with a black finish dominates the design and exudes a modern attitude perfect for indoor or outdoor spaces.
- Transform the mundane everyday with the sophisticated styling of this LED outdoor sconce.
- Ideal for any foyer, bedroom, entryway, porch, or patio.
- Perfect for transitional, modern, or contemporary settings.
- Measures 5-inch width by 13-inch height.
- Uses one integrated LED (11w max).
- Compatible with many Triac/ELV dimmers (see dimming controls)
- Includes installation instructions and mounting hardware.
- Progress Lighting products are designed for exceptional quality, reliability, and functionality.
- Dimmable to 10% brightness (See Dimming Notes)
- Canopy covers a standard 4" recessed outlet box: 4.75 in W., 12.5 in ht., 1.875 in depth
- Mounting backplate for outlet box included
- 6 in of wire supplied
- Americans With Disabilities Act (ADA) compliant

Performance:

Number of Modules	1
Input Power	11 W
Input Voltage	120 V
Input Frequency	60 Hz
Lumens/LPW (Delivered)	415/37 (LM-79)
CCT	3000 K
CRI	90 CRI
Life (hours)	54000 (L70/TM-21)
EMI/RFI	FCC Title 47, Part 15, Class B
Warranty	5-year Limited Warranty
Labels	cCSAus Wet Location Listed
	ENERGY STAR® qualified
	Meets California Title 24 JA8-2016

P560210-031-30


A.



Dimensions:

Width: 5 in
Height: 13 in
Depth: 3 in
H/CTR: 6-1/2 in

White acrylic Diffuser
Width: 4-1/8 in
Height: 12-1/8 in



Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7

PROGRESS LIGHTING™

Z-1080 LED

Wall Mounted Vertical Only • Wet Location Listed PROGRESS LED ENERGY STAR

P560210-031-30

Dimming Notes:

P560210-031-30 is designed to be compatible with many Triac/ELV controls.

The following is a partial list of known compatible dimmer controls.

Dimming Controls:

Leviton IPI06-1LZ
Leviton 6674
Lutron NTEVL-300
Lutron DVELV-300P
Lutron AYCL-153P

Dimming capabilities will vary depending on the dimmer control, load, and circuit installation.
Always refer to dimmer manufacturer instructions or a controls specialist for specific requirements.
Dimmer control brand names where identified above are trade names or registered trademarks of each respective company.

Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7

Shipping to: **Ashburn, VA**

B.

Maxim 13" Wide LED Outdoor Address Light

Model: 53610BZ | Item: bci3711150

from the Address Collection

★★★★★ (1)





$60.00

Finish: Bronze - 1091 In Stock

Bronze

Free Shipping!

Leaves the Warehouse in 1 to 2 business days - Shipping to 20147

Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7

Customers Also Viewed



Kichler 43800LED
$88.95



Maxim 53651
$78.00



Maxim 53650
$74.00

Details

Make your home safer, more secure, and welcoming by providing your guests with an illuminated address light. Create an inviting entrance and make it easier for deliveries, our LED address light is available in your choice of Black, Bronze, or White with number tiles sold separately.

Features:

- For use with Maxim address numbers (not included)
- Durable aluminum construction
- ADA and Title 24 compliant
- Dark Sky approved
- cETLus rated for wet locations
- Covered under Maxim's 5 year manufacturer warranty

Dimensions:

Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7

- Height: 7"
- Width: 12-1/2"
- Extension: 2-1/4"
- Product Weight: 1.21 lbs
- Wire Length: 6"

Electrical Specifications:

- Wattage: 3W
- Lumens: 160
- Color Temperature: 3000K
- Color Rendering Index (CRI): 80
- Average Hours: 25000

Additional Maxim Links

- View the Manufacturer Warranty
- Browse all Maxim Products
- Maxim Address Collection

Manufacturer Resources

PDF Specification Sheet

Dimensions and Measurements

Extension	2.25 in.
Height	7 in.
Nominal Height	7 in.
Nominal Width	13 in.
Product Weight	1.21 lbs.
Width	12.5 in.
Wire Length	6 in.

Included Components

Bulb Included	Yes


Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7

FIN - model: WP-LED1

Endurance Wallpack

WAC LIGHTING
Responsible Lighting®





ENERGY STAR · DLC QPL LISTED · IP66, WET

Fixture Type: AREA LIGHT C.

Catalog Number:

Project:

Location:

PRODUCT DESCRIPTION

Die cast aluminum factory sealed housings with patent pending design for a water and dust proof IP66 rated outdoor luminaire

FEATURES

- Factory-Sealed LED Light Engine
- 20° Forward Throw Illumination
- Photo/Motion Sensor Compatible (Sold Separately)
- Built-in Level For Easy Adjustment
- Suitable to install in all directions
- Multi-Function Dimming: ELV (120V) or 0-10V
- 85 CRI
- 100,000 hour rated life

SPECIFICATIONS

Construction: Die-cast aluminum

Power: Integral driver in luminaire. Universal voltage input (120V-277V)


Dimming: 100% - 30% with 0 - 10V dimmer (120V - 277V)

100% - 15% with Electronic Low Voltage (ELV) dimmer (120V only)

Finish: Powder coated Bronze, Graphite, and White

Standards: Energy Star®, DLC Listed, IP66, Wet Location, ETL & cETL Listed

PHOTOMETRY



ORDER NUMBER

		Power	Comparable	Delivered Lumens 3000K	Delivered Lumens 5000K	Color Temp		Finish	
	**WP-LED119**	*19W*	*39W HID*	*1390*	*1460*	**30**	*3000K*	**BZ**	*Bronze*
	WP-LED127	*27W*	*70W HID*	*2075*	*2135*	**50**	*5000K*	**GH**	*Graphite*
	WP-LED135	*35W*	*100W HID*	*2750*	*2825*			**WT**	*White*

[ ] – [ ] – [ ]

Example: **WP-LED119-50-BZ**

ACCESSORIES



Motion Sensor (120V)

MS-120-BZ	*Bronze*
MS-120-GY	*Gray*
MS-120-WT	*White*



Photo Sensor (120V)

PC-120-BZ	*Bronze*
PC-120-GY	*Gray*
PC-120-WT	*White*

WAC Lighting
www.waclighting.com
Phone (800) 526.2588 • Fax (800) 526.2585

Headquarters/Eastern Distribution Center
44 Harbor Park Drive • Port Washington, NY 11050
Phone (516) 515.5000 • Fax (516) 515.5050

Western Distribution Center
1750 Archibald Avenue • Ontario, CA 91760
Phone (800) 526.2588 • Fax (800) 526.2585

WAC Lighting retains the right to modify the design of our products at any time as part of the company's continuous improvement program. DEC 2014


Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7

D.

www.chikousa.com

PREMIER STEEL 4-CAR CARPORT/GAZEBO

The ChikoUSA Premier Steel 4-Car Carport / Gazebo is the most cost effective solar canopy solution in the market today! This elegant structure is designed with a beam and column configuration resulting in superior strength. Ease and speed of install are two important design benefits. This structure can accommodate a variety of panel sizes and configurations. The steel coating of Zinc-Aluminum-Magnesium (Zn-Al-Mg) or ZAM provides the best In class protection while delivering superior corrosion resistance.



Black



Silver



Side Profile

PRODUCT LINE

Item	Product Name
CK-QLCP-STEEL	Premier Steel 4-Car Carport/Gazebo

TECHNICAL DATA

Main Material	: S350 Steel Zinc Aluminum Magnesium (Zn-Al-Mg) Coated
Wind Velocity	: Up to 115MPH
Snow Load	: Up to 15 PSF
Tilt angle	: 5 Degrees
Module Orientation	: Landscape & Portrait
Foundation	: 3 Footer Options
Waterproof	: Optional
Module Type	: 60, 72 Cell & Large Format

ADVANTAGES

- Beautiful
- Easy installation
- Zinc Aluminum Magnesium (Zn-Al-Mg) Coated
- Anti-corrosion and anti-rust

FOOTER OPTIONS

Pier
Pad
Spread

WARRANTY




COMPONENT LIST

Material	QTY
Column	04
M-Rail	07
C-Channel	06
Column Base	04

UL 2703

ETL LISTED US
Intertek
Conforms to UL STD NO.2703

C PTL US
CERTIFIED



Overhead

Final Design can vary depending on Module Size, Orientation, Wind & Snow Load, and Seismic Requirements

www.chikousa.com
101 East Baseline Road Buckeye, AZ 85326
Tel : 1-800-948-5390
Email : info@chikousa.com

Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7

6. WINDOWS / DOORS

See Brochures / Cut Sheets Section for details information

Docusign Envelope ID: 5EE53A51-43E8-87AD-803E-798DFDB5CFB7

7. SITE IMPROVEMENTS

See Detailed Scope Of Work Section for the Architectural Site Plan